

AD-ELENA Performance in 2021 and plans for 2022

L. Ponce on behalf of the AD/ELENA team


➤ Outline:

- AD-ELENA start-up and performance
- Machines issues
- Run statistics
- Outlook for 2022



Special thanks to Davide and Christian


- Main objectives of AD and ELENA restart after LS2:
 - **Re-establish nominal 2018 performance for AD**
 - **Start physics production with ELENA**

- Summary of a long list of LS2 interventions:
 - AD target zone renovation:
 - New target system
 - Permanent quadrupoles replacing pulsed one
 - Mix of new and old PC controls system
 - AD ring:
 - Magnet refurbishment
 - New RF cavity, new LLRF
 - New synthetic B-train
 - Stochastic cooling completely dismantled and reassembled
 - Decabling campaign
 - ELENA:
 - ALL AD users connection to newly installed electrostatic transfer lines
 - 4 bunches distribution to 4 different users



- Problems found too late during HW commissioning to be fixed:
 - Restart in “degraded” mode after a Long Shutdown
 - In AD:
 - Short circuit in one module of the injection kicker:
 - No time to fix it without significant impact on planning
 - **Operating with only 5 out of 6 tanks** with nominal kick strength but no margin in case of trip (which did not happen!)
 - Couple of stochastic cooling amplifiers not operational
 - Same operating conditions as in 2018
 - **Repair done only last week of run**
 - New e-cooler collector not ready for installation in 2021:
 - gun performance OK for restart (No venting the sector)
 - **Restart with same e-cooler as in 2018**
 - In ELENA:
 - BTV screen in LNI not operational
 - Decided not to open vacuum in the kicker region because of known internal leak in kicker tank
 - Functionality replaced the grids in injection line
- => change of the BTV planned for this YETS**






- Challenging plans for restart of complex during main vacation period:
 - Mainly AD target area re-installation affected by the COVID19 delays
- Foreseen schedule:
 - 2 weeks for target area:
 - FTA optics checks, target conditioning, DI optimizations
 - 4 weeks for AD:
 - 1 week for stochastic cooling
 - 2 weeks for all RF systems
 - 1 week for e-cooler, instrumentation, cycle optimization
 - 3 weeks for ELENA:
 - Injection and cycle optimization, e-cooler
 - transfer line commissioning with pbars


- Beam delivered on time from the PS to start AD target commissioning:
 - FTA optics checks, new target conditioning, first injection line optimization
 - Pulse shape problem on the new FGC_62 power supply
 - ⇒ **Beam on target 25th June as planned, but some activities postponed**
- First injection in AD also on time, low intensity:
 - Bunch rotation setting-up, stochastic cooling at 3.5 GeV, deceleration...
 - ⇒ **Beam in AD 5th of July as planned, but...**
- Problem to get nominal performance of stochastic cooling at 2 GeV:
 - 1 week lost to recover performance
- Problem of beam loss at arrival of 100 MeV plateau:
 - 1 week lost to identify a wrong setting on current limit of the main quad
- Beam sent to ELENA with more than 2 weeks delay
 - Commissioning of ELENA with pbars in a couple of days
- Physics delivered on time 23rd of August to the users, thanks to:
 - Very efficient setting-up of bunch rotation, deceleration, working points and e-cooler
 - Getting AD in good shape took one extra month during physics run (profiting of 1 day for MD per week and time without any users request)
 - **Good preparation of the ELENA cycle and transfer lines with Hminus**

- Similar or better deceleration efficiency (~87%) than 2018
 - As well as better AD reliability (less shots with beam on target that had zero AD ej. Intensity)



CPS 1552.5	BCT9012 1469.3271	BCT9053 1368.575	3.5 GeV/c S 3.32E7 100%	3.5 GeV/c E 3.15E7 94%	2 GeV/c S 3.14E7 94%
2 GeV/c E 3.15E7 94%	300 MeV/c S 3.12E7 93%	300 MeV/c E 3.10E7 93%	100 MeV/c S 2.92E7 87%	100 MeV/c E 2.86E7 86%	BCT7049 2.95E7
PBAR for ELENA					
Comments (11-Nov-2021 12:02:00)					
Day time: ACR 76688/76689 Nights and w.e. CCC 76677					





- Typical AD cycle end of 2021 about 5 s longer than in 2018:
 - Using h=1 for the whole cycle (h=3 for 300 → 100 MeV/c ramp pre-LS2)
 - Using bunched-beam cooling before extraction (was bunch rotation pre-LS2)
- Most losses still during injection plateau and on 300 → 100 MeV/c deceleration



- ELENA deceleration efficiency ~ 80%, higher than design (60%):
 - Excellent reliability : what is injected is almost always decelerated
(Data over week 44 a reasonably quiet week at the end of the run)
- **New mode of operation:** each user can place a request at any time
 - Up to 4 experiments can take one bunch each at each cycle
 - if request is placed, bunch is extracted whatever is the situation of the experimental zone
 - If more than 4 requests, one may need to wait 2 cycles





- Present target (+AD injection) yield below 2018:
 - Higher proton losses in FTA than in 2018 → more investigation required
 - Too little time to optimize and need improved instrumentation



- Lower produced intensity than 2018:


Higher proton intensity asked to PS end of 2018




Typical delivered pbar intensity






- ELENA delivered bunch intensities well above design value despite lower intensity from AD than 2018:
 - Uncertainty (say 10-15%) on calibration/signal treatment of instruments
 - SEM are semi-interceptive device (about 10 % beam loss per monitor)



- Max pbar intensity over 1 hour periods since 1st of August








- Energy spread and bunch length typically within or better than design
 - Bunch length could be further reduced to 90 ns FWHM at expense of energy spread
- Typical emittances of 2 μm rms are about factor 2 worst than design, but factor ~ 2 better than 2018 estimate:


=> Overall reached close to nominal beam characteristics:

We might profit from further inputs from experiments to understand what to improve first



- Earlier worries about **profile monitor availability** and **data quality** were efficiently addressed before pbar arrival:
 - **Extensive studies** by ABT using **H⁺ beams only**
 - **Basically no need re-matching/ corrections with respect to design optics!** (change for ASACUSA optics on their request)
 - Only **minor steering** of the full line **with pbars** during the run
 - **Calibrated knob (mm and mrad) available fo steering at hand-over point**
- **High level parameters** (quadrupole and correctors strength) implemented in the transfer lines:
 - Allow steering with CERN-wide tools in 2 cycles

- As « expected » **AEgIS solenoid** does **perturb orbit** in nearby transfer lines (mainly to ALPHA, but also ASACUSA)
 - Profile monitors not inserted in ASACUSA line during magnet ramp-up, need to check the effect





- **Found steering settings** for « solenoid ON » and « solenoid OFF »
 - Reaching some correctors current limit, so needed to re-work the trajectory
 - Reference trajectory and settings in both configuration, easy to reload
 - Still beam not coming back exactly at the same position, so **fine tuning might be needed**
 - Need AEgIS magnet status flag to load corresponding settings

- Wrong minimum current limit set by mistake on the Main quadrupole:
 - 1 week lost on investigating beam loss at the arrival of 100 MeV/c plateau
 - Gained a good control of the working point!
 - Lack of diagnostics on the old power converter type


- New DI.QDE6020 power converter allowing lower pulse rate broke after couple of days of operation:
 - No spare parts to repair so switch back to spare
 - But spare Pow1553 PC not operational: **2 days of beam commissioning lost**
 - New system not back operational at the end of the run: not a problem till water leak...

- Current shape of the AD ejection septum inducing shot to shot orbit jitter in LNI:
 - Suspect issue of interference in cable tray between rise edge of the septum and orbit correctors
 - **Known (but forgotten!) problem since 2014**, fixed by adjusting the ramp rate




- AD Target BTV oxydation:
 - Rapid degradation of the BTV surface
 - Old BTV used to have a hole
 - Proposal to test different type at 2022 restart

After few days







- AD magnetic horn:
 - Problem with PLC to be resetted (expert action)
 - No piquet, only best effort intervention
- Water leak on quadrupole DI.QDE6020 few days before end of run:





- No time to exchange magnet so tried to run without water or without quadrupole
- 1/3 of intensity injected without the magnet (no time to optimize)
- Could not try to operate the quad without cooling because FGC_62 not available

=> Feasibility study of operating DI magnets without cooling to be considered?

- Cryo pump in AD:
 - Period of strong outgazing in the C10 – Stochastic cooling pick-up region inducing e-cooler or stochastic cooling performance degradation
 - Beam lost on the first deceleration (few shots) or only partially extracted
 - Found a “pre-warning” on SC temp sensor but solution was to try adjusting e-cooler energy during the storm
 - Problem fixed during the maintenance planned during YETS




- orbit system:
 - Wrong gain initially set (summer period!) in AD
 - Not stable reading when change of harmonic in the cycle in both machines:
 - **change of operational mode in AD**, not possible in **ELENA** so **no reliable orbit reading in ELENA** for the rest of the run




- Problem with the data of the scraper (interfaces between different groups):
 - No reliable emittance measurement, vertical measurement not available for several weeks during summer period
 - **Complex integration of the timings, RT tasks of different equipment (motor and scintillator)**
 - Very lengthy (and destructive) to debug started after summer period

- Good progress since in end of 2020 with more reliable H⁻ source operation
 - Still limited by source **intensity stability**, being **hopefully addressed during YETS**
- H⁻ have been instrumental for the learning and setup of:
 - **Magnetic cycle and LLRF control**
 - Cycle editor and general **control** issues **debugging**
 - **LLRF experience** efficiently reused in AD!
 - Investigations on measured b-train reliability
 - **Finally operated in 2021 without measured b-train: to be further investigated**
 - **E-cooling**
 - **Demonstrated that we can cool H⁻**, and therefore **setup e-cooling** with those.
 - **Tune and orbit measurement and correction**
 - **Solved most transmission losses** observed in 2018 (**quantification/studies to be continued!**)
 - **Instrumentation testing** (tune meters, orbit system, Schottky, scraper)
 - ELENA extraction **transfer lines commissioning**:
 - **More than 100 power supplies** to check and control
 - **Orchestration of timing** for beam delivery to up to 4 experiments at the same time
 - **SEM characterization**
 - Found **several wires in several not working**, but overall **quality sufficient for commissioning and operation**

- Very good availability for both machine (close to 2017 for AD, 2018 was a bad year!)
 - Note: need to consolidate the faults capture:
 - Faults not automatically registered, double counting of injectors faults...



Draft injector schedule for 2022



Experimental facility	Start Physics	End Physics	Duration 2022 [days]*	Duration 2018 [days]*
ISOLDE	28.03.2022	28.11.2022	245	217
nTOF	28.03.2022	28.11.2022	245	224
PS East Area	28.03.2022	28.11.2022	245	224
SPS North Area p ⁺	25.04.2022	14.11.2022	203	217
ELENA (AD)	28.04.2022	12.12.2022	228	196
SPS North area Pb ions	14.11.2022	12.12.2022	28	28
AWAKE	02.05.2022	12.12.2022	105	91
HiRadMat	16.05.2022	31.10.2022	35	25

- Key dates for 2022 pbars operation:
 - First beam on AD target on 28th of March
 - Start of physics on 28th of April
 - Commissioning during Easter period
 - End of pbar operation 12th of December
 - 228 days for physics run (MD not inc.)

- Restart of Hminus source operation mid February:
 - After BTV in LNI exchange
 - Mainly for ELENA cycle setting-up and new line commissioning
 - Could be delivered to users if beam permit signed

- Recover AD ejected intensities pre-LS2
 - Improve transport to in transfer lines (FTA, DI and AD to ELENA)
 - Time consuming activity
 - Optimize target production
 - Need improved instrumentation

- Reduce transverse emittances in ELENA transfer lines to deliver nominal parameters
 - Need users input to define optimum between transverse and longitudinal
 - Optimization on e-cooling, study of intensity dependence

- Improve repetition rate:
 - Reduce AD cycle length
 - Work on both cooling
 - Study ramp rate reduction
 - Work on cycle structure definition
 - Better adapt to PS supercycle

=> OP team will request again 1 day per week for Machine developement

- **AD and ELENA** have been **successfully** (re-)commissioned during summer period
 - **New era for antimatter physics**: 100 keV pbar beams delivered to all experiments

- **Beam characteristics very close to design values**:
 - Easy to get **shorter bunches** than design, but **emittances still a factor 2 bigger than nominal**
 - **Higher intensities than design** in ELENA despite lower intensities than 2018 in AD
 - Some margin to gain in the future? (but emittance...)

- **Extremely usefull run** for both **operation and users** to learn about advantages and pitfall of the new AD+ELENA combo:
 - Experience gained on operation with **4 bunches available** on demand **at any time** to any experiments:
 - But if **more than 4 users**, then **additional waiting time** for some users
 - **Beam request server could/should be further optimized** to allow « last second » change of destination (e.g. one user cannot suddenly take beam)
 - Pretty **good orbit stability** of beam delivery in transfer lines
 - Still **strong impact of experiment magnetic fields** when swicthing **on/off**
 - We can **compensate** for it but we **need to know the status of the magnets!**
 - **H-source operation very usefull** for **ELENA** and transfer line set-up, but also for **experiment** setup/optimization (higher repetition rate)

We are ready for a long exiting physics production run

Summary Key Performance Indicators



	Target (IPP #40)	Achieved 2021	How to measure
p at PS extraction	n.a.	1.5e13	
Requested p on target (compatible with Nov 2018)	(1.3e13)	1.3e13 - 1.4e13	BCT before target
p beam-size/orbit stability on target	??	1.5 mm rms	BTV before target?
p bunch length on target (4σ)	n.a.	28 ns?	To be checked
AD target → injection efficiency	2.75×10^{-6}	2.5×10^{-6}	Target BCT + Schottky on inj plateau or CCC ?
AD deceleration efficiency	85%	85%	Schottky on inj plateau or CCC ?
AD extracted pbars	3e7	2.9e7	BCT on DE line
AD cycle length	110 s	115s	FGCs...
AD uptime/for physics	90%/84%	???	BCT after extraction(?)
ELENA injection efficiency	95%?	???	BCT in the ELENA ring? BPM? LLRF?
ELENA deceleration efficiency	60%	90%	BCT in the ELENA ring? BPM? LLRF?
ELENA extracted pbars	4x 4.3e6	4x ~7e6	BCTs in transfer lines
ELENA uptime/for physics	95%?/90%?	???	BCTs in transfer lines(?)
AD+ELENA for physics	84%*90%=76%?	???	BCTs in transfer lines(?)
Cycles/day for physics	n.a.	???	BCTs in transfer lines(?)
Geometric emittance ϵ_{rms}	<4 mm mrad H/V ?	2 mm mrad	A few SEM in from time to time? Always?
Orbit stability at experiment	<< 1 mm?	???	A few SEM in from time to time? Always?
Bunch length σ_{rms}	75 ns?	<65 ns	BCTs in transfer lines? BPM in the ring?
Momentum spread δ_{rms}	0.7e-3?	0.5e-3	Tomoscope in the ring from to time?

Courtesy D.Gamba