





**THE OHIO STATE
UNIVERSITY**

Millicharged Particle Detectors

Michael Carrigan for milliQan
- with slides contributed by MoEDAL-MAPP

May 17, 2022 – LHCP 2022


- The LHC is aiming to collect $\sim 300\text{fb}^{-1}$ of data in run 3
- Other experiments can take advantage of this increased luminosity!



- milliQan and MoEDAL are two experiments located around the LHC far from the IPs
- These detectors take advantage of the collision products and their distance from the IP (shielding from rock) to search for millicharged particles

What is a Millicharged Particle?

- Millicharged particles (mCP) are theorized particles that have fractional electron charge
- Particles would come from a “dark QED” field A'
- This field mixes with hypercharge creating the millicharged particle ψ with mass M_{mCP}
- Redefining $A'_\mu \rightarrow A'_\mu + \kappa B_\mu$ results in a coupling between ψ and hypercharge $\kappa e'$
- And a coupling to the photon gives a charge $\epsilon = \kappa e' \cos\theta_w / e$



$$\mathcal{L} = \mathcal{L}_{SM} - \underbrace{\frac{1}{4} A'_{\nu\mu} A'^{\mu\nu}}_{\text{Dark Photon Term}} + \underbrace{i\bar{\psi}(\not{\partial} + ie' A' + iM_{mCP})\psi}_{\text{Dark Fermion}} - \underbrace{\frac{\kappa}{2} A'_{\mu\nu} B^{\mu\nu}}_{\text{Kinetic Mixing Term}}$$


Dark Photon Term

Dark Fermion

Kinetic Mixing Term



$$\mathcal{L} = \mathcal{L}_{SM} - \frac{1}{4} A'_{\nu\mu} A'^{\mu\nu} + i\bar{\psi}(\not{\partial} + ie' A' + -i\kappa e' B + iM_{mCP})\psi$$





- Limits on charge and mass of millicharged particles set by numerous experiments
- Large gap for masses $O(10^{-1}-10^2)\text{GeV}$
- Some limits set by:
 - Cosmic microwave background and CMB N_{eff}
 - SLAC MilliQ experiment (similar to milliQan and MAPP)
 - CMS searches for fractional charges
- This gap is targeted by both milliQan and MoEDAL-MAPP



**THE OHIO STATE
UNIVERSITY**



milliQan

- Detector in PX56 drainage gallery at P5 (above CMS)
- 33m from CMS IP at an angle $\eta \approx 0.1$
- 17m of rock act as natural shielding against bkgd



drainage gallery



- Millicharged particle parameterized by mass and charge of particle
- Previous experiments unable to probe this area
- milliQan detector aims to probe undetected phase space
 - $10^{-1} \text{ GeV} < M_{mCP} < 10^2 \text{ GeV}$
 - $10^{-3} < \frac{Q}{e} < 10$
- In Spring of 2021 published paper with run 3 design and updated sensitivity
- Exclusion limits for bar and slab detector from this paper are shown ([Phys. Rev. D 104, 032002](https://arxiv.org/abs/1511.01122v2))





- 4 layers each composed of 16 (5x5x60cm) bars
- Scintillator panels on front and back, top and sides for background veto
- Many improvements from demonstrator:
 - Special PMT amplifiers to efficiently reconstruct single photoelectrons
 - LED flasher system for calibration of sPEs
 - Etc...

Lever arm allows for easy construction and alignment of detector


Main structure reused from demonstrator



- Run 3 detector also includes a separate slab detector comprised of four layers of 12 scintillator slabs (40cm x 60cm x 5cm each)
- Larger area increases signal acceptance at higher masses ($M_{mCP} \gtrsim 1.4 GeV$)
- 4 PMTs per slab to increase collection efficiency



- Scintillator wrapped and tested at UCSB, U. Chicago, NYU, and University of Nebraska
- Bar and slab detectors currently being built at CERN




- Custom PMT amplifier bases are designed and built at UCSB
- Everything now shipping to CERN

- To prepare for installation of the run 3 bar detector we are now decommissioning the demonstrator
- Old equipment is being brought to surface



- Lab in the CMS assembly hall is used to test and calibrate our electronics, scintillators, PMTs, etc...






MoEDAL-MAPP


MoEDAL's Apparatus for detecting Penetrating Particles

MAPP Detector Location




- MAPP detector will be in UA83
- ~100m away from MoEDAL (near LHCb)

- Slightly different location from the prototype




- As of Feb 25, 2022 the MAPP detector has installed:
 - Support frame for scintillator bars
 - Fraction of the scintillator bars
 - Power connection
 - Ethernet connection
 - Fiber optic cable with LHC clock signal






- MAPP outrigger designed to improve acceptance of mCPs at higher fractional charges
- Scintillator “blocks” with size 50cm x 60cm x 5cm attached to PMTs


- Coincidence of 4 hits defines a mCP track
- Outrigger detector area is 4.8 m² – between ~ 1.5 & 6.5 deg. and 105m from the IP
- Plans to install after the MAPP Run3 detector



Millicharged particle detection



Neutral LLP Detection




*Charged LLP Detection
(In conjunction with MoEDAL)*


- MAPP detector will look for:
 - Millicharged particles
 - Neutral LLPs
 - Charged LLPs
- MAPP will monitor MoEDAL trapping detector
- Trapping detector exposed for 1y then moved below MAPP
- Sensitive to particles with lifetimes $O(10y)$

milliQan and MAPP plan to significantly improve current limits with Run3 data!

MoEDAL-MAPP Dark Higgs Long Lived Particle



milliQan Millicharged Particle







**THE OHIO STATE
UNIVERSITY**

Backup

Slab Detector Mechanics


- Slab detector is being built in parallel with bar detector






- Demonstrator was a 1% detector to test overall design
- 3 layers of a 3x2 array of scintillator bars attached to PMTs
- Scintillator “slabs” and lead plates between layers to help define pointing path and stop beam muons
- Scintillator panels surrounding bars to help veto cosmics
- Hodoscope in front and back to help with pointing path and timing



- Signal mCPs are simulated through many different processes and propagated through CMS B-field and the 17m of rock



- The detector is then modeled using Geant4 and validated using data from the demonstrator



- Data was collected during beam off using run 2 demonstrator aligned horizontally to allow addition of two bars to simulate run 3 bar detector
- This data was then compared with simulation of cosmic muons to validate simulation




- One of the two main background for the experiment is the shower background from cosmic muons
- The below is the bar detector signal selection and the estimated bar detector background after each cut

| Selection | Run 3 200 fb^{-1} | HL-LHC 3000 fb^{-1} | |
|--|-----------------------------|-------------------------------|--|
| ≥ 1 per layer | 8.1×10^5 | 8.2×10^7 | mCPs must have one hit per layer and no more |
| $= 1$ per layer | 6.0×10^3 | 1.1×10^4 | |
| Cosmic panel veto | 1.1×10^3 | 3.1×10^3 | Cosmics coming from above/sides and beam muons coming from IP are vetoed |
| Beam muon panel veto | 780 | 3.0×10^3 | |
| Four in line | 0.19 | 2.9×10^{-4} | mCPs will travel straight through 4 layers |
| $\text{Max } n_{\text{pe}} / \text{Min } n_{\text{pe}} < 10$ | 0.061 | 9.1×10^{-5} | mCPs leave the same energy deposit in each layer |
| $-15 \text{ ns} < \Delta t_{\text{max}} < 15 \text{ ns}$ | 0.012 | 2.0×10^{-5} | mCP must travel in small time window |

The cuts for the slab detector follow the cuts of the bar detector with two main differences:

1. The slab detector has no veto panels
→ Only the self-veto on muons is used (max/min nPE)
2. The distance between layers is larger, and for low charge mCPs a pulse is only seen when travelling below c
→ A larger timing window is allowed
 $15ns < \Delta t_{max} < 45ns$

| Selection | Run 3 |
|---|-------------------|
| ≥ 1 per layer | 2.0×10^7 |
| $= 1$ per layer | 4.8×10^6 |
| Muon veto | 2.6×10^5 |
| Four in line | 76 |
| Max n_{pe} /Min $n_{pe} < 10$ | 23 |
| $-15 \text{ ns} < \Delta t_{max} < 15 \text{ ns}$ | 7.1 |
| $15 \text{ ns} < \Delta t_{max} < 45 \text{ ns}$ | 1.4 |



Background Estimate
Run 3 ($200fb^{-1}$)

Timing Window


$$|\Delta t_{max}| < 15ns$$

$$7.1 \pm 3.9 \text{ events}$$

$$15ns < \Delta t_{max} < 45ns$$

$$1.4 \pm 0.8 \text{ events}$$

- The PMT dark pulse rate has been measured at 2kHz during the running of the demonstrator
- The estimated run time of the detectors during run 3 is 1.5×10^7 s
- Requiring 15ns maximum time difference between pulses this gives 0.0032 events per signal-like path
- The bar detector has 16 signal-like paths, and the slab detector has 12



Run 3 Dark Pulse
Background Estimate

Bar Detector
0.05 events

Slab Detector
0.03 events ($|\Delta t_{max}| < 15ns$)
0.7 events ($15ns < \Delta t_{max} < 45ns$)

| Milliqan Timeline | 2020 | | | | | 2021 | | | | | 2022 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------------------------------|------|-----|-----|-----|-----|------|-----|-----|-----|-----|------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|--|--|--|--|--|--|--|--|
| | Jul | Aug | Sep | Oct | Nov | Dec | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | | | | | | | |
| PMT + Amplifier board | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Design | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Prototyping | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Procurement | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Assembly & testing | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Readout | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Design | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Procurement | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Testing | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Trigger | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Design | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Prototyping | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Procurement | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Commissioning | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Bar detector | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Design | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Scintillator procurement | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Prototype wrapping | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Assembly & QC | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Remote commissioning | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Installation | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Commissioning | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Operation | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Slab detector | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Design | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Scintillator procurement | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Prototype wrapping | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Assembly & QC | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Remote commissioning | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Design support structure | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Construct support structure | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Installation | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Commissioning | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Operation | █ | | | | | █ | | | | | █ | | | | | | | | | | | | | | | | | | | | | | | | | | | |

- Well underway on assembly and quality control for bar and slab detector
- On schedule for installation of both detectors at the beginning of 2022
- In time to operate at the start of run 3!