



Overview of CC60 facility activity in 2021 and outlook for 2022

Matteo Brucoli (BE-CEM-EPR)

R2E Annual Meeting – 1-2 March, 2022
<https://indico.cern.ch/event/1116677/>



Controls
Electronics &
Mechatronics

1. The CERN Co-60 Facility
2. Upgrade: a new 110 TBq Co60 source
3. Operation and Statistics

The CC60 Facility




The CERN Cobalt-60 (CC60) facility



- Located in Prévessin (bld 772), operational since 2015
- Equipped with two sources: **110 TBq ^{60}Co** (in 2019) and **10 TBq ^{60}Co** (in 2015)
- Multiple users running in parallel are allowed in the facility
- The room is 3x4.5 m²
- Dose rate from 0.1 to 450 Gy/h

The facility is used to:

- Qualify electronic components and systems
 - Can be used for screening before CHARM or PSI tests
- Material testing
- calibration of dosimeters and R&D (Floating Gate, RadFET, Optical Fiber, NMOS)



Service for the Users



EPR section runs the facility as USER facility



Services

- Planning and coordination
- Support for cables and instruments
- **Dosimetry and calibration for each DUT**
- Radiation field homogeneity evaluation for bulky DUT

Utilities

- Website* cc60facility.web.cern.ch
- Test Request webform cc60facility.web.cern.ch/Test_Request
- Web Radiation Monitoring tool cc60monit.web.cern.ch

*[thanks to V. Baldassarre]



Challenges and Users' requirements



- Satisfying the users' requests implies **parallel testing** and **24/7 availability**
 - Measurement of the exact Total Exposure Time for each user
 - Each user has to deal with the needs of one another:
 - Planned or unforeseen accesses and irradiation interruptions
 - Radiation field inhomogeneities
 - Change in the dose rate for one or more of the users' DUT


- Very High Doses (tens of kGy)
- Larger DUTs get lower dose rates

In order to deal with the many requests, the facility has been upgraded with a new high-activity ^{60}Co source

The CC60 facility upgrade



^{60}Co source installation - project overview



Phase 0

PRELIMINARY STUDY (2018)


- (1) Dose Rate Levels Assessment
- (2) Design of Infrastructure Upgrades



Phase 1

CALLS FOR TENDERS

- (1) Source Provider
- (2) Installation Support



Phase 2

INSTALLATION STRATEGY

- (1) Procedure Design
- (2) Risk Analysis
- (3) DIMR & WDP
- (4) Simulations
- (5) Testing



Phase 3

WORK PREPARATION

- (1) Source production
- (2) Infrastructure Upgrade
- (3) ALARA Level assessment




Phase 4

SOURCE INSTALLATION

- (1) Delivery
- (2) Installation

**MISSION ACCOMPLISHED
IN SEPT 2021!**

It requires the collaboration of several entities...




Challenges in infrastructure upgrade




The installation of a high-activity source requires radiation levels assessment

- Simulations* were performed to design the necessary infrastructures upgrade:
 - Minimizing the residual dose around the irradiator when the source is stored → *Annulus shielding*
 - Constraining the beam size → *Collimator*
 - Minimizing the dose outside the irradiation room during irradiation → *Additional Lead door*
 - To fulfil the Swiss and French authorities' regulations → *Anti-intrusion alarm system and electronic lock*



*[performed by A. Infantino]




Installation Strategy



Following the investigation of different procedures, we designed a strategy to minimize the risks and the dose exposure:

- Gamma Service produces the source and loads it in a small container called **rabbit**, provided by Hopewell
- The rabbit is stored in the **transfer shielding**
- The transfer shielding is stored in the **shipping container** and transported to CERN by Gamma service
- The container is open, and the transfer shield is extracted
- The transfer shield is brought next to the irradiator
- The transfer shield is lifted on top of the irradiator
- The drawer is open and the rabbit falls in the irradiator
- Once the rabbit is loaded, the irradiator can be closed and tested



Summing-up the upgrade project

- During the installation everything went smoothly
 - None of unexpected events described in the safety procedure occurred
- The dose absorbed by the operators was within the predicted limits
 - The operations were faster than expected leading to lower doses

Group/Company	Estimated Dose (μSv)	Dose (μSv)
HOPEWELL	107	22
HSE-RP	10	23
EN-HE	117	14
BE-CEM-EPR	0	1
GAMMA SERVICE	12	0



CC60 Operation Statistics

The CC60 in numbers



Operation in the last four years

- 75 tests have been performed
- ~220 effective days of irradiation per year on average
- More than 20 publications in journals




- The number of tests and users increased over time thanks to the optimization of parallel testing
- These KPIs do not reflect the performance improved yet of the facility

The CC60 in numbers


In terms of delivered dose, the impact of the new source is already

- The achievable dose rate in standard position reaches 450 Gy/h (x17 higher)
- However, small samples can be installed in the irradiator aperture, where the dose rate reaches 1 kGy/h

Standard Radiation Tests



High Dose Rate Radiation Tests





CC60 2D Dose Field Mapping (ongoing)



- A dose map of the radiation field has been performed by means of an Ionization Chamber: data interpolation allowed to get a 2d map at beam-height

Impact on scheduling and coordination

- Dose rate can be evaluated as a function of the (x,y) position
- Field homogeneity as a function of the distance can be evaluated according with the area of the user setup



- The CC60 serves many users CERN-wide (ATS and EP)
 - EPR runs the facility as USER facility
 - Support to the users in test setups
 - Coordination and planning to maximize the efficiency → parallel testing, 24/7 availability
 - Constant work on the dosimetry: DUT position calibration
- CC60 Upgrade project
 - Long planning and risk analysis lead to successful installation in Sept 2021
 - The impact on the delivered dose is already remarkable after few months of operation



Thank you for
your attention!



**Controls
Electronics &
Mechatronics**



Phase 3 and 4 – Work Preparation and Source Delivery

- Installation procedure and Risk Analysis has been approved ([EDMS link](#)) ✓
 - Partial test performed with the empty transfer shield
 - Simulations performed to assess the radiation levels during the installation
- DIMR and Work Dose Plan ✓
- ALARA Levels Assessment ✓

- Delivery of the source and installation date
 - Foreseen for Q1-2021 (dealing with Covid19 travel restrictions) ⚠