



The ATLAS ITk Strip Detector System for the Phase-II LHC Upgrade



23rd International Workshop on **Radiation Imaging Detectors** 26 – 30 June 2022 iva del Garda, Italy

Christian Scharf*, on behalf of the ATLAS ITk Strip community


The Phase II Upgrade of the ATLAS ITk Strip Tracker




The High Luminosity Large Hadron Collider (HL-LHC) upgrade will require an upgrade of the ATLAS Inner Detector system. An integrated luminosity of 4000 fb⁻¹ and about 10 times higher track density compared to Phase I requires high granularity and high radiation tolerance of the Phase II tracker.

The new ATLAS tracker will be the all-silicon Inner Tracker (ITk) that will replace the current Pixel Detectors, SCT, and TRT. ITk will be comprised of a pixel detector surrounded by a strip detector. The strip detector will consist of 4 Barrel layers and 6 disks for each End Cap with 160 m² silicon and 50 M channels.

ITk Strip tracker layout, support, integration



ITk Strip modules



- n⁺p silicon strip sensors
 - Barrel pitch 75,5 μm, End Cap mean pitch 75 μm, 320 μm thick
 - See posters #40, #46, #47 for more information on sensors


Hybrid PCBs glued onto the sensors populated with

Production status & QA/QC

- ABCStar: Radiation-hard 130 nm front-end chips with 256 binary strip read-out channels
- HCCStar: Hybrid Controller Chip collects data from ABCStar chips and communicates with EoS

Powerboard glued onto sensor with

- AMACStar power control and monitoring chip
- High voltage filter and switch
- Low voltage DCDC converter



- Industrial-scale production of the ITk strip detector is shared across many institutes and companies on 4 continents.
- Production sites have built up their infrastructure in recent years and are undergoing site qualification steps. Currently, the pre-production phase is ongoing, during which production sites have to demonstrate they can build parts which pass all QA/QC tests.
- Production will run from 2023 2027 after which ITk will be installed into the ATLAS detector at CERN.


QA/QC for module building				
Sensors	HV tabs	Powerboards	Hybrids	Testframes
- Visual inspection - IV curve	- Visual inspection - Bond-pull tests	 Visual inspection Electrical tests 	(Assembled) - Visual inspection	- Reception tests
- Bond-pull tests		- Bond-pull tests	- Electrical tests - Bond-pull tests	

Lab infrastructure

Lab infrastructure:


- Clean rooms with dry storage
- Pick&place & glue dispensing robots
- Wirebonder/bond pulling machines
- Metrology setups
- Production street with custom tools, vacuum etc. services
- And much more


Stave and petal loading, systems tests



Automated pick & place and glue robot to mount modules to petals










- Extensive QA tests for all components before and after mounting on module After module assembly thermal cycling QA
 - step: -35°C to +40°C for

10 cycles







- Electrical and cooling tests of fully populated staves/petals
- Systems test setups for staves/petals loaded onto global structure