

---

# Beam Dump Synchronization

Not a proposition... Just the current  
status of our thinking

Etienne CARLIER (SL/BT)

01/02/2002

# The problem

---

How to guarantee permanently a correct **phase** between the extraction kicker rising edge and the particle free gap ?


- Dump requests are issued spontaneously
  - The dump requests must thus be synchronised such that the requests and the gap coincide at the dump kicker magnets
    - The revolution frequency pulse train with a fixed relative phase offset to the particle free gap must be used for this
- The tolerance for the synchronisation is small (100ns)
  - Any delay or jitter in the transmission of the revolution frequency has severe consequences for the synchronisation of the extraction process (beam loss all around the LHC)
  - The absence of beam in the kicker magnets must be verified at the moment of each revolution frequency pulse (with phase offset)
    - What has to be done if a phase error is detected?
    - What has to be done if the expected particle free gap is filled with beam?

# Definition...

---

- Revolution frequency
  - 11,2 kHz frequency synchronous with the circulating beam
- Particle free gap
  - 3 $\mu$ s long (119 bunches) circulating beam particle free gap dedicated for the extraction kicker rising edge
- Beam abort frequency
  - Frequency in phase with the beginning of the particle free gap at the injection and extraction first magnet input. Re-phased revolution frequency.


# Synchronization



- ① Synchronizes the rise of the magnetic field of the extraction kicker magnets with the particle free gap
- ② Continues operation if the beam revolution frequency signal is failing


# SPS Beam Dump

---



- Emergency dump requests are not synchronized with particle free gap (Request → Dump)
- Scheduled dump requests are synchronized with particle free gap through the SPS revolution frequency (43kHz clock)
- Cable and turn-on delays are compensated inside the timing system (20MHz clock)

# LEP Beam Dump




- Emergency and scheduled dump requests are synchronized with particle free gap
- Synchronization mechanism: gating-on of the LEP Beam Synchronous timing signal.
- Cable and turn-on delays are compensated through hardware passive delay lines (cable)

# LHC Beam Dump

Three functional levels :

- Three dump request sources
  - Machine protection system, Access system, beam dump system itself (kickers, septa...)
- Synchronization
  - Synchronize extraction kicker rising edge in phase with particle free gap
- Trigger distribution
  - Fan-out and distribute trigger request to the power trigger units
  - Match cable, electronic and turn-on delays with time of flight of the beam



# MKD Triggering Architecture

---

Title:  
J:\DESK\_TOP\PACK97\PACK97\8P007F1.EPS  
Creator:  
Micrografx Graphics Engine  
Preview :  
This EPS picture was not saved  
with a preview included in it.  
Comment:  
This EPS picture will print to a  
PostScript printer, but not to  
other types of printers.



# Possible Errors

---


- Bad phase relation between particle free gap and revolution frequency (**Type 1**)
  - Particle free gap is not correctly placed with respect to the revolution frequency
  - Offset in the revolution frequency
  - Modification of filling procedure
  - ....
- Particle free gap is filled with a wrong injection (**Type 2**)
  - First injection
  - Last injection
  - Any injection

# Operation Modes

---


- Operation modes
  - Filling
  - Acceleration, Physics
- Major possible errors occur during filling
  - Synchronization has to be **performed** / **checked** / **locked** during this period
- Once acceleration has started, synchronization has to be **kept** and **controlled**
- All RF frequencies will be re-synchronized before the start of the filling.
  - Initial conditions are, a priori, well known and stable

# Injection Error – Case 1




**Injection first batch: Type 1 error**

# Injection Error – Case 2




Injection first batch: Type 1 & Type 2 errors

# Injection Error – Case 3



**Injection last batch: Type 2 error**

# Injection Error – Case 4



Injection first batch n: Type 2 error

# Operation Mode (cont.)

---

## Filling

1. Filling particle free gap with the first injection
  - ◆ Can it be avoided by gating-off injection kicker ? →
  - ◆ Pilot beam (see “scenario II”) can be used to check the correct synchronization before injecting an intense batch
2. Filling the particle free gap with a wrong 4 batches injection
  - ◆ Still place to re-phase the beam about frequency
  - ◆ Beam can not be dumped with injection kicker (falling edge)
  - ◆ Re-phase beam about frequency with another empty gap ???
3. Filling of the particle free gap with the last injection
  - ◆ Very bad situation: particle free gap will be filled & first circulating batch will be touched
  - ◆ Beam has to be dumped with un-correct synchronization

# Beam Injection Inhibition at kicker level

---

- Injection kicker (MKI)
  - Adjustable kick length: up to 7.8us
  - Falling edge: 2.8us
  - No clipper switch... It is not possible to stop rapidly ( $\sim 100\text{ns}$ ) the injection kick
- Injection is triggered by the injection prepulse received from the LHC-RF
- Prepulse is bind to the SPS/LHC common frequency but the final position in the LHC depends of the selected SPS extraction turn




# Beam Injection Inhibition at kicker level

---


- Authorization to inject can be gated-off → injection prepulse inhibition
- Due to the 3.3.4... injection pattern different inhibition durations exist
- Inhibition durations
  - 3 batches injection: 5.8us before and 2.8us after beam abort frequency → **8.6us**
  - 4 batches injection: 7.8us before and 2.8us after beam abort frequency → **10.6us**
- Injection inhibition can be set to 10.6us (4 batches injection) up to the last injection where it has to be reduced to 8.6us
  - LHC injection inhibition is SPS elementary cycle dependent

# Injection Inhibition – Case 1




**Injection first batch**, prepulse correctly synchronized  $\rightarrow$  beam correctly injected

# Injection Inhibition – Case 2




**Injection first batch**, prepulse not correctly synchronized (inside inhibit windows)  
→ injection inhibited and beam on TDI

# Injection Inhibition – Case 3




**Injection third batch**, prepulse not-correctly synchronized w.r.t filling pattern but outside the inhibition windows  $\rightarrow$  beam injected at the wrong position, but particle free gap is still available

# Injection Inhibition – Case 4




**Injection third batch**, prepulse not-correctly synchronized w.r.t filling pattern but inside the inhibition windows  $\rightarrow$  injection inhibited and beam on TDI

# Injection Inhibition – Case 5



**Injection last batch**, prepulse correctly synchronized w.r.t filling pattern, injection inhibition windows reduced to 8.6 $\mu\text{s}$  and injection kick length reduced to 6 $\mu\text{s}$   $\rightarrow$  beam injected and availability of particle free gap is kept

# Injection Inhibition – Case 6



**Injection last batch**, prepulse correctly synchronized w.r.t filling pattern, injection inhibition windows reduced to 8.6 $\mu\text{s}$  but, injection kick length maintained at 7.8 $\mu\text{s}$  and 4 batches beam  $\rightarrow$  beam injected, no particle free gap anymore, beam losses

# Operation Mode (cont.)


## Acceleration

## Physics

1. Beam abort frequency is locked with the correct phase w.r.t the beam before start of acceleration
2. Synchronization between frequencies (beam abort and revolution) is maintained & guaranteed through a digital PLL redundant logic system →
  - ◆ Revolution frequency is continuously measured
  - ◆ Generation of the beam abort frequency signal is guaranteed if the revolution frequency is failing
  - ◆ Any loss or jump of the revolution frequency will issue a synchronous dump request.
3. Any deviation of the beam abort frequency with respect of the particle free gap will be detected and a synchronous dump request will be issued



# Synchronization



# Status - Signals availability

---

- Revolution frequency
  - Direct connections requested between LHC-RF Point 4 & LHC-Beam dump Point 6
  - No request for a direct connection to injection kicker in LHC Point 2 and LHC Point 8 has been made up to now, but TTC system will be available
- Circulating beam measurements
  - Beam pick-ups (BCT or BPM) requested in Point 6 (ring 1 & ring 2), in Point 2 (ring 1) & in Point 8 (ring2)

# Status - Prototype

---

- Prototype for a synchronization and trigger system has been studied, developed and tested in SL/BT
  - Martin RAMPL & Johan DIEPERINK
  - Digital PLL and Numerical Controlled Oscillator (NCO) based on a 50MHz base clock appears to be stable enough to guarantee a correct synchronization for at least 5 turns without reception of the revolution frequency

# Conclusion / Remark

---

- Technical solutions exist to guarantee a correct synchronization during acceleration and physics if initial condition are fulfilled at the end of injection
- Particle free gap filling during acceleration and physics has not to be taken into account by the dump synchronization system
- Tracking the particle free gap during injection appears to be a more difficult challenge. Injection kicker can be used to inhibit wrong injection pattern, but can not cover all the possible errors (...mainly because it don't have a clipper switch)

# Conclusion / Remark

---

- Who is the guardian of the particle free gap during injection
  - ◆ RF: generates the revolution frequency and the injection prepulses
  - ◆ BT: can inhibit injection if wrong prepulses are received with respect to the received revolution frequency
  - ◆ Both... (BT & RF)