



# Beam Interlock System Electro-Magnetic Compatibility Testing



B. Todd AB/CO/MI MPWG 9<sup>th</sup> June 2006





## 1. System Overview

- Beam Interlock System
- Block Diagram
- Electrical Diagram

## 2. EMC Tests and Results

- Beam Interlock Controller to CIBU
- CIBU to User System
- Power Supplies

## 3. Conclusions

- Areas of Concern



## 1. System Overview

- Beam Interlock System
- Block Diagram
- Electrical Diagram

## 2. EMC Tests and Results

- Beam Interlock Controller to CIBU
- CIBU to User System
- Power Supplies

## 3. Conclusions

- Areas of Concern

## Beam Interlock Controllers (BIC)

16 BICs

- Two at each Insertion Point

Up to 20 User Systems per BIC

6 x Beam-1

8 x Both-Beam

6 x Beam-2

4 fibre-optic channels from Point 6

1 clockwise &

1 anticlockwise for **each** Beam

10MHz Square wave generated at IR6


-Signal can be cut by any Controller


-Signal can be monitored by any Controller

When any of the four 10MHz signals are absent at IP6, BEAM DUMP!

Beam-1 / Beam-2 are Independent!


Beam Dump **Beam-1** and **Beam-2**






Based on VME – Has a few sub-components







## 1. System Overview

- Beam Interlock System
- Block Diagram
- Electrical Diagram

## 2. EMC Tests and Results

- Beam Interlock Controller to CIBU
- CIBU to User System
- Power Supplies

## 3. Conclusions

- Areas of Concern



Tests according to the IEC-61000 for electrical systems:

Severity Level	Power and Grounds
1	0.5kV
2	1.0kV
3	2.0kV
4	4.0kV

Ideally: **A** at 4.0kV

Results categorised into four different types:


Test Result	Description	Example
A	No Noticeable Fault	No signals are seen to be perturbed
B	Corrected Fault	Critical Signal error, corrected by BIC
C	Fault	Critical Signal error, not corrected by BIC
D	Complete Failure	Loss of power / control

1. User Permit set to **FALSE** = see if EMC makes it **TRUE**


2. User Permit set to **TRUE** = see if EMC makes it **FALSE**

← **Unsafety**

← **False dumps**




## Cable with FULL Shields FULL Grounds



## Results

Full Shield, Full Ground	Severity Level			
	0.5kV	1.0kV	2.0kV	4.0kV
<b>User System Output</b>				
TRUE	A	A	A	A
FALSE	A	A	A	A


## Cable with FULL Shields NO Grounds




## Results

Full Shield, No Ground	Severity Level			
	0.5kV	1.0kV	2.0kV	4.0kV
User System Output				
TRUE	A	A	A	A
FALSE	A	A	A	A






## Cable with FULL Shields FULL Grounds



## Results

Full Shield, Full Ground	Severity Level			
	0.5kV	1.0kV	2.0kV	4.0kV
User System Output				
TRUE	A	A	A	A
FALSE	A	A	A	A

## Cable with Pig-tail Shield **No Grounds** E.G. Vacuum System




### Results

Two Pig-tails, No Ground	Severity Level			
	0.5kV	1.0kV	2.0kV	4.0kV
User System Output TRUE	A	A	A	D
User System Output FALSE	A	A	A	D

**Power PC Crashed – Ethernet Controller Stopped responding**

## Cable with One Pig-tail Shield No Grounds E.G. BLM System



### Glitches recorded in History Buffer


One Pig-tail, No Ground	Severity Level			
	0.5kV	1.0kV	2.0kV	4.0kV
User System Output	0.5kV	1.0kV	2.0kV	4.0kV
TRUE	A	B	B	C
FALSE	C	C	C	C

Permit FALSE on each salvo

Permit TRUE on each salvo




## VME PSU, Specified as “IEC-61000 Tested”



## Results

	Severity Level			
	0.5kV	1.0kV	2.0kV	4.0kV
VME PSU	A	A	A	A

CIBU PSU (CIBD), Specified as “IEC-61000 1kV”



Supply has been double encased, and has mains filter

Results

	Severity Level			
	0.5kV	1.0kV	2.0kV	4.0kV
CIBU PSU	A	A	A	D

**Power PC Crashed – Ethernet Controller Stopped responding, SW Permit FALSE**

## 1. System Overview

- Beam Interlock System
- Block Diagram
- Electrical Diagram

## 2. EMC Tests and Results

- Beam Interlock Controller to CIBU
- CIBU to User System
- Power Supplies

## 3. Conclusions

- Areas of Concern



The current loops from CIBU to User System are the weakest link

- If USER SYSTEMS don't follow the rules... it doesn't look good...

The CIBO

- Events seen on the Permit Loop, to be investigated – this was already planned

The Power PC

- Having to power cycle to wake it up... this will be corrected (so I am told)
- The software permit... Does every BIC need one?

The Timing (we also tested Timing Cables with Pablo from AB/CO/HT)

- VME bus errors recorded
- Safe Beam Flag dropped out
- I haven't the complete results, maybe not an EMC problem, but a supply integrity issue?? (Pablo)



The Beam Interlock System was designed for maximum EMC...  
The system performance is EXCELLENT if simple rules are obeyed!

A second sequence of tests will be done in the summer  
-with upgraded CIBO & complete chassis shielding  
-AB/CO/MI will report back to the MPWG then



# Lessons Learned from CNGS so far



The CNGS experiment has been excellent for testing the design of the BIS..  
And for finding out where we (AB/CO/MI) can improve

In just over two weeks, an interlock system ~1/4 the size of LHC was installed...  
...without major issue. (two cables wrong, some fibres missing)

## Lesson

## Example

1. Changing things at the last minute is a headache

new CIBM initialisation routine

Lots of extra work. For not much benefit...

If it isn't broken, don't fix it

2. Changing things without fully testing them is a bigger headache

new CIBM initialisation routine

Another debug iteration, moving cards back and forth. Wasting time.

Every change (no matter how small) means 100% has to be retested

3. Users don't read documents 100%

CIBU to User Cabling

Cabling is not as requested, probably because document is a bit long 30pg

Make a single page guide, with accompanying document to explain  
make EDMS approval for document

4. Documentation is key!  
4b. Everyone should agree on work before it's started

CIBM Matrix functionality

Agreed upon, but not everyone understood the same thing

Make a paper trail for everything important, even if it squashes "artistic freedom"



# Lessons Learned from CNGS so far



5. Installation of a CIBU is not trivial, it needs 4 people

Installing CNGS

Coordination suffers, as everything has to be done by mobile phone...  
**Agree on a rough course of action beforehand... stick to it... plan!**

6. User Systems appearing at the last minute are a nightmare

Hadron Stop Cooling

Resource management is hard, because everyone is already busy... and of course everything is urgent  
**Agree beforehand! No more things like this, please!**

7. The implementation of the Safe Beam Flag is unclear

Because everyone has their own ideas...  
And not everything is clear about how it will work...  
And everyone has already a lot to do, so SLP has suffered.  
**Let's agree on a course of action for the hardware, ASAP**

8. The Timing System

For me it is unclear how it all fits together, we need to understand what is possible and what isn't.. and how the necessary safety requirements are achieved  
**See the SLP...!**

9. The Software

Software has been tough to debug for the CNGS system, it's never clear if the software is at fault... or the driver's wrong... or the hardware is wrong... or the understanding is missing at some point in the chain.  
**Let's write some simple software specifications.**



## 10. Things that aren't clear

Some questions still remain unanswered, at the system level. If we aren't careful this is going to lead to a 'bricolage' when LHC starts...

Examples are:

-How are we to dump both beams when the LHC is above a certain energy?

We need to break all 4 beam permit loops...

-How do we disable the software interlocks on the BICs that shouldn't use them?

-How do we test the BEAM\_PERMIT\_INFO – by design it's untestable...

-Beam Permit Loops? Is the 10M vs DC the final solution?

-LBDS Interface collaboration...

These kinds of question, influencing the system level design need answering soon!



FIN