



# CIBU connection Review



BT, BP & IRR AB/CO/MI 12December 2008



## 1<sup>st</sup> presentation: CIBU Failure in UJ33 *(Benjamin TODD)*

- Background
- Before the incident
- The incident
- Future goals


## 2<sup>nd</sup> presentation: Proposal cures on HW side *(Bruno PUCCIO)*

- CIBU connection change
- Redundant signals and independent outputs
- Consequences on the Users side

## 3<sup>rd</sup> presentation: Proposal for automated test *(Ivan Romera )*

- The purpose
- First implementation on PIC-BIC interfaces
- Proposal & CMW interface with the Users.

The next steps...



BIS = Distributed system (all around LHC) for gathering Permit signals  
 BIS = Fast & reliable messenger for carrying dump request  
 BIS = Unique way for dumping the beam(s); "two BIS" as it's fully redundant.  
 BIS linked to various systems in using a single manner: CIBU (& CIBF)  
 BIS shall be fully checked before and after each beam operation  
 The connections with User systems will be checked as well  
 => Automated tests launched by the LHC Sequencer.

## 1<sup>st</sup> presentation: CIBU Failure in UJ33 (*Benjamin TODD*)

- Background
- Before the incident
- The incident
- Future goals

## 2<sup>nd</sup> presentation: Proposal cures on HW side (*Bruno PUCCIO*)

- CIBU connection change
- Redundant signals and independent outputs
- Consequences on the Users side

## 3<sup>rd</sup> presentation: Proposal for automated test (*Ivan Romera*)

- The purpose
- First implementation on PIC-BIC interfaces
- Proposal & CMW interface with the Users.

The next steps...



## 1. Background

- CIBU Input Circuits
- Installation Rules
- MI Stance

## 2. Before the Incident

- Vacuum System as Tested
- Conformity
- Functional Testing

## 3. The Incident

- Modified Interconnection
- Failure in the CIBU
- Report of Non-Conformities

## 4. Future Goals

- Connection Specification
- Improvements to Interfaces
- Automated Test Sequences

## Machine Interlocks Section

Develop fail-safe dependable hardware  
Testing / failure modes analysis of all critical hardware  
Audited / reviewed internally and externally

### We commit to

Be open and honest with you about our work  
Share our experiences openly (both bad & good)  
Be completely open to critique / criticism  
Optimise the balance safety versus physics

If ever we find weaknesses in our designs effecting safety  
We will present the findings to MPP and **stop the LHC until issues can be solved**  
Every experience is fed back into the design  
Everyone's opinion counts.

This is an example of this commitment to you – no blame to be assigned!  
Quite the opposite!  
We can use this to improve our designs - Let's take a look...



# The User Interface (CIBU)



## User System to Beam Interlock System connection

1. Unique Hardware for All Users
2. Current Loops
3. Redundant Circuits
4. Tested to CIBU Output Connector Internally using BIS TEST
5. Need **USER SYSTEM Test** for full coverage

CIBU is used in the whole accelerator complex  
Many CIBU-Hours of operation for statistics  
Around 2e6 unit-hours - SPS since 2006

Link Specified in:


<https://edms.cern.ch/document/636589/1.4>

Until this year – NO failures on critical paths










User System

User Interface (CIBU)


to Controller








# CIBU Input Circuit





### Mandatory Circuit

1. All ground / earth / 0V connected
2. Spare wires grounded
3. Shield 360° at both ends
4. No pig-tails
5. More than 5m = FORBIDDEN
6. Cable should be:
  - a. Twisted Pair NE8/NF8
  - b. LEMO 00 from VME FP

7<sup>th</sup> August 2008

No Beam In the Machine


Final Commissioning Vacuum System to Beam Interlock System

1. Vacuum Valves moved IN around IR3
2. Vacuum UJ33 USER\_PERMIT\_A stayed TRUE
3. Vacuum UJ33 USER\_PERMIT\_B stayed TRUE
4. BIC Test Mode showed ALL OK

Commissioning Fail

## AS TESTED (Vacuum mid-July)

1. All ground / earth / 0V connected
2. Spare wires grounded
3. Shield 360° at both ends
4. No pig-tails
5. More than 5m is forbidden
6. Cable correct type:
  - a. Twisted Pair NE8/NF8







Between July and August  
EIS (Elément Important de Sécurité)

1. Added to Interlock Logic
2. EIS controlled by Access System (Personnel Protection Device)
3. Access System connected to BIS via Vacuum System

MI were not aware of this cabling change





Surface IR3

46 Signals From other equipment

6 floating wires

100m

5-10m

100m

PLC = 48V

Not Enclosed

2m to Lift Motor

1m to GSM Repeater

Vacuum Interface

Shielded & Twisted Pair Cable

CIBU - USER INTERFACE


24V

0V

1m

**WHEN CONNECTED  
CIBU ALWAYS TRUE  
(next slides)**


Access – Connected Panel to Surface PLC incorrectly initially  
...took several attempts ...




## Presumed Failure


### 1. Excessive Voltage

Is applied in the Access System PLC rack, due to erroneous cabling



2. This subjects the CIBU negative current loop to an excessive voltage (48V)







3. The Transient Voltage Suppressor (SM6T30CA) Clamps the voltage and dissipates the energy



4. Experiments show that after 1-2 seconds the TVS will fail, this TVS fails open-circuit  
The 'A' loop TVS now absorbs the excess




5. 1-2 seconds later this TVS fails short-circuit




6. The fault is discovered in the ACCESS system and is removed

But the TVS is so badly damaged it fuses to ground



7. At this point both USER PERMIT A and B are stuck TRUE as current flows to ground through A (green) and B (blue) using the damaged TVS



## Several events = complete Blind Failure

1. Two Equipment systems sharing the same channel
2. PLC Voltage against rules
3. TVS Blocked Short-Circuit
4. Inputs were not redundant
5. Not re-commissioned by MI after a significant change

## In addition...

- a) Cable length against rules
- b) EMC would have been a show-stopper anyway!

Shows weaknesses in the interconnection conception:

1. No redundancy = No SIL
2. Can a GND short be mitigated?
3. Human Error can never be 100% eradicated –  
Testing before each fill should be possible if in doubt!

For each User System

1. Change to use full redundancy
  2. Change so a GND fault doesn't fail blind
  3. Automated Test from User Side  $A \neq B$
- } 2<sup>nd</sup> presentation
- 3<sup>rd</sup> presentation



Intentionally blank (end of 1<sup>st</sup> part)





## 1<sup>st</sup> presentation: CIBU Failure in UJ33 (*Benjamin TODD*)

- Background
- Before the incident
- The incident
- Future goals

## 2<sup>nd</sup> presentation: Proposal cures on HW side (*Bruno PUCCIO*)






- CIBU connection change
- Redundant signals and independent outputs
- Consequences on the Users side

## 3<sup>rd</sup> presentation: Proposal for automated test (*Ivan Romera*)


- The purpose
- First implementation on PIC-BIC interfaces
- Proposal & CMW interface with the Users.

The next steps...


## Several events has led to a complete Blind Failure

1. Two different Equipment systems sharing to the same channel  Vacuum "hosted" E.I.S. connections in 2008.  
E.I.S. (managed by Access system) will have their **dedicated** channels on 2009
2. PLC Voltage against rules  No additional protection possible with existing design...  
(only regular tests can "protect")
- 3 .TVS Blocked Short-Circuit  Slight change of the interface (on User system side) for each connection  
(see next slide)
4. Inputs were not redundant  Redundant signals should be supplied  
It will become mandatory in 2009.  
(see following slide)
5. Not re-commissioned after change  
+ Human errors...  
+ possible Hardware failure....  *Tests, tests and tests...*  
*in other words: regular tests.*  
*"as frequently as possible" .*  
*Every fill will be the best option*  
*=> implementation of **Automatic tests***  
(see next presentation)

On User side, the connection should be modified in order to avoid a fail blind if GND short (i.e. a damaged TVS fuses to ground)




( Same for Input #B )




( Same for Input #B )

The BIS is fully redundant from CIBU inputs to the outputs to Dump Kickers.

In order to avoid/minimize the single mode failure:  
 the two CIBU inputs should be no longer linked together  
*(neither in series nor in //)*




each User system has to provide two independent signals to the CIBU




Despite there is a single decision maker...

The aim is to make two physical connections....



Will be required for automated tests...



## For the redundancy constraint:

As far as we know (*information gathered during the 2008 commissioning*):  
the following systems are not delivering redundant signals:

- ALICE magnet, ALICE ZDC
- BPM (Beam Excursion)
- BTV
- CMS (Detector part)
- TOTEM
- MKI2 & MKI8
- PO for the MSI Converter Sum Fault
- RF
- VAC

For the independency of the two outputs activation  
and

For the connection change (i.e. move of the “switch”)

We cannot identify because basically  
we do not know how it is currently implemented...

*Only BLM has kindly sent us the corresponding schematics.*



## LHC Beam Interlock System Connections

B.P.  
27<sup>th</sup> May 08

	User Systems	LHC ring																	Injection		Abbrev.
		L1	R1	L2	R2	U3	S3	L4	R4	L5	R5	L6	R6	U7	S7	L8	R8	CCR	#	1	
1	Collimation (Environmental par.)	••	••	••	••	••				••	••	••		••	••	••	••	22	•	•	COLL_ENV
2	Collimation (Motor positions)		••	••	••	••				••	••	••		••	••	••	••	20	•	•	COLL_MOT
3	Vacuum system ("sector valves")	••		••	••	••		••	••	••	••	••	••	••	••	••	••	24	•	•	VAC
	Vacuum system ("X valves")		•		•					•							•	6	•	•	"
4	PIC for essential circuits	•	•	•	•	••		•	•	•	•	•	••		•	•		16			PIC_UNM
	PIC for auxiliary circuits	•	•	•	•	••		•	•	•	•	•	••		•	•		16			PIC_MSK
5	BLM at aperture limitations*	•					•	•	•						•	•		8			BLM_UNM
	BLM in arcs	•		•			•	•	•						•	•		8			BLM_MSK
6	Fast Magnet Current Change Monitors	•		••		•••				•		••		•••				12	•	•	FM_xxxx
7	Warm Magnets Interlock	•		•		•		•	•		•		•		•			8			WIC
8	Screens		•		••			•	•		•		•		•			8			BTV
9	RF & Transverse Damper							••	••									4			RF
10	Beam excursion (BPM)										••	••						4			BPM
11	LHC Beam Dumping system										•	•						2	•	•	LBDS
12	LHC Control Room (Operator Buttons)																••	2	•	•	CCC
13	Programmed Beam Dump (via Timing)																••	2	•	•	LSEQ
14	LHC Safe Machine Parameters																••	2	•	•	SMP
15	ATLAS (movable devices)		••															2			ATL_MOV
16	TOTEM (movable devices)									••	••							2			TOT_MOV
17	Fast Beam current Change Monitors								••									2			FBCM
18	Beam Aperture Kicker							••										2			MKA
19	Injection Kicker			•												•		2	•	•	MKI
20	LHC Access Safety System																•	1			LASS
21	ATLAS (Detector part)		•															1	•	•	ATL_DET
22	LHCF (Detector part)		•															1			LHCF_DET
23	ALICE (Detector part)				•													1	•	•	ALI_DET
24	CMS (Detector part)										•							1	•	•	CMS_DET
25	TOTEM (Detector part)										•							1	•	•	TOT_DET
26	LHCb (Detector part)															•		1	•	•	LHCB_DET
27	LHCb (movable devices)															•		1	•	•	LHCB_MOV
28	ATLAS Experiment Magnets		•															1			ATL_MAG
29	ALICE Experiment Magnets				•													1			ALI_MAG
30	CMS Experiment Magnets									•								1			CMS_MAG
31	LHCb Experiment Magnets															•		1			LHCB_MAG
32	ALICE-ZDC (movable device)																		•	•	ALI_ZDC
33	MSI Convertor Sum Fault																		•	•	MSI_SUM
																	186	14	13		

Total of connections

•• : Individual Beams connections  
(•• if Unmaskable)

• : Both Beams connection  
(• if Unmaskable)

*Difficult to evaluate the impact on the Users.*

*Same for the implementation of Automated tests.*

*Should be seen case by case.*

*We are obviously willing to help and to collaborate.*



Intentionally blank (end of 2<sup>nd</sup>part)



## 1<sup>st</sup> presentation: CIBU Failure in UJ33 (*Benjamin TODD*)

- Background
- Before the incident
- The incident
- Future goals

## 2<sup>nd</sup> presentation: Proposal cures (*Bruno PUCCIO*)

- CIBU connection change
- Redundant signals and independent outputs
- Consequences on the Users side

## 3<sup>rd</sup> presentation: Proposal for automated test (*Ivan Romera*)

- The purpose
- First implementation on PIC-BIC interfaces
- Proposal & CMW interface with the Users.

The next steps...

## 1. BIS side:

Test that all HW links from User Systems to CIBUs are working correctly

- ensure that each User system is able to give/remove both Permits
- guarantee no blind failures (electronic part)
- Forms part of BIS pre-operation checks
- will be launched by the LHC Sequencer
- Frequency not yet decided (every month? every week? every fill?...)

## 2. Machine protection side:

Test could be also used in order to check that the full chain is working correctly


The way to perform the test will be different for each system

(for ex: how to proceed with thousands of BLMs channels?

in addition, not possible to move each vacuum valves, etc...)

Should be discussed case by case => chosen solution endorsed by MPP.

- Automated tests successfully developed and tested during the HWC
- Integration in the Sequencer Framework
- BICs communication already implemented
- LSA database for configuration and storing results



1. Request to the User from external system (SEQ) to enter in Test Mode

2. User in Test Mode?

*acknowledge by checking the Beam Permit Info (if connected)*

3. Loop through all the Users involved in the test:



3.1. Initial conditions OK for BIC and User? (both Channels A/B are FALSE)

3.2. Set Channel A and Channel B independently on User side

3.3. Verify consistency on the BIC side

3.4. Reset failure conditions

3.5. Save results to Database (LSA?)



1. Name of the property CibuTest.
2. Property should allow setting and getting - set/get type.
2. Fields of the property: A, B, Test - all boolean type.
3. Partial set should be implemented.
4. Server action implementation of this property, should ensure boolean complementary, that means when the A field is set, B isn't and viceversa when the B field is set, A isn't.
5. When user try to set both A and B at the same state in one call then an exception should be thrown and nothing should be changed.



Intentionally blank (end of 3<sup>rd</sup> part)





1. Give time to evaluate the proposals
2. Discussion for the feasibility and the timescale with each User
3. Summary of requests/issues presented in the framework of coming MPP meeting (possibly on 2<sup>nd</sup> or 3<sup>rd</sup> week of Feb.09)
4. Setting up of schedule for re-commissioning
5. Give support and discuss in case of issue

FIN