



Common Systems, Infrastructure and Facilities

This part of the proposal for 2010-16 is about:

- Modifying the Common Systems & Infrastructure of the CMS apparatus to maintain or improve safety & reliability, or to accommodate detector consolidation/upgrade.
- Re-configuring & equipping facilities for upgrade assembly & integration

Divided into 10 projects/tasks:

- (1) Safety systems for the protection of personnel and equipment**
- (2) Magnet and magnetic field measurement/simulation**
- (3) Yoke, Shielding and Moving Systems**
- (4) Experiment Beampipe**
- (5) Beam Radiation Monitoring System**
- (6) Experiment Service Infrastructure**
- (7) Beam, radiation, cosmic ray or environmental Test Facilities**
- (8) Surface assembly buildings, workshops, laboratories, and storage space**
- (9) Logistics and Integration**
- (10) Planning and Coordination**

....the following summarises the main activities in each:



Safety Systems

General Safety

- safe areas and evacuation route
- magnetic-field tolerant public address system

Detector Safety system (DSS)

- shifter friendly user-interface
- maintainability of racks

Sensor systems

- rad. tolerant opening/closing sensors
- environment monitoring (fibre-optic sensors)

Nitrogen, dry air and compressed air

- factorise functions
- introduce redundancy
- capacity to run Tracker cold.



Safety systems

Fire prevention, detection and extinguishing
extend filter farm system

Radioprotection precautions, measuring & traceability equipment
equipping buffer zones & workshops (esp SX5 building)
screening instruments for faster RP turnaround

Access control
speed up access procedures and issue of sensitive keys

Safety Training
pt 5 specific training



Magnet

Magnetic field off: ~ no useful physics

Magnet on-off-on: limited number of such cycles in lifetime

Helium compressor pair

- critical single point failure
- replacements now only built to order
- provision for redundant pair foreseen

Compressor lubricant separator


- prevent pollution of high-pressure unit

Cold box

- redundancy or cold-swap of pre-turbine filters to avoid ramp-down for regen.

Miscellaneous

- spares for power & control systems






Magnetic field measurement & mapping

Hardware: Flux loop system for measurements in yoke + more Hall probes in fwd.

Software: Effect of shielding disks YE4

Fringe field effects in forward directions







Yoke, Shielding, Moving

Safer, more flexible movement, with lowered risk to beampipe

- air pad compressed air source: bottles → compressors + buffer
- forward opening with bp at vacuum
- hydraulics for inter-disk movement

YE4 Disks

- completion of the high lumi shielding system



Key part of the forward muon upgrade





Yoke, Shielding, Moving

YE4 pushback system

- mitigate effect of scrambled sequence in forward muon upgrade
- YE4(+z) an YE4(z) construction 2012-13
- endcap muon layer(-z) 2013-14?

Radiation shielding

- protect personnel from activated elements during maintenance & upgrade activities



10/7/2010

TIG Meeting Gerwig/Siegrist/D.-R


Urgent to test in 2012-2
before activation significant



Yoke, Shielding, Moving

Forward Region

correct for underestimated magnetic fields and forces
apply ALARA to dose received in forward closing sequence
allow forward detectors to be swapped in with bp at vacuum (if needed)





Beampipe



Reduce central Be pipe diameter

- aim for ~23mm
- 12 facet pixel layer1
- maintain $\eta = 4.9$ ec cones


To check:

beam stay-clear vs z
sagging
vacuum stability
supports





Quantity	Original estimate	Measurement
Construction tolerance	2.6mm	<0.6mm
Installation tolerance	2.6mm	2.7mm
Sagging between supports	2.2mm	<3.0mm (for r=25mm pipe)
YB0 yoke distortion	1.4mm	<0.5mm
Field induced yoke movement	1.2mm	<1.0mm
Cavern movements	5mm	<1.0mm
Linear sum	15mm	<8.8mm
Assumed “stay-clear” radius	14mm	14mm
Min beam pipe radius	29mm	~23 mm

Beam Radiation Monitoring


RADMON: 18 monitors around UXC
PASSIVES: Everywhere



C.M.S. PARAMETERS
Longitudinal View - Field Off



←
BPTX: 175m





Beam Radiation Monitoring

Pixel Luminosity Telescope

- under construction: install 2012-13

Fast Beam Condition Monitors

- collaborate with LHC BI

Beam Condition Monitors & abort func

- readout based upon LHC BLM
 - keep systems contemporary
 - keep collaborative effort with

Beam Scintillator Counters

- rad tolerant upgrade in 2012-13

Beam Pickup Timing for the eXperime


- zero-bias trigger remains invaluable
- needs electronics consolidation

Detectors for benchmarking radiation :

Simulation invaluable for numerous aspects of background and access planning

- additional monitoring, especially neutron monitoring and passive
- "HF RADMON" (prop chamber) & Medipix neutron Camera measured n flux
- foresee additional units

CMS-BRM at the forefront of practical applications of diamond detectors





Experiment Service Infrastructure

Upgrade to:

- maintain reliability at higher luminosity, radiation load & activation
- eliminate perceived weaknesses threatening data-taking efficiency
- replace obsolescent parts
- accommodate upgraded detector

Cooling system

- establish cold operation of Si Tracker (isolate/backup from HVAC)
- filter farm cooling 600kW → 1MW (attempting in 2010-11!)
- RPC cooling : reduce operating temperature to nominal UXC temp.
- equip YE3 manifold to accommodate RE4
- improve leak tolerance/ detection/ suppression (YE1 manifold re-build)
- USC rack system extension for trigger/DAQ upgrades
- separate SCX control room cooling from filter farm



Experiment Service Infrastructure

Electrical distribution:

- further improve CMS “ride-through” of electrical transients
- extend UPS & diesel coverage of SCX control room & service cavern
- install harmonic filters

Heating, Ventilation & Air Conditioning

- improve ventilation seals for shafts, safe areas and USC-UXC-LHC (as needed to maintain safe access to/work in underground zones)
- maintain minimum cavern humidity (~30% RH – workers, electronics)



Test facilities

Beam, radiation, cosmic ray or environmental test facilities

Needed for:

- controlled investigation of anomalous detector behaviour
- upgrade R & D and beam validation

SPS North area: H2 beamline

- permanent combined calorimetry test apparatus
- large beam energy range due to special low energy tertiary beamline

SPS North area: H4 beamline

- η - ϕ moving platform in environmentally controlled zone, calibration laser

Large area cosmic ray tracking telescope

- replace ISR system when moving muon assembly/test to 904

Irradiation facilities

- γ , π , n , mixed field: new GIF and mixed field facilities to be supported

High Magnetic Field Facilities:

- refurbish vac & controls of M1 3T large aperture (1.4m) magnet, SPS North Area beamline H2 (should be joint project with PH, EN?)
- purchase small bore (20cm) 4T magnet for short tests of small objects.



CMS assembly & lab areas: future

External constraints : entire 3000m² CMS area in ISR destined for rad material treatment
entire 1500m² CMS area in 867 destined for machine ra material handling.

Agreed Solution (endorsed by HSE and later by Site Committee on 24/9/2009):

For maintenance of equipment exposed to beam in UXC (including activated material)¹

—> Concentrate activity in existing SX5 building, LHC Point 5, Cessy.

For maintenance of non-activated equipment NOT exposed to beam in UXC or elsewhere,
And for upgrade.

—> Concentrate activity in 186 (Meyrin) & 904 (Prevessin) + some additional smaller zones (eg 892)

Concentration ensures that CERN staff TSO and support technicians can be assigned to each of these sites. Key infrastructure will be included in TI desk monitoring.



Logistics and Integration

Cranes and rigging equipment & personnel

- resources to match the intense efforts expected in 2012-3,2016

Tooling and Working platforms

- CSC/RPC tooling adapted to accommodate YE4
- shielding installation tooling
- climate controlled enclosure for working on cold Si detectors in UXC
- simplified beampipe support for some configurations to reduce risk

Engineering Integration:

- additional effort on top of M & O & host lab provision
- averages to 2 FTE engineers plus tech/draughting

Electronic & Electrical Integration

- additional effort on top of M & O provision
- averages to 1 FTE engineer plus some tech assistance.



Logistics & Integration

Logistic support teams: **NB careful not to underestimate upgrade costs in this area:**

Projected CMS M & O A budget lines based on an outdated LHC operating pattern:

- annual (~4 useable month) shutdown mid-Nov to mid-March.
- one end of CMS opened each shutdown (on average)
- single (mostly re-certification driven) annual maintenance cycle performed on items such as moving equipment and access devices.
- extra logistic teams required 4 months/year from the Collaboration, Field Support Units (FSU), survey & beampipe teams and contractors.
- integration, planning, field coordination efforts cover only shutdown maintenance (ie what would have to happen even if no upgrade)

Simple count of useable shutdown months 2010-16, gives:

baseline model: 23 months

actual planning: 39 months


Simplistically, scale M & O provisions by at least 39/23

Reality is worse, since 2012-13 will be as intense as 2008 or 2009.



CMS Technical Organisation: Overview

for Operation, Maintenance & Upgrade Projects





Planning & Coordination

Constraints: timescale for installation of consolidation & upgrade items mostly set by readiness wrt the 2012-3 and 2016 shutdowns

technical stops (2013) 2014 can also be useful for completing 2012-3 work without full opening (maintenance permitting)

configurations of CMS limited by

- beampipe support
- size of UXC wrt CMS
- procedures for bp bakeout



Planning : pixel & beampipe forced to be 2016
 need detector fully open (*both ends*) or in bakeout most of time compatible with HCAL barrel & endcap HPD → SiPM refurb

YE4 construction forced to be 2012-3
 need detector closed or near closed at one end most of the time compatible with HO HPD → SiPM refurb

YE4 pushback in case one end RPC/CSC arrives after YE4. (eg 2014)

TC and EAM teams need equivalent strength to 2008-9 for this intensity of activity

Task Name	Duration
1 <input type="checkbox"/> +Z end sequence	258 days
2 CMS in Configuration A	0 days
3 Go to configuration G	17 days
4 <input type="checkbox"/> CMS +Z in Configuration G	36 days
5 Install PLT, Service PIX & TK	28 days
6 Replace faulty HB Readout modules on YB+2	1 wk
7 Service RPC & CSC chambers on YE+1	36 days
8 Go to configuration E	5 days
9 <input type="checkbox"/> CMS +Z in Configuration E	48 days
10 Assemble YE+4 + new jacking system	6 wks
11 Go to configuration H	6 days
12 <input type="checkbox"/> CMS +Z in Configuration H	42 days
13 Change HO Phototransducers on YB+2IP, YB+1AIP, YB0+Z	42 days
14 Service RPC on YB+2/+1/0+Z	18.5 days
15 Service DT on YB+1 & YB0 + upgrade infrastructure	26 days
16 Go to configuration C	13 days
17 <input type="checkbox"/> CMS +Z in Configuration C	52 days
18 Perform Magnet Test	4 days
19 Pull out YE+4 using new jacking system	2 days
20 Install CSC station 4	46 days
21 Go to configuration B	3 days
22 <input type="checkbox"/> CMS +Z in Configuration B	8 days
23 Install T1	8 days
24 Go to configuration A	4 days
25 Pump Down CMS Beam pipe	3 wks
26 CMS Ready for beam	0 days



The working planning already reached 230 discrete tasks





Extras


More about: assembly building 904
 PLT
 BSC upgrade

Pixel Luminosity Telescope


CC L



8 telescopes per "end"



Prototype telescope




finished detector

- Measure luminosity by counting tracks pointing at the IP every 25ns "FAST-OR"
- Online relative luminosity to a precision of 1%
- Use single crystal cvd diamond, bump bonded to pixel chip PSI46
- Tested in 3 testbeams so far - pixel yield and fast-OR >98%
- 33/60 Detectors are bump bonded at PRISM/Princeton US
- Assembly about to start at CERN
- First diamond pixel tracker to be installed in HEP
- *Testbeam results published: NIM A (2010) in press*


Beam Scintillator Counters Upgrade



- Beam Scintillator Counters designed for startup phase
 - Essential: Min-bias trigger for 2009-10 running
 - Design luminosity for these devices reached
 - **Simple**, rad-hard replacement required
- 2010 run shows that a beamgas background device for vetoing/triggering essential
- This should have high acceptance for beamgas originating in Long Straight Section




- At least 4 planes:
 - $\pm 10m, \pm 14.4m$
 - Present BSC2 alone 30% acceptance, 30% \emptyset coverage



In front of HF, ..best location in middle of T1




ISR: conditions naturally stable enough



Temperature 21 ± 3 degrees C
(for RPC 20 ± 2 is ideal)

Relative humidity: 45 ± 10 %

(For RPC 40 ± 5 % is ideal)




Building mods & HVAC to achieve these conditions
in all of 904 VERY expensive:

CMS suggestion to use temperature-controlled internal
lab enclosures with central HVAC



CSC Chamber Factory Production at CERN

Floor Layout at Bldg 904



Production line disassembled at FNAL and is at sea at this moment

O.Prokofiev
Feb 16, 2009



RPC production line

PRODUCTION RPC Bt 904

Climate controlled zone

