PAUL SCHERRER INSTITUT




Joachim Grillenberger :: Large Research Facilities :: Paul Scherrer Institute

# The High Intensity Proton Accelerator Facility Status and Perspectives






# High Intensity Proton Accelerator 50<sup>th</sup> Anniversary in 2024






# High Intensity Proton Accelerator Facility






# 590 MeV Ring Cyclotron at PSI in operation since 49 years (19.2.1974 first muons)



Beam energy:	590 MeV		
Beam current:	2.4 mA		
Beam power:	1.4 MW		
<b>Relative losses:</b>	<b>12·10</b> <sup>-4</sup>		
Single turn extraction			
4 cavities (50.63 MHz):	850 kVp		
1 Flattop (151 MHz):	550 kVp		
Harmonic number:	6		
Number of turns:	186		
8 sector magnets:	0.6 – 0.9 T		
R <sub>in</sub> :	2.1 m		
R <sub>out</sub> :	4.5 m		


#### **Energy efficiency:**

$$\eta_{acc} = \frac{P_{beam}}{P_{Grid}} = \frac{1.42 \ MW}{8 \ MW} = 0.18$$





**Empirical Power Scaling Law** 



W. Joho, High intensity problems in cyclotrons, Proceedings of the 9<sup>th</sup> International Conference on Cyclotron and their Applications, pp. 337–47. Les Editions de Physique, BP 112, 91402 Orsay (France), ISBN 978-3-95450-160-1 (1981).

Page 6



# **Copper Cavities at PSI**




- f = 50.6 MHz
- U<sub>max</sub> = 1.2 MV (presently 850 kVp)
- $Q = 4.8 \cdot 10^4$
- Transfer of up to 400 kW power to the beam per cavity






Wall plug to beam efficiency:

- AC/DC: 90%
- DC/RF: 64%
- RF/beam: 55%
- All over: 32%





### Injector 2 Cyclotron Commissioned in 1985



• beam energy: 72 MeV

- max. beam current: 2.7 mA
- 4 sector Magnets: 0.33 0.36 T
- weight per magnet: 180 tons
- 2 resonators: 50.63 MHz
- 2 flattop resonators:150 MHz
- harmonic number:10
- injection radius: 0.4 m
- extraction radius: 3.5 m
- 80 turns


Beam power: 72 MV • 2.7 mA = **194 kW** 

#### Ongoing upgrade project for 3.0 mA and reliability



1995 the operation observed in Injector 2


- the same extraction rate without Flattops (accidently switched off)
- a higher extraction rate with reversed phase (accelerating mode, less turns)



#### Explained by the «vortex effect»

M. M. Gordon, The longitudinal space charge effect and energy resolution, In McIIroy[47], 425pp. 305– 317 (1969)


S. Adam, Space charge effect in cyclotrons - from simulations to insights, In Comell[48],439pp. 446–448 (1995)




- Vortex motion stabilizes the bunch
- Space charge couples longitudinal and horizontal motion
- Longitudinal focusing (weak though)



- 1. Goal: reduce the number of turns from 83 to 60 for 3 mA (n<sup>-3</sup> law)
  - $\Rightarrow$  Increase energy gain per turn  $\Rightarrow$  Increase acceleration voltage





150 MHz Flattops not needed (Vortex Effect) double energy gain per turn

Already installed 2018

60 instead of 83 turns -> 3.0 mA according to  $I \simeq \frac{1}{n^3}$  where n = number of turns



# Injector 2 – Upgrade



resonance frequency	50.6328 MHz
accelerating voltage	400 keV @ R <sub>out</sub>
dissipated power	50kW @ 400kVp
Q	24'500
Tuning range	200 kHz
material cavity RF-wall	EN AW 1050
material structure	EN AW 5083
cooling water flow	15 m³/h
dimension	5.6 x 3.3 x 3 m
weight	7000 kg

#### New Resonator 2 Installed 20.02.2018

Resonator	type	material	frequency	gap voltage	Wall losses in cavity	incident power @ 2.4 mA Beam
1&3	Double gap cavity	aluminum	50 MHz	~ 420 kVp	~ 150 kW	~ 225 kW
2&4	Flattop cavity	aluminum	150 MHz	~ 31 kVp	~ 5 kW	$\sim$ 14 kW
2 & 4 new	Single gap cavity	aluminum	50 MHz	~ 400 kVp @ extraction	~ 50 kW	~ 100 kW

#### M. Schneider, PSI



Status Injector 2 – Upgrade The new 50 MHz Resonators

#### **Resonator 2:**

- Installed in Injector 2 Cyclotron in 2018
- No tuner up to 2023

served very well as a vacuum chamber.....

#### **Resonator 4:**

- In test stand for tuner and power tests
- Treated with Aquadag (multipactoring)



Resonator 4: treated with Aquadag



Resonator 2 installed in Injector 2




Resonator 4 in test bunker Installation in 2024




# Tuner for new Resonators tested in Resonator 4







- Tuners show abrasion caused by contact springs
- Tests with different materials, different spring preload, ... failed
- New concept was necessary

Finger contacts between vaccum vessel and plunger









- No spring contacts
- New vacuum vessel Al instead of steel
- Additional cooling channel on vacuum vessel
- Optimized geometry to reduce RF leaking into vessel
- New plunger with improved cooling channels



# Installation of tuners during Shutdown 2023




Installation team



Coaxial transmission line (RL100-230, Spinner) New tuners installed

#### 6. September 2023 first beam through Ring with 1 mA



3'250

3'000

0.001

0

2'250

2'750

radius (mm)


2'500

Page 17




Resonator 2 Commissioning

Peaks shift as desired — higher energy gain per turn











- 2. Goal: Higher RF-voltage for new Resonators 2 + 4
- 3. Goal: replace outdated amplifier chains for resonators 1 + 3






### Resonator 4 Amplifier control unit



- Unit failed in June 2022
- 40 years old / no documentation
- No spare parts
- Amplifier replaced with two SSAs BBL200-A10000
- Will be used as drivers for Res. 1-4



Reduced beam current for 6 months 1.8 mA instead of 2 mA





# Injector 2 – Upgrade Amplifiers


- 2. Goal: Higher RF-voltage for new Resonators 2 + 4
- **3. Goal:** replace outdated amplifier chains for resonators 1 + 3



Commissioning: Res 2 in 2023, Res 4 in 2024, Res 1 & 3 in 2025



# High Intensity Proton Accelerator Facility Cockcroft – Walton





## Cockcroft – Walton 870 keV, 30 mA



Cockcroft-Walton with 810 kV platform and acceleration tube ECR-source very reliable (>99%)



2020: HV breakdown due to scorched acrylic glas



 $SF_6$  disposal



polishing



Recurring: burnt fibre optics



different supplier or laser transmission




Defect transformer in microwave amplifier No more support New solid state version





# Status of the Ring Cyclotron







**Current routine operation at 2 mA** Reason: Injector 2 – Upgrade

#### • Vacuum improved (rad. hard In sealings)




- Electrostatic Elements shielded (RF)
- Cu–Cavities ready for 3.0 mA
- RF-Amplifiers need upgrade for 1.8 MW
- New long radial probe



## Long Radial Probe Ring cyclotron Renewal Project


# Not available since 2012 but important for beam dynamics






accelconf.web.cern.ch/ibic2020/papers/wepp33.pdf

- New mechanical drive
- New wire fork






Wires still burn out even with RF only Studies with C-nano tubes ongoing



# 150 MHz Flattop Cavity (1979)

#### 72 MeV beam \



- 3<sup>rd</sup> harmonic «flattop» cavity
- 151 MHz
- 550 kV (11% of main voltage)
- Q = 28000
- Gap = 0.25 m





- Larger phase acceptance (40° instead of 9°)
- Factor of 10 less losses at extraction

Probe RRL I just showed



## Röntgen Emission Cavity 5






Ionisation chambers




# Multipactoring Flattop Aquadag Coating



#### Aquadag to suppress secondary electron emission




Empirical Scaling Law by W. Joho<sup>1</sup>



[1] W. Joho, High intensity problems in cyclotrons, Proceedings of the 9<sup>th</sup> International Conference on Cyclotron and their Applications, pp. 337–47. Les Editions de Physique, BP 112, 91402 Orsay (France), ISBN 978-3-95450-160-1 (1981).




- variation of accelerating voltage over the bunch length increases energy spread
- thus a third harmonic flattop resonator is used to **compensate the curvature** of the cavity voltage w.r.t. time (apparently no vortex effect in Ring cyclotron)





# New 150 MHz Flattop Cavity for 3.0 mA




Improved cooling for 140 kW dissipated power

Material choice: pure Aluminum

New coupler design (ongoing)

٠


٠



- Multipactoring studies
- J.-Y. Raguin, M. Bopp, R. Fortunati, J. Grillenberger, T. G. Lucas, M. Pedrozzi, M. Schneider, M. Stoll, PSI E. Solodko, Transmutex



# Availability of the Accelerator Facility



High availability is of uttermost importance for the users Secondary particle yield comes second




- Life-time of ball bearings 6 months (1 failure per year)
- Life-time of motor 3 years



Exchange flask

Hotcell





#### Challenges

- 50 kW on Target E
- Cooling (1700 K)
- Temperature resistant material
- Thermal stress (deformation)

- $\Rightarrow$  Rotation 1 Hz (**bearings**)
- $\Rightarrow$  Radiation, Cu-shielding cooled
- $\Rightarrow$  Polycrystalline graphite
- ⇒ Spokes (thermal expansion) Slits in wheel


#### Bearings were the neuralgic spot

New ball bearings with solid state WS<sub>2</sub> lubricant by S. Makimura (J-Parc) & KOYO® Installed in 2019


# No target failure during user operation since December 2019







30 – 50% increase in surface muon rate (measurement and simulation agree)




Beam position monitoring by current transmission measurement



Steps Towards a Higher Efficiency SINQ – Upgrade 2019

- Replacement of neutron guides
- Optimization of instruments
- Optimization of D<sub>2</sub>O moderator geometry




- measured flux gains ranging from 2–30 depending on the instrument
- signal to noise ratio increased by a factor of 6
- The Accelerator's uptime and beam intensity remain the primary driving forces!



# Steps Towards a Higher Performance Accelerator part

Increase Beam Power to 1.8 MW

- Understand and reduce losses
- More diagnostics and simulations
- Finish Injector 2 Upgrade (by 2025)
- Increase gap voltage in Ring (n<sup>-3</sup> law)
  - More powerful RF-amplifiers (SSA?)
  - new flattop system
- Well trained operators and more beam development (A.I. does not exist...)





- The PSI accelerator has already deliverd a 1.4 MW beam in CW mode
- Major performance steps achieved by RF-upgrades
- The average availability now is 90%
- Number of short trips (<5 min) is >10 per day
- Modular design allows for fast and save repair (< 2days, 4h average)
- Energy efficiency is 0.18 (bare accelerator)
- High demand of Neutron Sources
- Since 2020 new neutron guides/ monochromators (2–30 more neutrons)
- New project IMPACT is on its way
- Operation until 2030+



https://www.psi.ch/en/impact CDR: https://www.dora.lib4ri.ch/psi/islandora/object/psi:41209

#### We have to/want to prepare for another 20-30 years of operation

#### Infrastructure, conventional systems, cooling, hotcells, etc are in good condition



# 10 Year Upgrade Plan



- **Electronics and Control System** 
  - Replacement of CAMAC-based system
  - New Firmware and Control system integration
  - interlock integration and level adaption
- RF Renewal and/or Upgrade
  - new Flattop
  - Renewal / Upgrade of RF-amplifiers (SSD)
- **Magnet Renewal and Spares** 
  - many coils over 50 years old
  - Bending magnets critical stock
- Diagnostics ٠
  - Fast Wire Scanners (beam current 3 mA)
  - BPMs in 590 MeV beamline
  - Profile monitors in 590 MeV beamline
  - Radial Probes (new wire material, e.g., nano tubes)
- Power Supplies
  - On-Going and recurring project
  - New design with Silicon Carbide
- Vacuum System





Injector 2 -2025 prestudies -2030 strategic decision

inventory stock keeping

started -2026 strategic started -2030 started -2026 promising

running -2026











# Wir schaffen Wissen – heute für morgen

# My thanks go to Alps: 30 – 150 Million years Markus Schneider My Colleagues • Your attention! CERN