




*High precision measurement of  $\theta_{13}$ :*  
**Progress of Daya Bay reactor  
antineutrino experiment**

*Zhimin Wang, IHEP, China*  
*On behalf of Daya Bay collaboration*  
*NuFact'11, 1<sup>st</sup>~6<sup>th</sup>, Aug., Geneva*



# Daya Bay, China

Southern  
China




- Very powerful nuclear power complex:
  - Daya Bay: 2 X 2.9GW
  - Ling Ao I: 2 X 2.9GW
  - Ling Ao II: 2 X 2.9GW (will be online 2011)

**~17.4GW**

# The Daya Bay collaboration

Political Map of the World, June 1999



**~250 Collaborators**



Daya Bay, Nu

*39 Institutes, ~ 250 collaborators from China, USA, Hong Kong, Taiwan, Czech Republic and Russia*

# Outline



- Goal
- Daya Bay detectors
- Assembly & Installation & Test
- Current status & Schedule

# Goals

- Daya Bay's goal:
  - Precision measurement of  $\theta_{13}$  (if it's large)
  - Best sensitivity to  $\theta_{13}$  (if it's small)

## Reactor neutrinos:

- ✓ Clean signal
- ✓ No CP violation
- ✓ Negligible matter effects
- ✓ Free neutrinos!



# Systematic uncertainties

- **Few key factors for systematic uncertainties control:**
  - Near-Far measurement
  - **Identical Antineutrino detectors**
  - **Overburden**
  - **Active/passive multi Muon veto**
  - Detector swapping (optional)

Source of uncertainty		Chooz (absolute)	Daya Bay (relative)		
			Baseline	Goal	Goal w/Swapping
# protons		0.8	0.3	0.1	0.006
Detector Efficiency	Energy cuts	0.8	0.2	0.1	0.1
	Position cuts	0.32	0.0	0.0	0.0
	Time cuts	0.4	0.1	0.03	0.03
	H/Gd ratio	1.0	0.1	0.1	0.0
	n multiplicity	0.5	0.05	0.05	0.05
	Trigger	0	0.01	0.01	0.01
	Live time	0	<0.01	<0.01	<0.01
Total detector-related uncertainty		1.7%	0.38%	0.18%	0.12%

arXiv:hep-ex/0701029v1 CDR




Expt.	Thermal Power (GW)	Target mass Near/Far (tons)	Baseline Near/Far (Km)	Overburden Near/Far (m.w.e)	Signal rates Near/Far (per day)	Sensitivity to $\sin^2 \theta_{13}$ 90% C.L. 3years
Double Chooz	4.25 × 2 8.5	8.2/8.2	0.4/1.05	120/300	400/50	0.03
RENO	2.73 × 6 16.4	16/16	0.29/1.38	120/440	1280/114	0.02
Daya Bay	2.9 × 6 17.4	40,40/80	0.36, 0.48 / 1.99, 1.62	255, 290/910	840, 740 / 90	0.008

Daya Bay, NuFact'11

Numbers from A. Cabrera (DC) and K. K. Joo (RENO)'s talks in NEUTRINO 2010

# Antineutrino Detector (AD)

- 8 “identical”, 3-zone detectors in 3 experimental halls
  - 20t GdLS, 20t LS, 40t MO, separated by Acrylic Vessels
  - 192 8” PMTs in 8 rings, top and bottom reflectors
  - Precise target mass control
  - Low background
  - Low charge threshold
  - High precise calibration: auto scan and manual calibration
- No position reconstruction, no fiducial cut needed




$\Phi$  5m

Neutron capture  
time on 0.1%  
GdLS ~28us

# Muon veto detectors

- Multi Muon Veto detectors:
  - Active and passive Muon detectors
  - Two layers water Cherenkov detector
  - RPC detector on top
- Redundant veto system = highly efficient Muon rejection
  - $\epsilon > (99.5 \pm 0.25)\%$




- Water Cherenkov
  - Passive shielding against radioactivity and neutron at least  $\sim 2.5\text{m}$ ,
  - Two layers optically separated by Tyvek
- RPC on top
  - 4 layers: X or Y strip direction of each layer
  - Independent Muon tagging
  - Retractable roof above pool



# AD assembly

- The assembly of 2 pairs of ADs has been finished at **S**urface **A**ssembly **B**uilding (SAB) of Daya Bay; the 3<sup>rd</sup> pair is being assembled.
  - Installation in Clean room
  - Leakage check for all the flanges
  - Hardware test after installation: **Dry run** (results show later)




# Move SSV

(Stainless Steel Vessel,  $\Phi 5\text{m}$ )



# SSV sits in pit




Daya Day, Nufact 11

# Clean SSV inside



Daya Bay, NuFact'11

# Insert bottom reflector



Daya Bay, India Oct 11

# Insert outer AV

(Acrylic Vessel,  $\Phi 4\text{m}$ )



# Insert inner AV

( $\Phi 3\text{m}$ )



# Close outer AV lid






# Lift PMT ladder

(Photo Multiplicity Tube)



# Install top reflector



# Close SSV lid



Daya Bay, India Oct 11



# Install ACUs

(Auto Calibration Unit)




# Daya Bay near Hall Installation

RPC



Water pool

# Daya Bay near hall




- 1<sup>st</sup> pair of ADs has been put into the pool
  - Doing final installation
  - Water filling



**AD#1**



**AD#2**



# Online / slow control system ready

## Daya Bay near hall

- Online system ready
  - GPS clock system: uniform clock and time stamp for all the subsystems
  - Master trigger board for cross trigger (MTB)
  - Local trigger board for event trigger (LTB)
  - Front End Electronics (FEE): precise charge and relative hit time measurements
  - RPC electronics
  - DAQ
- Slow control working






**Installed electronics  
for Daya Bay near hall**

# AD Prototype (Beijing)




- 2005. Jan ~ 2008. Sept.
  - Validate detector design principle
  - Geant4 simulation
  - GdLS study: Long term stability
  - Effects of reflectors
  - Reconstruction algorithm
  - Gamma and neutron response: PuC tagged neutron
  - Electronics development / system commissioning



Data comparison with MC










Plutonium-Carbon neutron source





# AD Dry run (Daya Bay)


- All the subsystems test for Antineutrino Detector except liquid scintillator
- Goals:
  - Check hardware status for installation
  - System commissioning/debug, software/analysis development
  - Detector/Auto Calibration Units test
  - Detector identical study: differ <1%, and consistent with MC



AD3 & AD4 comparison with scintillator ball

# AD sensors


- To monitor:
  - Detector status, precise target mass
- The sensors:
  - 4 mineral oil temperature sensors at different depth
  - 2 Cameras for vision check after lid final closed
  - Lid sensors for temperature, tilt level, and liquid level of GdLS and LS by ultrasonic, capacitance, CCD etc



AD Lid  
Instrumentation





Daya Bay, NuFact'11



**Installed sensors in  
central overflow tank**


# Dry water pool test (Daya Bay near hall)

- Goals:
  - Check the hard ware status
  - LED calibration system
  - Cover light tightness
  - Basic detector performances



# GdLS/LS production

- ❖ All the Gd-LS and LS for the experiment have been mixed and stored




# GdLS/LS properties



❖ The liquid properties have been stable so far



Gd-LS ~5 months




LS ~1.5 months



Preliminary

Absorption monitoring

UV-vis of 4-ton Dry Run Gd-LS




# GdLS/LS filling


- 1<sup>st</sup> pair of ADs has been filled till now, preparing for 2<sup>nd</sup> pair
  - Auto liquid level control
  - Precise target mass control




Coriolis mass flowmeters < 0.1%



load cell accuracy < 0.02%




# Response of filled AD



- After the installation of filled AD#1 to Daya Bay near hall without water in pool, a short test was taken to check the detector response;
- The plot shows the measured charge spectrum with  $^{60}\text{Co}$  located at detector centre;
- All the systems working properly: detector, scintillator, online, slow control, and offline analysis

Co Raw Spectrum in DayaBayAD1 . Vertex cut.




# Schedule



**Daya Bay near hall**

Water filling now



**Ling Ao near hall**

Muon pool Tyvek and PMTs being installed




**Far hall**

Completing facilities installation

- Smooth progress: Daya Bay near hall
  - 1<sup>st</sup> filled pair of ADs fully completed
  - Muon system installation completed.
  - Water pool filling now.
  - Physics data ready this summer;
- Fall 2012:
  - All near/far halls physics ready

Daya Bay, NuFact'11






# Summary

- Daya Bay experiment can measure the mixing angle  $\theta_{13}$  to a great precision:  $\sin^2 2\theta_{13} < 0.01$  @ 90% C.L.
- Smooth progresses are going on for civil, detector assembly, filling, detector installation, test/commissioning;

Exciting time as rapidly increasing of test run/commissioning data!



# *Thanks*

