




KAHVE Laboratory Status and Plans


Aytul ADIGUZEL, On behalf of KAHVELab



KAHVE LABORATORY



TOBB ETÜ
Ekonomi ve Teknoloji Üniversitesi



- **KAHVELab** (Kandilli Detector, Accelerator and Instrumentation Laboratory) is a **particle detector, accelerator and instrumentation research laboratory** located in the Feza Gürsey Institute building at Boğaziçi University, Kandilli Observatory Campus.
- In addition to the host Boğaziçi University, our team consists of and closely collaborates with researchers from a number of institutes from all around Turkey.
- Build a number of particle detectors and electron and proton machines aiming keV and MeV energies, all with local resources.
- Also experimental particle physics research at CERN.

OUTLINE



Kandilli
Algıç
Hızlandırıcı
Ve
Enstrümantasyon

✱Algıç - Detector

- GETO - DWC
- Scintillator counters
 - Local & 3D printed
- Beam Measurements
- Scanning E. Microscope

✱Enstrümantasyon - Instrumentation

- Automation & Control
 - Electron Beam Lithography
- Readout & Digitization
- Software

✱Hızlandırıcı - Accelerator

- PROTON
 - 2 MeV Linac
 - 20 keV MD Ion Source
 - LEBT Line
 - Measurement BOX
 - Radio Frequency Quadrupole

ELECTRON

- 50 keV : Electron Gun
 - Electron Beam Welding
 - Electron Beam Hardening
- 1 MeV : Rhodotron

RF

- FM band
 - PSU
 - RF Transmission Line
- UHF band
 - PSU
 - RF Transmission Line

The Team




ACCELERATOR : Electrons

- ELECTRON
 - 50 keV : Electron Gun
 - Electron Beam Welding
 - Electron Beam Hardening
 - 1 MeV : Rhodotron

50 keV eGun


- Local design & manufacture
 - springboard project
- Tested a number of ideas
 - W, W(Th), LaB6, Disp cathodes
 - Al₂O₃, PEEK, Teflon insulators
 - HV platform insulation, safety
 - Remote control & monitoring via BT & WiFi
 - Magnet production: steerer & focusing coils
 - Automatic beam control: PID controller
 - PLC vs Labview
 - ...
- ✓ Stable operation
 - after lots of grounding work
 - ready for other projects



CST simulation



PSU & Vac. Rack






eGun applications

EBWelding


EBHardening





50 kV 40 mA
φ 100 x 200 mm
10⁻⁷ mbar
2 dof
~mm spot size





Radiographic Inspection



1 MeV Rhodotron




- Rhodotron starts with an eGun
 - sync e- with RF phase
 - multipass machine
- 1MeV machine design completed
 - dedicated sw being developed
- Construction ongoing
 - had some initial setbacks
 - vacuum tests to be completed by summer
- First beam in 2023



next...

- Finish Rhodotron
- EB microscope
- ebeam to air
- xray production




ACCELERATOR : Protons

- PROTON
 - 2 MeV Linac
 - 20 keV MD Ion Source
 - LEBT Line
 - Measurement BOX
- Radio Frequency Quadrupole

PROTON TESTBEAM at KANDILLI (PTAK)


- ✱ Proton beamline using an RFQ @ 800 MHz to accelerate 1 mA, 20 keV energy proton beam to **2 MeV**.

2MeV Linac



- Project Goals:
 - educating the next generation of accelerator physicists and engineers on the job
 - accumulating operational know-how
- Components are locally designed and manufactured in tandem with local companies.
- Secondary purpose of the project is to be a particle accelerator technologies test set up such as PIXE

Proton Testbeam At Kandilli (PTAK)



Parameters	Value	Unit
p extraction	20	kV
I_{peak}	1	mA
d.f.	< 20%	-
LEBT length	165	cm
RFQ length	98	cm
E_{out}	2	MeV
RFQ frequency	800	MHz

Proton Source

Magnetron

IS

Solenoid-1

Measurement Box

Solenoid-2


RFQ (virtually)

MAGNETRON circuit as microwave source with 2.45 frequency, 700W power and 50Hz repetition rate

PTAK IonSource 1 - EM MDIS

- Design with IBsimu
- Local construction
- 20 kV extraction voltage
- HV insulation via Teflon & Delrin
- Vacuum $\sim 10^{-7}$ without beam
- possible to control uWave power via magnetron power control
- possible to monitor transmitted and reflected power (not simultaneously)
- IS sols: current source + cooling water
- simulations show @1.3 mA current the RMS emittance is $0.0254 \pi \cdot \text{mm} \cdot \text{mrad}$
- stable operation in Q4 2021 ... Q1 2022

- IS upgraded to PM MDIS...




MDIS setup with electromagnets


PTAK IonSource 2 - PM MDIS

- Electromagnets are good but...
 - occasional sparks between solenoids & plasma chamber
 - need cooling (ohmic losses & the plasma chamber's heat)
- The permanent magnets are better:
 - can be kept under HV
 - do not require additional PSU
- 32 N40 type neodymium magnets


H_2 : 0.01 sccm
 V_E : 20 kV
 P : 4×10^{-5} mbar
 I_{ave} : 0.4 ... 1.5 mA



The PM-MDIS design with plasma chamber and electrode extraction part



The field measurement setup for the trial production




Magnetron circuit and microwave transmission waveguide system, hydrogen plasma visible in pink at the end of the waveguide line, and PM-MDIS operating under 20kV voltage.



The obtained beam image from the fluorescent screen placed at the end of the PM-MDIS system.






Faraday cup through the oscilloscope is found as 0.38mA. The difference is about 8% wrt HV PSU.



PTAK - Low Energy Beam Transport



DemirciPRO simulations:
 $1\sigma \sim 16\text{mm}$ @ $z=70\text{ cm}$ (noSC)



PTAK - LEBT - MBOX



Beam Diagnostics:



1 & 2 : emittance

2 : profile



3 : current

Beam Direction

- Placed between LEBT line magnets
- Used for beam measurements:
 - ✓ beam emittance (Pepper Pot Mask)
 - ✓ beam profile (Scintillator Screen)
 - ✓ beam current (Faraday Cup)








beam diameter (FWHM) : ~16 mm in x & y



PTAK - LEBT - Results

Sim. Measure



	Sim.	Measure
ϵ -norm [π mm.mrad]	0.031	0.029
α	-4.5	-18.9
β [mm/ π .mrad]	1.33	2.13
beam size(mbox) [mm]	14.8	15
beam size after s2 [mm]	1.9	2




df = 0.4
rep. rate: 50 Hz
I = 0.03mA

PTAK RFQ


	f_{res} (MHz)	E_{in} (MeV)	E_{out} (MeV)	L_v (cm)	$T_{\text{total/acc}}$ (%)	P_{RF} (kW)	V_v (kV)	S_f (Kp)	max d.f.	Q	vanetip r(mm)	bore radius r0(mm)
PTAK	800	0.02	2.0	98	90/30	48.6	33	1.39	2%	7036	1.392	1.392





- Module-0 from Copper produced to finalize the manufacture procedure
- Vacuum and EM tests completed
- mounting sensitivity: $18 \pm 1 \text{ um}$



**PTAK
RFQ
Vacuum**




**sealing with 3D o-ring
 1×10^{-6} mb achieved**









**PTAK
RFQ
EM**




beadpull setup



Alumina window coupler design and size image




all tuners are flush;
Fquadrupole : 796.05 MHz,
Q₀ : 6973 sim. & 5850 mea.



RF studies on:
surface roughness,
multipacting

PTAK Status & Plans




- ★ IS + LEBT installed, system being commissioned
 - ★ 2.45 GHz circulator being added, PMIS to be used now on
 - ★ Beam measurement station now fully automated
- ★ RFQ being manufactured
 - ★ Cu module-0 produced, tested.
 - ★ OFE-CU modules 1 & 2 production to start in coming weeks
 - ★ installation in 2022
 - ★ Vacuum, RF training in Q1 2023
 - ★ First beam in Q3 of 2023 depending on RF PSU status

ACCELERATOR : RF



- RF
 - FM band
 - PSU
 - RF Transmission Line
 - UHF band
 - PSU
 - RF Transmission Line

RF - FM band

- 2D (SFISH) & 3D simulations (CST) to calculate Q and Pwall
 - $f=107.5$ MHz, $Q \sim (60k) 45k$, $T_{fill} \sim 0.120$ ms
 - Simulations for 50kW total power
- Common RF source
 - merge two RF PSUs
- Status
 - all PSUs individually tested
 - will use coaxial transmission line
 - RF signal generator and preamplifier tested
 - remote control tested
 - need a good RF load
- Design being finalized
 - 3dB adder or feed cavity in two places
 - coupler(s) design being checked
 - multipactings verifications ongoing



30kW FM PSUs



LLRF tests

RF - UHF Band

800MHz RFQ

parmteq

Demirci

Q 7036 7190

capacitance (pF/m) 91 122

stored energy (mJ) 67.8 71.7

rf power loss (kW) 48.5 50.6

max surface field (MV/m) 36 =1.38KP


- Assuming 40% safety factor, max RF power needed ~ 70kW
- Assuming 30% RF PSU efficiency, 2% d.f. wall power needed = 4.7kVA
- Received 1+1 RF PSUs as donations
 - ➔ TH582 & TH382 Tetrodes + spares
 - ➔ max power delivered by TH582 in pulsed mode = 35kW.
 - ➔ RF power combination via a magic Tee
- PSUs are being rejuvenated





RF container



TH382



RF - UHF - Transmission Line




combined power to cavity via WG circulator



waveguide (T) combiner



- ✓ Signal generator
- ✓ SS preamplifiers (1.5 kW each)
- ✓ circulator, WGs & RF loads
- ✓ Magic Tee



Detector




*Algıç - Detector

- GETO - DWC
- Scintillator counters
 - Local & 3D printed
- Beam Measurements
- Scanning E. Microscope



ongoing projects


- EB microscopy
- TC vacuum gauge
- Beam monitor screen
- wifi/bt voltage/current controller
- wifi/bt anode & target current sensors







Instrumentation


for electron beamline



for proton beamline



MBOX from design to installation



mbox vacuum chamber



diagnostic station and pneumatic cylinders



mbox assembled



Vacuum Tests

**MBOX had good vacuum:
no beam: $1.3e-6$ mbar
with beam: $1.9e-5$ mbar**





29

Installation




by Dr. O. Ilday, UFOLab, Bilkent







a 3D printer is a very useful tool to have

copper coating





controlling the beam



- PLC
- LabView
- uController (arduino)

Hardware and software being developed to fine control the ebeam



possible applications:
ebeam lithography

summary & outlook

- by 2023 KAHVELab aims to have MeV level e- and p beams
 - mA current, in house designed
 - Maximal local construction,
 - Educational and application value
- Beams to test detectors, instrumentation & readout systems
 - gaseous detectors, scintillator detectors
 - locally develop, internationally deploy
- Looking for collaborations
 - qualified personpower always needed
 - know-how for building stuff, e.g. Al_2O_3 , Ferrites,...

backup slides

RFQ types

RFQ history

Vacuum sealing

Comparison with CERN HF RFQs