

ESRF Alignment Techniques and Results


D. Martin on behalf of the
ESRF Survey and Alignment Group

ALIGNMENT TOLERANCES

There were two key constraints for EBS

First respect the magnet (and other) alignment tolerances

Machine	Δx [μm]	Δy [μm]	Δz [μm]
Long. Varying field dipoles	1000	>100	>100
High gradient quadrupoles, Combined function dipoles	500	60	60
Medium gradient quads	500	100	85
Sextupoles	500	70	50
Octupoles	500	100	100




Maximum permissible error 2.5σ


... and second ensure the new machine was in the same place as the old machine to minimize disturbance to the functioning beamlines.

FIDUCIALISATION

For a magnet, we are interested in putting the magnet axis in the right place



But we cannot see the magnet axis




So we have to reference it with respect to external references that we can see.

ESRF FIDUCIALISATION

The original plan was for the magnet manufacturers to do the fiducialisation and shimming, but it was discovered that there were unacceptably large differences between measurements made at the ESRF* and by the manufacturers ...

So the ESRF Survey and Alignment group were asked to fiducialise all of the magnets ...



At the ESRF this is done on a magnet measuring bench using a stretched wire.

**The problem was with the manufacturers 3D measuring arm instruments...*

FIDUCIALISATION UNCERTAINTY


	Ux [μm]	Uy [μm]	Uz [μm]
Laser Tracker			
Wire position	13	15	18
Measurement	9	10	9
Repeatability	3	3	12
<i>Magnet measurements*</i>		4	4
<i>Magnetic Fiducialisation*</i>		19	24
<i>Magnet Shim Determination</i>			24
Total		19	34

* G. Le Bec ESRF

We combine all of these errors/uncertainties to determine the fiducialisation uncertainty contribution.


This is the first of several contributions to the overall alignment uncertainty...

There are several families of vacuum chambers:




Magnet pole positions
impose tight mechanical
tolerances ...

Low profile cross section






High profile cross section




BPM tolerances
~100 um...

BPM FIDUCIALISATION



GIRDER ASSEMBLY



Girders are installed and aligned in the horizontal plane

Magnets are installed on the girder 0.5 mm

Magnets are fine aligned 0.05 mm

Magnets are opened

Vacuum string is installed


BPMs aligned 0.1 mm

Magnets are closed

Fine magnet alignment
check and survey

Assembly was made at ESRF01 – a dedicated building

GIRDER ALIGNMENT UNCERTAINTY



USMN - Unified Spatial Metrology Network

Weight	Instrument (check if moving)	Weight	Point	Ma...	Ra...	Ux	Uy	Uz	Umag	Meas
<input type="checkbox"/>	1.000 0: SA A:-0 - Leica emScon AT403	<input checked="" type="checkbox"/>	DL2B_3_E	0.032	121%	0.007	0.008	0.008	0.013	01_345_
<input checked="" type="checkbox"/>	1.000 1: SA B:-0 - Leica emScon AT403	<input checked="" type="checkbox"/>	QF6B_SI	0.025	104%	0.006	0.007	0.007	0.012	01_3456
<input checked="" type="checkbox"/>	1.000 2: SA C:-0 - Leica emScon AT403	<input checked="" type="checkbox"/>	QF6B_EI	0.028	101%	0.006	0.007	0.007	0.012	01_3456
<input checked="" type="checkbox"/>	1.000 3: SA D:-0 - Leica emScon AT403	<input checked="" type="checkbox"/>	DL2B_2_E	0.021	98%	0.008	0.008	0.009	0.014	01_345_
<input checked="" type="checkbox"/>	1.000 4: SA E:-0 - Leica emScon AT403	<input checked="" type="checkbox"/>	DL2B_3_S	0.027	95%	0.007	0.008	0.008	0.013	01_345_
<input checked="" type="checkbox"/>	1.000 5: SA F:-0 - Leica emScon AT403	<input checked="" type="checkbox"/>	SD1B_EI	0.032	95%	0.008	0.009	0.009	0.015	01_345_
<input checked="" type="checkbox"/>	1.000 6: SA G:-0 - Leica emScon AT403	<input checked="" type="checkbox"/>	DL2B_4_E	0.024	93%	0.007	0.008	0.008	0.013	01_345_
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	QF6B_SI	0.021	89%	0.007	0.009	0.008	0.014	01_3456
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	SD1B_SE	0.027	88%	0.008	0.009	0.008	0.015	01_345_
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	QF6B_EE	0.031	88%	0.008	0.009	0.007	0.014	01_3456
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	CH6-BPM04-P2	0.023	87%	0.009	0.011	0.010	0.018	___45_
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	DL2B_1_E	0.025	85%	0.009	0.009	0.009	0.016	_1_345_
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	DL2B_1_S	0.025	85%	0.008	0.009	0.009	0.015	_0_345_
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	DL2B_5_E	0.027	81%	0.007	0.007	0.007	0.013	01_345_
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	DL2B_4_S	0.021	81%	0.007	0.007	0.007	0.012	01_345_
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	DQ1B_SE	0.020	78%	0.009	0.011	0.009	0.016	___3456
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	DQ1B_EE	0.020	75%	0.007	0.009	0.008	0.014	_0_345_
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	G128-SI08	0.020	72%	0.008	0.009	0.009	0.016	___3456
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	QF6B_SE	0.017	72%	0.006	0.007	0.007	0.012	01_3456
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	QD5B_SI	0.023	71%	0.008	0.009	0.008	0.014	01_345_
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	G128-SE07	0.022	70%	0.010	0.010	0.011	0.018	012_
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	QF6B_SE	0.022	69%	0.008	0.009	0.008	0.014	01_3456
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	QF6B_EI	0.020	68%	0.008	0.009	0.007	0.014	01_3456
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	QF6B_EE	0.018	67%	0.007	0.007	0.007	0.012	01_3456
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	QD5B_EI	0.016	65%	0.008	0.009	0.008	0.014	01_345_
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	SD1B_SI	0.021	65%	0.009	0.009	0.009	0.016	01_345_
<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	QD5B_SE	0.014	65%	0.008	0.009	0.009	0.015	01_345_

Instrument Solution Reference Frame
 Instrument Frame Working Frame

Auto Solve, Trim Outliers, and Re-Solve
 Do this automatically

Uncertainty Field Analysis
 Samples: 300
 Time Limit: 4.0 min.

Reporting
 Error Uncertainty

Apply Results
 Create composite group: USMN Composite
 Create point uncertainty fields
 Update composite point offsets
 Apply instrument and point group transforms in SA
 De-activate measurements weighted to zero

No scale bars defined.

Summary
 Point Error: Overall RMS = 0.009, Average = 0.007, Max = 0.032 'SD1B_EI'
 System Solution Time: 0.3 sec, Robustness Factor = 0.002318, Unknowns 24, Equations 762
 Uncertainty Magnitude: Average = 0.016, Max = 0.023 'CH5-1'
 68.2% Confidence Interval (1.0 sigma), Samples: 300, WCF: GNet:Gref
 Uncertainty Analysis Time: 39.8 sec

	Ux [μm]	Uy [μm]	Uz [μm]
Measurements	6	7	6
Difference to nominal	126	24	25
Overall uncertainty		16	17
Total	126	30	31

EBS INSTALLATION IN THE TUNNEL

Plates Pre-Tracing

Plates Setting Out

Plates Alignment

Plates Control

Girder Pre-Alignment

Girder Fine-Alignment

Girder Control

Girder Touch-ups



Girder Re-control

DQ2 Alignment

DQ2 Control

HLS Installation

STORAGE AND TRANSPORT



Storage place	Quantity	Comments
G.L.D.	90	Girder direct access with a crane
ESRF 01	9	End of the assembly process
Chartreuse hall	30	Non standard girders + ID24 entry point

Source: Mini-Workshop on Girders and Alignment – 10-11 May 2021- Thierry Brochard (ESRF)

INSTALLATION




Girders were:

- transported from storage on a truck,
- unloaded using a crane,
- transported to a gantry,
- lifted into the tunnel using the gantry, and
- transported to their final position with the transport module.

EFFECT OF STORAGE, TRANSPORTATION, INSTALLATION AND BAKEOUT

After the installation and initial alignment in the tunnel all of the girders were remeasured like they were during in ESRF01. This was done again after the bakeout was finished in the tunnel.




The magnet positions were then adjusted onto the magnet positions measured at ESRF01.

Survey	Uy [μm]	Uz [μm]
ESRF01 (see previous slide)	16	17
After transport (3D adjustment on ESRF01)	17	20
After bakeout (3D adjustment on ESRF01)	19	21


These results suggest the effect of transport was $\sim 10 \mu\text{m}$ – and the effect of bakeout on the alignment less than that ...

NOVEMBER 2019 – AFTER FINAL ALIGNMENT - ERROR

dR magnet center errors with respect to EBS nominal values




dZ magnet center errors with respect to EBS nominal values




NOVEMBER 2019 – AFTER FINAL ALIGNMENT - RESIDUALS

dR magnet center residuals with respect to a smooth curve




$U_R = 52 \text{ } \mu\text{m}$
 $U_Z = 30 \text{ } \mu\text{m}$



dZ magnet center residuals with respect to a smooth curve



28 NOVEMBER 2019 AT 19hrs FIRST TURNS IN EBS-SR




Recall the second major constraint – put the machine back where the old machine was...




RMS Y [mm]	RMS Z [mm]	RMS Direction [urad]
0.32	0.22	8

IMAGE OF PHOTON BEAM ON ID09 JANUARY 30 2020



Old SR
26 November 2018




EBS
30 January 2020

...The EBS X-ray beam at distances varying from 45 to 160m was found within fractions of millimetres from its position in December 2018...


E-mail Francesco Sette to all staff on 31/01/2020

MARCH 2022 – 28 MONTHS AFTER FINAL ALIGNMENT

srMar22 dR Position (St Dev = 0.063 mm)



srMar22 dZ Position (St Dev = 0.062 mm)



$U_R = 63 \text{ um}$ was 53 um in 11/2019
 $U_Z = 62 \text{ um}$ was 30 um in 11/2019



TEMPORAL AND SPATIAL DEFORMATION - GENERAL SITE MOVEMENTS

Every site is different, has different site movement signatures and evolves differently.

Recall smoothing:

$U_R = 63 \text{ um}$ was 53 um in 11/2019



$U_z = 62 \text{ um}$ was 30 um in 11/2019



TEMPORAL AND SPATIAL DEFORMATION – FLOOR AND GIRDER MOVEMENTS



Generally magnets are installed on supports (girders) that are themselves installed on a concrete floor ...

Concrete floors are subject to thermally induced movements – temperature variations over the day and year





A number of experiments have been made at the ESRF to study this ...

TEMPORAL AND SPATIAL DEFORMATION – FLOOR AND GIRDER MOVEMENTS



TEMPORAL AND SPATIAL DEFORMATION – FLOOR AND GIRDER MOVEMENTS

Bending movements vary between 0 and 700 μm over 6 months depending on time and position



1hr	2hrs	4hrs	8hrs	12hrs	24hrs	48hrs	1wk	2wks	4wks	2mo	4mo	6mo
1	2	3	6	9	13	19	43	74	138	270	470	655
1	1	3	5	7	10	15	34	59	110	217	374	521
0	1	2	4	5	7	11	24	42	77	155	266	365
0	1	1	2	3	4	6	12	21	40	79	137	187
0	0	0	1	1	1	2	5	8	15	30	54	70
0	0	0	0	0	0	0	-1	-2	-2	-3	-3	-7
0	0	0	0	0	0	-1	-1	-2	-3	-6	-10	-24
0	0	0	0	0	0	0	0	1	1	2	2	5

Again every site and floor is different, but the principle is the same...

TEMPORAL AND SPATIAL DEFORMATION – FLOOR AND GIRDER MOVEMENTS

Recently experiments were made at the ESRF to create a closed vertical ID angle bump using girder movements.

The experiment worked well and it was shown that ID bumps using the girders are both feasible and achievable


However, during the experiment, we found there were coupled parasitic horizontal movements. These movements were observed both in the beam and with capacitive captors installed to measure them.

There were both one-off and repeatable movements.

It is important to note that the girders were tested before installation and parasitic coupled movements were not observed in unconstrained girders.

It is postulated these movements are constraints introduced into the rigidly fixed girder as a result of small movements of the floor similar to those measured in the previous slides.

We would like to do more tests to see if this is a reasonable mechanism to explain what we have observed.



MANY THANKS FOR YOUR ATTENTION

