

# HIE-ISOLDE (High Intensity and Energy) project

## Protection of superconducting solenoids



MPE work shop – December 14, 2010

G.J. Coelingh TE-MPE-CP

# Overview

- HIE-ISOLDE Project
  - Overview, layout, work structure, QPS budget
- Circuits to protect
- Quench Detection
  - Magnet, Current Leads
- Energy Extraction
- Resources

# Scope of HIE-ISOLDE





## Energy Upgrade:

The HIE-ISOLDE project concentrates on the construction of the SC LINAC and associated infrastructure in order to upgrade the energy of the post-accelerated radioactive ion beams to **5.5 MeV/u in 2013** and **10 MeV/u by 2014/2015**

## Intensity Upgrade:

The **design study** for the intensity upgrade, also part of HIE-ISOLDE, **starts in 2011**, and addresses the technical feasibility and cost estimate for operating the facility at **10 kW** once LINAC4 and PS Booster are online. **The 30 kW option (SPL beam) will be studied at a later stage**

# HIE-ISOLDE Layout



Steering Committee

International Advisory Panel

1. Project Management

2. Linac Systems

3. Infrastructure & Integration

4. Installation & Commissioning

5. Target Study

6. Target Area and Class-A Lab Integration

- 2.1 Cavity RF BE/RF
- 2.2 Cavity Design manufacturing EN/MME TE/VSC
- 2.3 Beam dynamics BE/RF-ABP
- 2.4 Cryomodules TE/MS EN/MME
- 2.5 Beam Instrumentations BE/BI
- 2.6 SC Solenoid TE/MS
- 2.7 Beam transfer line (magnets) TE/MS
- 2.8 Linac Integration EN/MEF
- 2.9 Vacuum TE/VCS
- 2.10 Survey BE/ABP

- 3.1 Civil Engineering GS/SEM
- 3.2 Integration EN/MEF
- 3.3 Cooling ventilation EN/CV
- 3.4 Electrical systems EN/EL
- 3.5 Cryogenic system TE/CRG
- 3.6 Power converters TE/EPC
- 3.7 Industrial Control system EN/ICE
- 3.8 Beam Control system BE/CO
- 3.9 Interlocks TE/MPE

- 4.1 Single cavity test BE/RF
- 4.2 Cryomodule test BE/RF
- 4.3 Transport & Handling EN/HE
- 4.4 Planning & Installation EN/MEF
- 4.5 Linac commissioning BE/RF-OP

- 5.1 Target design EN/STI-HE
- 5.2 Front Ends EN/STI TE/EPC-ABT
- 5.3 Beam Diagnostics BE/BI

- 6.1 Layout upgrade EN/MEF
- 6.2 Cooling and ventilation EN/CV
- 6.3 Electrical systems EN/EL
- 6.4 Vacuum TE/VCS
- 6.5 Survey BE/ABP
- 6.6 Civil engineering GS/SEM
- 6.7 LL Control system EN/STI

- 1.1 Project Leader – Y. Kadi (EN/HDO)
- 1.2 Project Safety Coordinator – A.P. Bernardes
- 1.3 Technical Coordinator – M. Pasini BE/RF
- 1.4 Design Study Coordinator – R. Catherall EN/STI
- 1.5 Budget and Planning – E. Delachenal EN/GMS
- 1.6 Administration – E. Cochet EN/GMS

8. Safety

- 8.1 Safety Coordinator GS/DI
- 8.2 Radioprotection DG/SCR
- 8.3 Access System GS/ASE
- 8.4 Access System GS/ASE


7. Injection & Beam distribution

- 7.1 Off line separator EN/STI
- 7.2 Separator areas EN/STI
- 7.3 Experiment Hall EN/MEF
- 7.4 Beam lines BE/ABP

# Work Breakdown Structure



# HIE-ISOLDE material budget



Title	PPA	Work Package	Code	Dep.	Group	Total Request
<b>HIE-ISOLDE Linac (M. Pasini BE/RF)</b>						
SC Cavity RF	EIS-PRJ	WP2.1		BE	RF	2'320
SC Cavity Design & Manufacturing	EIS-PRJ	WP2.2.1	55601	EN	MME	3'700
SC Cavity Sputtering	EIS-PRJ	WP2.2.2		TE	VSC	553
SC Cavity Sputtering (IS)	EIS-PRJ	WP2.2.2		TE	VSC	355
SC Cavity Test	EIS-PRJ	WP4.1		BE	RF	-
SC solenoids						656
Cryomodules						4'600
Cryomodules (MME)	EIS-PRJ	WP2.4.1	55602	EN	MME	413
Cryomodule Test	EIS-PRJ	WP4.2	99159	TE	MSC	-
Beam Dynamics	EIS-PRJ	WP2.3		BE	RF	-
Beam Instrumentations	EIS-PRJ	WP2.5		BE	BI	1'450
Beam Transfer Line	EIS-PRJ	WP2.7		TE	MSC	1'710
Linac Integration/Installation	EIS-PRJ	WP2.8 & WP4.4	55603	EN	MEF	80
Linac Commissioning	EIS-PRJ	WP4.5		BE	RF	-
Vacuum	EIS-PRJ	WP2.9		TE	VSC	1'400
Survey	EIS-PRJ	WP2.10		BE	ABP	201
<b>Total</b>						<b>17'638</b>

# HIE-ISOLDE Schedule


2008				2009				2010				2011				2012				2013				2014				2015	
Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2

Planning HIE-ISOLDE kick-off meeting

## Important milestones for Energy Upgrade:

- Start project Jan 1<sup>st</sup> 2010
- Start construction by Jun 2010
- Launch Procurement of Cryogenics equipment:
  - ✓ Market survey by Mar 2010
  - ✓ Tech. Specific. By May 2010
  - ✓ Finance Committee by Sep. 2010
- Cryogenics installed and commissioned Jun 2013
- High energy beam line (5.5 MeV/u) installed by Oct 2013
- 10 MeV/u Linac installed by 2014/2015
- Commissioning organized inline with L4 and PSB commissioning

April 2010 planning - to be updated




Cold test of first cryo-module in April 2013

# Circuits

- 8 individually powered circuits with S.C. solenoids of 130 mH each
- Nominal current 450 A – Stored Energy 13 kJ
- Powering scheme tbd. Grounding, Series/parallel extraction
- Protection delay tbd. This will determine EM or SSt switch






# Quench Detection

- Magnet Detection based on existing digital LHC – SAM detectors
  - 4 redundant voltage taps on layer 0, layer 8, layer 12 and layer 20.
  - First tap on the top and the redundant at the bottom.
    - The difference will be 0.5 turns which should be negligible for the detection system

# Quench Detection & Controls




- Lead detection depending on lead type but most likely conventional copper model will be used. Tbd.
- Controls/Data transfer to be determined –  
Field Bus or Ethernet?
  - Valid for Detection and Extraction
- Interlocks – PC-QPS-EE-PIC. Tbd.

# Strategic Plan for EE


- Solid State Switch development recently started
  - Goal: Prototype by May/June 2011
  - Challenge to finish series production before 2.5 years from now
- In parallel: upgrade existing LHC 600 A EE system; improvements from exploitation/maintenance points of view
  - 10 systems can be delivered within 2 years
- If choice will be Solid State - use EM systems as spares for LHC

# EE: Solid State or EM

- Solid State Switch: Semi-conductor IGCT
  - Integrated Gate Commutated Thyristor
  - Fast and “maintenance” free vs  
Forward Losses – water cooling
- Electro-Magnetic circuit breaker
  - very low forward losses vs  
maintenance (preventive & corrective)




Two, 600A extraction systems in a common rack



IGCT and its integrated drive electronics.





Thank you for your attention