

# WP7 HFM Status

**F. Kircher** (CEA Saclay) **and Gijs de Rijk** (CERN)

EuCARD 2<sup>nd</sup> Annual meeting

CNRS, Paris, 11-13 May 2011

# WP7 High field magnets



- Task 1: Coordination and communication
- Task 2: Support studies
- Task 3: High field model
- Task 4: Very high field dipole insert
- Task 5: High Tc superconductor link
- Task 6: Short period helical SC undulator

# Task 1: Coordination and communication (1)



After the kick-off in February 2009, 7 collaboration meetings were held (at CEA, CERN, PWR, UNIGE and CNRS Grenoble)

Task 1 activities in the last months:

- Semestriels reports
- Organization of the collaboration meetings
- external review 20-21 January 2011

Plans for next semester:

- Organize the next collaboration meetings
- Organize the dipole mini-reviews

# Task 2: Support studies (1)



Macej Chorowski & Jarek Polinski (PWR)


PWR, CEA, CERN

[ 7.2.1 minor delay, personnel: +, material - ]

[ 7.2.2 task on schedule, personnel: +, material - ]

## 7.2.1 Radiation studies for insulation and impregnation (PWR)

- Future and upgraded accelerators need radiation hard magnets. Insulators in the coil are one of the sensitive components
- LHC inner triplet type dose (total of all types) : 50 MGy, to be done with electron beam of a few MeV
- Test at Soltan have resulted in the feasibility of irradiating with a 6 MeV accelerator structure the thermal and electrical sheets in reasonable time: 12 working days for 11 samples in parallel. It should be possible to irradiate the 52 samples during 3 months.
- For the mechanical samples (6x6x20 mm) it is not possible to do this as the beam spot is too small and the penetration too little: PWR is working on designing smaller samples so that it will fit with the 6 MeV beam



# Task 2: Support studies (2)



EuCARD WP 7: HFM Task 2 Start = 01/04/09	1st year				2ed year				3td year				4th	
	Q1 3	Q2 6	Q3 9	Q4 12	Q5 15	Q6 18	Q7 21	Q8 24	Q9 27	Q10 30	Q11 33	Q12 36	Q13 39	Q14 42
				EuC Rep				EuC Rep				EuC Rep		
<b>Sub-task 2.1: Radiation resistance certification</b>														
Methodology for coil radiation resistance certification								M(24)						D(42)
Determination of radiation types and doses	IM													
Determination of irradiated sample tests scope						IM								
Selection of the Institute capable of the irradiation						IM								
Test samples production														
Irradiated sample test set-ups preparation								IM						
Sample irradiation														IM
Irradiated sample tests (mech+elec+therm)														IM

Achieved  
report from October  
2010

SOLTAN Institute  
Warsaw  
remark: not fulfilling  
all requirements  
resulting from the  
report

Conceptual design of  
irradiation cryostat  
ready

Studies

Manuf

Tests

WP - Work Package Report

M - Mileston

IM - Inter. Milestons

D - Deliverables

EuC - EuCARD Report

# Task 2: Support studies (3)




## 7.2.2 Thermal models and design (CEA, CERN, PWR)

At CEA and CERN models have been build to simulate the thermal behaviour of the Fresca2 magnet (task 3 dipole).

This has been used to calculate 2 cases:

- Steady state losses at 1.9 K and 4.2 K
- Cool down scenarios


A milestone report has just been finished, it will be released in the next 2 weeks




# Task 2: Support studies (4), Modeling of thermal process in the magnet during ramp rate – 2 D steady state model



## Maximum temperature difference in magnet at different bath temperature and heat load



	Name	Unit	Value				Critical temperature rise
			0,2	1,0	5,0	10,0	
Heat load	Total	W	0,2	1,0	5,0	10,0	
	Unit	W/m	0,1	0,5	2,6	5,3	
	Volumetric	W/m <sup>3</sup>	4,3	21,8	108,9	217,7	
Maximum temperature rise	@ 1,9	K	0,231	1,053	2,906	3,951	<b>6,1</b>
	@ 4,2	K	0,066	0,354	1,344	2,197	<b>3,8</b>
			CUDI Model	Homogenous model			




Temperature rise in the magnet as a function of heat load

# Task 2: Support studies (5), Modeling of cool-down process – 2 D transient model -




- Temperature differences in the magnet should be minimized to avoid peak stresses ( $< 20$  K)
- Cool-down from 300 K  $\Rightarrow$  80 K with 16 bar He gas in tube in contact with outer cylinder
- Cool-down from 80 K  $\Rightarrow$  4.2 K with He gas injected in the cryostat
- A 4 day cool-down from 300 K  $\Rightarrow$  4.2 K looks preferable



Evolution of maximum  $\Delta T$  within the magnet structure



## Task 2: Support studies (6), Thermal test of TGPAP - DETD



Assembled "drum" apparatus in the cryostat

The numbers and thicknesses of tested samples

Sample	D1	D2	D3	D4
	$\mu\text{m}$	$\mu\text{m}$	$\mu\text{m}$	$\mu\text{m}$
Thickness (average value)	16,0	28,9	40,0	61,1



Sample glued to the holder flange

- The heat conduction properties of virgin and irradiated samples of various insulator schemes are to be measured (continuation of NED)
- Work done at CEA with in the NED cryostat and at PWR in a new cryostat
- Measurements have just started

# Task 3: High field model (1)




Jean-Michel Rifflet (CEA)

CEA, CERN, PWR

[ task delayed by 9 months, personnel: =, material - ]

- **Objective:** Design, build and test a 1.5 m long, 100 mm aperture dipole with a design field of 13 T, using  $\text{Nb}_3\text{Sn}$  high current Rutherford cables.
- Magnet design is mostly finalized, only the coil connections are to be designed.
- Drawing of the structure are ready, procurement of magnet components to start next weeks
- Tooling tests and design has started winding tests, reaction tests, etc)
- Strand procurement contracts placed for the pilot production ( 2 x 15 km, = 2 double pancakes). Full production order to be placed this summer (45 km). Deliveries to be complete by end 2012.
- Test of the magnet by Dec 2013



# Task 3: High field model (2)



- The ESAC high field dipole design review was held at CEA Saclay, on January 20-21, 2011
- Review committee:
  - Giorgio Ambrosio (Fermilab)
  - Shlomo Caspi (LBNL)
  - Pasquale Fabricatore (INFN Genova)
  - Yukikazu Iwasa (MIT)
  - Tatsushi Nakamoto (KEK)
  - Lucio Rossi (CERN)
- Recommendations (selection only)
  - Wind full-scale dummy (copper) coils to test tooling and procedures
  - Wind full-scale dummy (underperforming) Nb<sub>3</sub>Sn coils to check fabrication process and conductor behavior)
  - Take into account all deviations from ideal geometry and imperfection of various systems, to check how much the design is sensitive to tolerance, discrepancies and defects

# Task 3: High field model (3)




- Un(der)-addressed issues:
  - Insulation material and thickness;
  - Coil dimensions after winding (ceramic binder);
  - Dimensions of reaction and impregnation cavity (how to accommodate conductor expansion?);
  - Impregnation materials; Splice design;
  - Quench heaters (type, location, power requirement);
  - Instrumentation plan (strain gauges, voltage taps, thermometers, field sensors)
- Schedule
  - The overall schedule is very aggressive and success oriented.
  - additional steps (dummy coils, ...) may induce delays, but increase considerably the probability of success
  - Focus on FRESCA2 magnet: (skip time and resources consuming accelerator features)
  - Plan a series of decision points and small readiness reviews
  - Speed up the conductor procurement

# Task 3: High field model (4)



- A resource loaded planning was made including all activities (design, tooling, procurements, tests etc.)
- The first magnet can be tested end 2013



HFM-WP7 Status, FK & GdR, 11 May 2011

11/05/2011

GdR

EuCARD Task 3 High field dipole							2011																																																2012																																																2013																																																2014																																															
program	Activity	person	code	material resources (KCHF)	personnel resources (PM)	begin date	end date	month																																																																																																																																																																																														
Short Model Coil		CERN				1-Jan-11	31-Dec-11																																																																																																																																																																																															
Task 3 management		CEA		80	29.6	1-Jan-10	31-Dec-10																																																																																																																																																																																															
magnet detailed design		CERN		0	3.0	1-Feb-11	31-May-11																																																																																																																																																																																															
magnet engineering		CEA		0	17.6	1-Jan-10	31-Dec-10																																																																																																																																																																																															
Quench protection		CEA		0	0.4	1-Jan-11	28-Feb-11																																																																																																																																																																																															
Thermal design		CEA/CERN		0	1.7	1-Jan-11	31-Mar-11																																																																																																																																																																																															
Instrumentation and connection design		CERN		10	2.2	1-Mar-11	30-Nov-11																																																																																																																																																																																															
Winding tooling design and tests		CEA		70	6.2	1-Apr-11	31-Jan-12																																																																																																																																																																																															
Reaction tooling		CEA		100	9.1	1-Apr-11	31-Mar-12																																																																																																																																																																																															
Impregnation tooling		CERN		50	1.3	1-Jan-11	30-Sep-11																																																																																																																																																																																															
materials choice / quality control		CEA/CERN		0	6.1	1-Mar-11	31-Dec-11																																																																																																																																																																																															
sample tests		CEA		0	3.3	1-Mar-11	31-Dec-11																																																																																																																																																																																															
structure manufacturing		CERN		100	2.0	1-Jan-11	31-Jul-11																																																																																																																																																																																															
structure LN2 test		CERN		0	3.5	1-Jul-11	30-Sep-11																																																																																																																																																																																															
Conductor procurement & qualification 2x15km		CEA/CERN		320	5.1	1-Jan-11	31-May-12																																																																																																																																																																																															
Conductor procurement & qualification 45km		CEA		40	4.5	1-Apr-11	31-Dec-12																																																																																																																																																																																															
cabling for 1 coil set		CERN		30	3.5	1-Jan-11	31-Dec-11																																																																																																																																																																																															
Vertical test station construction		CERN		250	2.0	1-Jan-11	31-Jul-12																																																																																																																																																																																															
Furnace		CERN		578	3.5	1-Jan-11	31-Jan-12																																																																																																																																																																																															
Cu coil manufacturing		CEA		115	22.4	1-Nov-11	31-Mar-12																																																																																																																																																																																															
1st CEA SC double pancake manufacturing		CEA		0	15.2	1-Apr-12	31-Jul-12																																																																																																																																																																																															
1st CERN SC double pancake manufacturing		CERN		90	7.6	1-Aug-12	31-Dec-12																																																																																																																																																																																															
test 1st double pancake in structure at LHe		CERN		150	9.6	1-Nov-12	28-Feb-13																																																																																																																																																																																															
2nd CEA SC double pancake manufacturing		CEA		0	5.4	1-Mar-13	30-May-13																																																																																																																																																																																															
2nd CERN SC double pancake manufacturing		CERN		90	3.0	1-May-13	31-Jul-13																																																																																																																																																																																															
assembly first set of coils in structure		CERN		150	3.8	1-Apr-13	30-Sep-13																																																																																																																																																																																															
First cold test with first coil set		CERN		50	8.6	1-Oct-13	31-Dec-13																																																																																																																																																																																															
3rd CEA SC double pancake manufacturing		CEA		0	5.4	1-Jan-14	31-Mar-14																																																																																																																																																																																															
3rd CERN SC double pancake manufacturing		CERN		90	3.0	1-Feb-14	30-Apr-14																																																																																																																																																																																															
4th CEA SC double pancake manufacturing		CEA		0	5.4	1-May-14	31-Jul-14																																																																																																																																																																																															
4th CERN SC double pancake manufacturing		CERN		90	3.0	1-Jun-14	31-Aug-14																																																																																																																																																																																															
assembly second set of coils in structure		CERN		150	3.8	1-Sep-14	31-Oct-14																																																																																																																																																																																															
Cold test with second coil set		CERN		50	8.6	1-Nov-14	31-Dec-14																																																																																																																																																																																															

# Task 4: Very high field dipole insert (1)



Pascal Tixador (CNRS Grenoble-INPG )

CNRS, CEA, KIT,  
INFN, TUT, UNIGE, PWR

[ task on schedule, personnel: =, material - ]

- **Objective:**

Design and realization of a high temperature superconductor (HTS) very high field dipole insert (6-7 T), which can be installed inside the 13 T Nb<sub>3</sub>Sn dipole of task 3

NB: test of the two dipoles together is not part of the present EuCARD contract but will be done nevertheless...

Sub tasks:

7.4.1 Specification, characterization and quench modelling


7.4.2 Design, construction and test of solenoid insert coils

7.4.3 Design, construction and test of dipole insert coils

# Task 4: Very high field dipole insert (2)

## Specification, characterization and quench modeling

- The conductor has been selected: YCBO 12 mm width
  - The Bi-2212 option is parked for the moment due to  $I_c$  performance, the fragile nature of the strands and the additional difficulty of the reaction.
- The conductor characterization is in progress a model for the conductor performance has been made.
- Quench models (TUT and INFN-LASA) have been made and are being used to study the quench development and protection schemes.
- The quench models will be 'calibrated' with the solenoid tests coils
- Important subject for quench study is the coupling with the dipole outsert





# Task 4: Very high field dipole insert (3)



Test solenoids in YBCO tape

- Several have been made
- On the learning curve to make coils from YBCO
  - Conductor damage during handling
  - Connections splice problems
- The latest coils was much improved
- About 6 months delay to produce working coils
- Test cryostat existing
  - Tests in 20 T background fields at CNRS Grenoble and KIT









# Task 4: Very high field dipole insert (4)



- Conceptual design of the insert done.
- Winding pack in 6 flat pancakes of 12 mm wide YBCO tape using a total length of 1770 m
- Insert will be mechanically independent (outer diameter 99 mm , dipole aperture 100 mm)
- Support tube 3 mm thickness + stainless steel structural part ( e beam welded )
- Total Horizontal force  $\sim 1000$  t (at 6 T insert field in 14 T oursert field from the dipole)



3D geometry

# Task 5: High Tc superconducting link



Amalia Ballarino (CERN)

CERN, COLUMBUS, BHTS, SOTON

[ **task ahead of schedule**, personnel: =, material = ]

- Conceptual design done of a novel 600 A twisted-pair cable made from different High Temperature Superconducting tapes ( $\text{MgB}_2$ , Y-123 and Bi-2223)
- assembled prototype cables of about 2 m length successfully tested at CERN at 4.5 K in a straight configuration
- Southampton University has designed and assembled a cryogenic test station to test cables of 2 m length in He gas in a variable temperature range (from 5 K to 70 K). Tests have already been performed on a 600 A twisted pair Y-123 cable
- Columbus has manufactured and delivered to CERN 1200 m of  $\text{MgB}_2$  tape, and worked on the optimization of the joints between  $\text{MgB}_2$  tapes
- CERN is now working on the assembly of a 5 m long prototype link, which is planned to be tested at Southampton University before the end of 2011
- The HTS material needed for the 20 m long prototype has already been procured by CERN. A cabling machine is being designed and assembled at CERN for the production of long twisted pair electrically insulated cables.

# Task 6: Short period helical undulator (1)



Short period undulator for the ILC positron source

Jim Clarke (STFC-DL)

STFC (DL and RAL)

Period 11.5 mm , field  $>1$  T

Aim :

- fabricate and test a short helical undulator prototype using Nb<sub>3</sub>Sn wire.
- With: 11.5 mm period and winding bore of 6.35 mm.
- Nb<sub>3</sub>Sn usage for high current density and large thermal margin to go higher than the 1.15 T achieved for Nb-Ti


Primary challenges:

- The Nb<sub>3</sub>Sn conductor
- Nb<sub>3</sub>Sn insulation system (compatibility with heat treatment at 650C)
- Thin insulation (high current density).

## Task 6: Short period helical undulator (2)




- First test winding of wiggler done
- Small issues seen with the forming of the helical groove in the steel piece: solvable problem
- The conclusion is that with 0.5 mm diameter wire one can wind a helical wiggler with a correct precision and impregnate it



# Task 6: Short period helical undulator (3)



- Low field (<5 T)  $I_c$  measurements were done at KIT for the selected OST 0.5 mm RRP strand
- The strand shows at low field instabilities
- These instabilities are linked to the high  $J_c$  performance of the strand at high field.
- A different strand has to be found: with a lower  $J_c$
- Open question: will a stable  $Nb_3Sn$  strand used at these field give a higher field than a  $NbTi$  strand ?
- Deliverable date will depend on the strand availability



# Deliverables and Conclusions



Mile-stone	Description/title	Nature	Delivery month	Comment
7.1.1	1 <sup>st</sup> annual HFM review meeting	O	M12	
7.1.2	2 <sup>nd</sup> annual HFM review meeting	O	M24	
7.1.3	3 <sup>rd</sup> annual HFM review meeting	O	M36	
7.1.4	Final HFM review meeting	O	M48	
7.2.1	Methodology for the certification of radiation resistance of coil insulation material	R	M24	
7.2.2	Preliminary heat deposition model for a dipole Nb <sub>3</sub> Sn model magnet	R	M12	publication on web
7.2.3	Engineering heat deposition model for a dipole Nb <sub>3</sub> Sn model magnet	R	M24	publication on web
7.3.1	Dipole Nb <sub>3</sub> Sn coils finished	D	M36	2 coils ready for mounting
7.3.2	Dipole Nb <sub>3</sub> Sn model magnet finished	D	M42	Ready for cold test
7.4.1	HTS conductor specifications for insert coils	R	M12	
7.4.2	Two HTS solenoid insert coils	D	M24	
7.5.1	Final design report HTS link	R	M34	
7.6.1	Short prototype SC helical undulator fabricated and tested	D	M36	