




HL-LHC MCBRD CCT Magnets: Review and Latest Progress in China

Qingjin XU IHEP-CAS For the CCT Magnet Team



19-22 September 2022 – 12th HL-LHC Collaboration Meeting, Uppsala University, Sweden


MCBRD: the HL-LHC D2 orbit correctors, 12+1 units, providing a 5 Tm integrated field in two apertures, vertical in one and horizontal in the other.



IHEP

Q. Xu,12th HL-LHC Collaboration Meeting, 19-22 Sep 2022

Main design parameters of the CCT magnet



0.5-m model coils R&D in China in 2017-18



https://indico.cern.ch/event/765288/contributions/3178832/attachments/1768774/2881344/20181212-Short_Model_Prototype_and_Series_Program_of_MCBRD_in_China.pdf

Development of the 0.5-m Model in China


Bore field / T	2.64			-
Current / A	422			
Layers	5+5			
CCT angle /°	30		Land Contraction	01
Turn width /mm	5.2(0.6)			
Turns per layer	55			
Integrated field / Tm	0.757			18 0
Peak field / T	3.1			
Io/Ic	55%	2.6 2.4		
Slot size in former	2 mm×5 mm, 0.6 mm for rib	2.2 2.0 1.8		
Iron yoke size/mm	Φ614/539.4	1.6 1.4 1.2		
ID and OD of two formers/ mm	The first layer: 105 /119; The second layer: 119 /133	1.0 0.6 0.6 0.4	Integrated	field :0.757 Tm
Dia of wire / mm	0.825(767A@3T 700A@4T) 0.99(with insulation)	0.2 X count 04.0 Y count 0.0 2 count 0.0 Component 83, from turber Line, inte	94.0 94.0 80 80 3000 100 100 100 100 100 100 100 100 100	84.0 80 100.0

Test of the 1st 0.5m Model Coil


ille [Test Procedures							
	data	time	details	c				
	2018/7/14	8:40	cooling by LN2					
	2018/7/14	9:20	cooling by LN2	7				
	2018/7/14	10:05	discharge of LN2	7				
/ 4	2018/7/14	11:00	dry under nitrogen	9				
100	2018/7/14		dry with heating					
	2018/7/14	12:20	cooling by LHe2	1				
ALL COMMON	2018/7/14	13:50	cooling by LHe2					
W	2018/7/14	14:05	excitation 1A/s	-				
	2018/7/14		excitation 2A/s	48				
i a	2018/7/14		excitation 3A/s from 0 to 460A, 1A/s from 0 to 470A, pause, excitation	47				
	2018/7/14	15:18	excitation 4A/s					
a charles and	2018/7/14	15:28	excitation 4A/s					
	2018/7/14	15:44	excitation 4A/s					
lo 4.0 5.0	2018/7/14	15:49	excitation 4A/s	52 mi				
				-				

Loadline comment check 76K, 75k 40A3.84 77K.76k 98K.88K 543A @ 4.2K 102K .95k 41cm 483A guench 471A quench 469 4A 529A 543A 520A last 20 min. 551A quench

HILUM



> 1# inner coil: the wire is 0.2-0.3 mm higher than the former.
> 2# inner coil: the wire is 0.1 mm higher than the former.




Test of the 2nd 0.5m Model Coil


489A quench at the wire 1# of inner coil and 2# of outer coil

Agreement For CCT magnets signed in Sep 2018 at IHEP





IHEP



Q. Xu,12th HL-LHC Collaboration Meeting, 19-22 Sep 2022

Related partners

Contracts of the materials and componentsfor the 12+1 CCT magnetsNbTi wires:Contract with WST China.Insulated wires:Contract with CGP France.Coil formers:Contract with HE-Racing China.Yoke laminations and end plates:Contract with KEYE China with iron plates from CERN

Fabrication of the magnets: prototype by WST, series by BAMA

• Coil winding and impregnation, instrumentation, magnet assembly.

Performance test

- Coil stand-alone test at IHEP: training to 530 A, then magnet assembly;
- Magnet test at IMP at 4.2 K: training to 422 A with iron.
- Magnet test at CERN at 1.9 K: double-check the performance.

QA &QC: IHEP & CERN and related partners.




Superconducting wires

NbTi bare wire from WST China:


similar J_c but with lower Cu ratio than CERN wire: 1.2-1.3 instead of 1.9

• The insulation done by CGP France.



WST strand versus MB outer layer strand fitting, corrected for Cu:non-Cu ratio of 1.3

- WST, 1.9 K, without self-field correction
- WST, 4.3 K, without self-field correction
- 1.9 K fit, based on MB outer layer, corrected for Cu-nonCu ratio
- 4.3 K fit, based on MB outer layer, corrected for Cu-nonCu ratio







7

Coil fabrication



VPI

- Coil VPI for aperture V and H with pressure
 - ✓ Baking coil before vacuum impregnation at 80°C for 3 days.
 - Electrical test before and after VPI procedure





Aperture V coil after VPI



Magnet assembly




HI

Fabrication completed in May, test completed in Aug. 2020



MCBRDP2 4.2 K Test at IMP: both apertures reached the ultimate current.



Delivery to CERN Aug-Oct 2020



Test Setup at SM18 CERN






MCBRDP2 1.9 K test at CERN

Each aperture, individually and combined, arrived to ultimate current without quench





Q. Xu,12th HL-LHC Collaboration Meeting, 19-22 Sep 2022

Progress of series production


	Coil name	Winding method	Location	Coil stand-alone performance at 4.2 K	Magnet performance at 4.2 K	
	MCBRD_CB01	Wet wind	CERN	530 A		
Magnet1	MCBRD_CB03	Direct wind	CERN	410 A (training stopped due to the availability of the test station)	Both apertures reached ultimate current 422 A, and passed 4-hour stability test	
	MCBRD_CB02	Direct wind	CERN	Failed to reach the design current		
Magnet2	MCBRD_CB04	Wet wind	CERN	422 A (training stopped due to the availability of the test station)	Both apertures reached ultimate current 422 A, and passed 4*1 hour stability test	
U	MCBRD_CB06	Wet wind	CERN	530 A		
Magnet3	MCBRD_CB09	Direct wind with new channel size	IMP	530 A	Both apertures reached ultimate current 422 A, and stability test to be done this	
in agricuo	MCBRD_CB12	Direct wind with new channel size	IMP	520 A (training stopped due to the availability of the test station)	week	



13

Training-history of Bama coils CB1-6





CB01 has the best training performance of all the 2.2m coils from China.

Wet-winded with a coil former whose machining error exceeds the tolerance: having the smallest depth of the channel

Field quality is good: ~5 units (measured at IMP)


Quench Number

Q. Xu, 5th SC Meeting for HL-LHC MCBRD magnets, 28 Jan 2022

Proposals in the CERN-China SC meeting in Jan 2022



- **Further optimize the channel size immediately**, try to make the conductor a bit higher (0.1~0.2 mm) than the former outer surface, then apply support stress outside of each layer by wrapping glass tapes.
- Wet wind **back to direct wind**, make the process simple, with a careful check of the VPI system at Bama before hand.
- IHEP provides components of 2 magnets (insulated conductors, coil formers and iron plates) to CERN. CERN fabricate the 2 magnets with the same procedures as in China, to have a double-check of the performance at 4.2K.



Direct winding of CB09



Using 3 layers of glass fiber to **reduce the channel depth from 5.2 mm to 4.8 mm**; The conductor is ~**0.2 mm higher than the former surface** after winding.




Direct winding of CB09






Q. Xu, 6th SC Meeting for HL-LHC MCBRD magnets, Jul 8 2022

P-T setting of the VPI procedure






Directly degassing the mold



Resin pipeline

Directly degassing the mold








Q. Xu, 6th SC Meeting for HL-LHC MCBRD magnets, Jul 8 2022

Stand-alone test of CB09 at IHEP










Stand-alone test of CB09 at IHEP and followed by CB12, 13



Training History of the HL-LHC CCT Coils





Quench Number


Training of the 1st series magnet MCBRD01

Aperture1 of the 1st series magnet

The 1st practice coil from Bama with new fabrication process wet wind plus 5-bar VPI.

Aperture2 of the 1st series magnet


The 2nd coil from Bama with direct wind process plus 5bar VPI, similar to the process of the 1st prototype.






23

Holding test of the 1st series magnet




Field quality measurements at 4.1K

All field harmonics are within the 10-unit requirement, <5 units for most cases.




The 1st series magnet delivered to EU


The 1st magnet Packed and delivered to Sweden Uppsala University on Oct. 18 2021



MCBRD01 1.9 K Performance test at CERN



"After the test in China, the magnet was shipped, connected to the bench at Freia, transported to CERN, connected to the CERN bench. After all this, the magnet showed a very good memory!"





"the target voltage of 1620V from each aperture to ground according to the Electrical Design Criteria (EDMS 2363906) was not reached for any of the two apertures in magnet MCBRD01. The maximum voltage reached at 1100 V for aperture 1 to ground and 1500 V for aperture 2 to ground, but tripped at those levels"

27



The 2nd series magnet MCBRD02



CB 04&06 trained stand-alone to 520 A at IHEP in Nov 2021. To Bama for magnet assembly in Jan 2022.










Magnet 2 assembled on the test platform at IMP










Training history of MCBRD02






The training history of MCBRD02

Quench number




The holding test








Crosstalk—Multipoles in the 2 Apertures



IL-LHC PROJEC



32

Electrical test before packaging

Table 11. The insulation test results (final tests)

Equipment	Coil ID	Object	Function	Voltage/Current	Test Time	Resistance	
Ap		Coil to Ground	IR	102V/1.28nA	30s	79.5GΩ	
		Coil to Ground	IR	201V/1.28nA	30s	>100GΩ	
	Ap	Coil to Ground	IR	308V/1.64nA	30s	188.1GΩ	
	Aperture	Coil to Ground	IR	340V/1.98nA	30s	172.2GΩ	
	ure	Coil to CCS322	IR	103V/0nA	30s	>100GΩ	
		Coil to CCS322	IR	254V/0nA	30s	>500GΩ	
		Coil to CCS323	IR	104V/0nA	30s	>100GΩ	
Megger		Coil to CCS323	IR	254V/0nA	30s	>500GΩ	
MIT 525		Coil to Ground	IR	102V/0.54nA	30s	>100GΩ	
		Coil to Ground	IR	201V/1.74nA	30s	>100GΩ	
	Ap	Coil to Ground	IR	308V/2.07nA	30s	149.1GΩ	
	ert	Coil to Ground	IR	340V/2.13nA	30s	159.3GΩ	
	Aperture	Coil to CCS317	IR	101V/0nA	30s	>100GΩ	
	92	Coil to CCS317	IR	254V/0nA	30s	>500GΩ	
		Coil to CCS324	IR	101V/0nA	30s	>100GΩ	
		Coil to CCS324	IR	254V/0nA	30s	>500GΩ	
Test condition: 23.7°C & relative humidity 38.9% & before packaging							

The magnet's two apertures pass all insulation tests.




MCBRD02 Shipped to CERN in June 2022





The 3rd series magnet MCBRD03

- AP1(CB12, 25 quenches 526A) reached ±422A after 11 quenches.
- AP2(CB09, 33 quenches 530A; after thermal cycle >500A) reached ±422A without any quenches.





Summary

- In total 3 series CCT magnets MCBRD01-03 have been fabricated. All of them reached the ultimate current and passed the field quality test (MCBRD 03 to be done this week)
- Long training "problem" has been solved with modifying the design parameters and improving the fabrication process.
- Wire insulation at the endplate of MCBRD01 is broken, caused low insulation strength, to be repaired at CERN. MCBRD03 passed 1620 V HV test in LHe at IMP Lanzhou.
- Components for 2 CCT magnets being shipped to CERN from IHEP, to verify the performance with WST wires and coil formers fabricated in China with CERN fabrication process, and also speed up the project progress.
- Schedule for the following magnets: every ~3 month per magnet.





Thanks for your attention



Q. Xu,12th HL-LHC Collaboration Meeting, 19-22 Sep 2022