




Warm Powering Status Report

Michele Martino – CERN
on behalf of WP6B



12th HL-LHC Collaboration Meeting – Uppsala – Sweden – September 20th 2022

WP6B – Who's who



HL-LHC [18kA; $\pm 10V$]: RPAFE_{RQX} latest news

6B.1 Status





- Reminder: built of 9+1 2kA $\pm 10V$ subs with Energy Storage System
 - 2kA sub validated by 03/2022 ✓ [TCC #126 02/21 and TCC#152 03/22]
- All collaborations are now completed ✓
 - EPFL – Switzerland 09/2020
 - [High-Current Low-Voltage Power Supply for Superconducting Magnets](#)
(first Ph.D. dissertation discussed over zoom in Covid time at EPFL)
 - LIC-CONICET – Argentina 06/2022
 - UPV/EHU-APERT – Spain 08/2022
- Prototype for IT String is being assembled ✓
- New crowbar design presented at MCF #107 08/2022 ✓
 - Part of the **new general WP6B contribution to circuit protection** TDR Sec. 6B.4.5
 - ECR being drafted, approval foreseen by end of 2022



HL-LHC [18kA; $\pm 10V$]: RPAFE_{RQX} Prototype

- All components have been delivered to CERN ✓
- Power modules assembly is progressing steadily: $\geq 65\%$ [last week]





6B.1 Status



HL-LHC [18kA; $\pm 10V$]: RPAFE_{RQX} Crowbar

- Modular diode-based crowbar design with $>10\%$ redundancy
 - 28 modules – 650A-module successfully validated (tested up to 750 A) ✓
- 1200 x2 power diodes for the IT String proto ordered ✓ expected end 2023



6B.1 Status



HL-LHC [14; 18] kA testbed: Completed ✓

- Two different circuits to validate 14kA and 18kA Class 0 converters
- A link between the two to simulate energy recovery
 - 18kA converter feeding the 14kA freewheeling diodes
 - 14kA converter supplying the 18kA energy recovery system (modular testing)
- More than 7 tons of copper in total & dedicated WIC system


6B.2 Status



HL-LHC [14kA; 08V]: RPAFE^{RD1/2} demo completed ✓

- [20kA; 08V] PC delivered to 6B.5.2 ✓ for Class 0 DCCT testing 08/2022
- Achievement for 6B.2: validation of the full control of 9+1 2kA subs ✓
 - Validation of electronics crate/boards + regulation software
 - Validation of N+1 redundancy [sudden lost of a sub not to affect the output current]
 - Basis for the mechanical integration of the 14kA [7+1 2kA subs]

6B.2 Status





Converter installed in its final location P-Hall (bldg. 377)



HL-LHC [14kA; 08V]: RPAFE^{RD1/2} steps ahead

- Prototype for the IT String being assembled
 - Mechanical frames production ongoing, expected by end of September 2022
 - Busbars and water cooling components already available at CERN ✓
 - Already tested power modules (from R2E LHC) ready for installation ✓



HL-LHC [$\pm 2\text{kA}$; $\pm 10\text{V}$]: RPBAA_{IT OC}, RPBAB_{IT trims}

- Prototype (\rightarrow pre-series) successfully tested end of 2021 ✓


6B.4 Status



Power Module
400A



Auxiliary Supply Module



Protection Module



Power Rack


HL-LHC [$\pm 2\text{kA}$; $\pm 10\text{V}$]: RPBAA^{IT OC}, RPBAB^{IT trims}

- Prototype equipment passed CE marking tests by 02/22
 - Safety: EN 52368-1 ✓ EMC: EN 61000-6

6B.4 Status



Voltage dip test





Radiated Immunity test

- **Contract for power modules + racks ongoing ✓** [Jema Electrónica – Spain]
 - Pre-series: racks expected by 12/22 – modules by 05/23

HL-LHC [$\pm 2\text{kA}$; $\pm 10\text{V}$]: RPBAA, RPBAB Crowbars


RPBAA – OC circuits

Redundant Design - Thyristor based



RPBAB – IT trims circuits

Redundant Design - Diode based






- Design completed 07/22 – Production started 08/22 ✓
 - Both expected at CERN by 12/22 [for successive installation in IT String]

HL-LHC [$\pm 600\text{A}$; $\pm 10\text{V}$]: RPBMF D2 correctors

- Design (full PC) to be completed by end 2022
 - Built with 2 x 400A modules \rightarrow fully redundant PC as $I_{\text{nom}} < 400\text{A}$
- 8 x 400A power modules prototypes ordered \checkmark expected by 10/2022 [Estonia]
- Proto to be validated by mid 2023
- Redundant thyristor based crowbar design ongoing

6B.4 Status



R2E-LHC [$\pm 200\text{A}$; $\pm 10\text{V}$]: RPBMD_{SF 2nd}

- 400A power modules (R2E – LHC) produced and tested ✓ 11/2019
- Four racks (assembled with 200A DCCTs) produced, tested and ready for installation ✓ since 03/2022
- First “series” Power Converters ready for HL-LHC – 1x for IT String ✓

2 x



6B.4 Status

Control Electronics

6B.5.1 Status

- ECR for FGC3.1 control approved in 10/21 [[EDMS 212383](#)]
- Procurement x LS3 is ongoing [facing long delivery time for some components]
- All electronics for IT String is ordered or already available ✓ except:
 - Inner Triplet PIC “concentrator” chassis [[EDMS 2730935](#)] exp. by 12/22
 - FPGA logic for 2 channels Class 0 external ADCs [optical link] exp. by 12/22
- HIL tester for IT decoupling control completed in 08/22 ✓




HIL IT decoupling control tester [Typhoon]

6B.5.2.1 ADCs – Class 0: HPM7177


- HPM7177 [[open hardware](#)] fully validated in 2021 [[EDMS 2520612](#)] ✓
- MS4690 and IT4690 carried out in 2021 [[EDMS 2579048](#), [EDMS 2629302](#)] ✓
- Pre-series production launched at the end of 2021 ✓ – delivery end of 2022
- Independent EMC testing in 2022 ✓
- **Metrology validation in PTB in 2022** (with Programmable Josephson Voltage Standard) ✓

6B.5.2 Status



6B.5.2.1 ADCs – Class 3: ANA 104

- ANA104 (FGC internal ADC): prototype validated in 2022 [[EDMS 2424037](#)] ✓
- Ready for production ✓ Component procurement has started ✓



6B.5.2.2 DCCTs – Class 0

- Class 0 DCCTs (18kA & 14kA) prototypes validated ✓ [[EDMS 2687320](#), [EDMS 2687321](#)]
- Pre-series production ongoing ✓ delivery expected by May 2023

6B.5.2 Status




EMC testing



18kA performance testing

6B.5.2.2 DCCTs – Class 2

- Class 2 DCCTs (2kA) prototypes validation ongoing
- Stability performance not yet within specs: 2.5 ppm achieved vs 1.5 ppm required
- Intense work is ongoing with the manufacturer to improve it
- Delivery to IT String is currently estimated by September 2023



12h drift after 0A to I_{nom} step [excluding first 5 min]

6B.5.2.3 DCCT Test Infrastructure

- 20kA and 6kA Power Converters installed and commissioned 08/2022 ✓

6B.5.2 Status



20kA Power Converter ["14kA demo" from 6B.2]





6kA Power Converter

6B.5.2.3 DCCT Test Infrastructure


- CERN DCCT CALIBRATOR prototype validated 07/2022 ✓
 - Drift better than 0.2 ppm peak-peak over 20 hours
 - Finalization is ongoing [TECH student arriving 10/22]

6B.5.2 Status



Control Software

- IT decoupling control library is ready since end of 2020 ✓



- Validation by means of HIL tester expected by Q1 2023
 - during IT String testing it will be seen if MQXF saturation needs to be taken into account [after 10/24]

6B.5.3 Status

R2E-LHC [60; 120]A: RPLBC_{120A} & RPLAC / D_{60A}

- 3 different converters RPLBC_{R2E} 120A, RPLAC_{R2E} 60A, RPLAD 35A_{60A}
- 2 common building blocks: POWER MODULE – CONTROL & PROTECTION MODULE
 - DM 1 special crowbar module (up to 3.5 kA for Q1a KT modulation)
- High synergy leading to cost optimization ✓
 - R2E 60A & 120A: 500 Gy current target - first design phase completed ✓
 - Modules of all three types are currently under construction ✓



PM rated 60A



CPM

DM Module for RPLAD

R2E-LHC [60; 120]A: RPLBC_{120A} & RPLAC / D_{60A}

- Simulated & measured performance of PM_{Voltage Source} fully satisfactory ✓

6B.6 Status




- All highly critical components tested under radiation (R2E Team)
 - Degradation was measured and is now integrated in components models ✓
 - Support of R2E team @ CERN is crucial (heavy campaign) ✓
 - 570 000 components ordered (75% of critical semiconductors) ✓
 - Shortage on components is currently mitigated (but some delivery in Q3 2024)



R2E-LHC [60; 120]A: RPLBC^{120A} & RPLAC / D^{60A}

6B.6 Status



Current sensor radiation qualification
[campaign @ PSI]

				Tested											
0	0	Low	TBD (no design & vs its use)	TBD (no design & vs its use)	NPN Transistor	D44H11G	TO220								
0	0	Low	TBD (no design & vs its use)	TBD (no design & vs its use)	PNP Transistor	D45H11G	TO220								
0	0	Low	OK (Tested)	OK (Tested)	NPN Transistor	BCP56-16	SOT223								
0	0	Low	OK (Tested)	OK (Tested)	PNP Transistor	BCP53-16	SOT223								
0	0	Low	OK (Tested)	OK (Tested)	NPN Transistor	FMMT491TA	SOT23								
0	0	Low	OK (Tested)	OK (Tested)	PNP Transistor	FMMT391	SOT23								
0	0	Low	TBD (no design & vs its use)	TBD (no design & vs its use)	Bridge Rectifier	26MT160	D-34A								
2	2	High	TBD (no design & to be tested)	TBD (no design & to be tested)	Current Sensors	BJHCS-K3-100A HAS 100S	20mm x40mm x10mm								
2	2	High	OK (Tested)	OK (Tested)	Phase Sh. PWM	UC2873N (UC1873 (62))	DIP20								
2	2	High	OK (Tested)	OK (Tested)	Op. Amplifiers	OPA2192 OPA1611	SO8								
1	1	Med.	OK (Tested)	OK (Tested)	Analog Switches	SW06GSZ (DG4443)	SOIC16								
0	0	Low	OK (Tested)	OK (Tested)	Comparators	LM193	SO8								
0	0	Low	OK (Tested)	OK (Tested)	Volt. Reference	TL1431 (TL431, TL431LL)	SOT23								

“Live” documentation on
R2E components qualification

R2E-LHC [60; 120]A: RPLBC_{120A} & RPLAC / D_{60A}


- Work on power rack started for
 - RPLBC [120A] in RRs
 - and RPLAD [35A] in URs + SM18_{IT} String
 - Design well advanced taking into account operational aspects
 - including CDB like operations for lock-out tag-out:
 - Disconnection, Earthing, Short circuits (for tests)



Easy to “earth” circuit or disconnect it from converter side

CDBs & WCBBs

- Deliverables:
 - Circuit Disconnecter Boxes for circuits $\geq 600\text{A}$
 - Water Cooled Bus Bars for circuits $\geq 14\text{ kA}$
 - ECR for WCBBs recently approved ✓ 06/22 [[EDMS 2453935](#)]
 - Technical (and status) info tomorrow at MCF parallel session – [talk: S. Seshadri](#)
 - deliverables for Run4 might come as in-kind contribution - discussion ongoing ✓




CDBs

- Power Racks
 - Mechanical design completed in 2021 ✓ - Prototypes finalized by 06/22 ✓
 - Pre-series for IT String being assembled for installation during 10/22 ✓
- Control rack
 - Design finalized in 06/22 ✓
 - Contract for pre-series being finalized for delivery end of 01/23


Contract in 2023 for Series Production in 2024

6B.11 Status



Conclusion

WP6B - in work schedule presented at PSM 2nd June 2022





Thank you for your kind attention



Credits to: V. Montabonnet, S. Pittet, N. Kuczerowski, V. R. Herrero Garcia, B. Todd, M. Cerqueira Bastos, Q. King, Y. Thurel, C. Coupat, H. Thiesen

Spare Slides



Scope and deliverables: Power Converters

WBS	Eq. Code	Magnet Circuit	Ratings <small>precision class</small>	Deliverables
6B.1	HCRPAFE	Inner Triplet Mains	[18 kA; ± 10 V] <small>class.0</small>	06 (04: operation)
6B.2	HCRPAFF	D1-D2	[14 kA; 8 V] <small>class.0</small>	10 (08: operation)
6B.4	HCRPBAA	Inner Triplet Correctors	[± 2 kA; ± 10 V] <small>class.2</small>	37 (32: operation)
	HCRPBAB	Inner Triplet Trims	[± 2 kA; ± 10 V] <small>class.2</small>	
	HCRPMBF	D2 Correctors	[± 600 A; ± 10 V] <small>class.3</small>	32 (22: operation)
	HCRPMBD _{R2E}	SF 2 nd Order (± 200 A)	[± 600 A; ± 10 V] <small>class.3</small>	
	HCRPMBE _{R2E}	11 T Trim (± 250 A)	[± 600 A; ± 10 V] <small>class.3</small>	
6B.6	HCRPLBC _{R2E}	SF High Order	[± 120 A; ± 10 V] <small>class.4</small>	36 (32: operation)
	HCRPLAD	Q1a Trim (± 35 A)	[± 60 A; ± 10 V] <small>class.4</small>	06 (04: operation)
	HCRPLBC _{R2E}	LHC Correctors + Q4-Q5-Q6 Correctors	[± 120 A; ± 10 V] <small>class.4</small>	100 (92: operation)
	HCRPLAC _{R2E}	LHC Correctors	[± 60 A; ± 10 V] <small>class.4</small>	154 (144: operation)

* : deliverables other than **operational converters** are given as “equivalent” units; they do not represent “full converters” (protos/spares in different phases, spare parts, etc.).

Scope and deliverables: complements

WBS	Equipment	Deliverables for 381* Power Converters <i>(338: operation)</i>
6B.5.1	Control Electronics	Modular & high-reliability control electronics for all WP6B power converters based on FGC3.1 & FGCLite <small>R2E</small>
6B.5.2	Current High Precision Measurement	Current measurement equipment for all WP6B power converters - Development of ultra-precision HL-LHC Class 0 (DCCTs, ADCs,...) - Test and calibration infrastructure
6B.5.3	Software	Software production for IT decoupling control and IT current monitoring system
6B.9	Transport & Installation	Manage all activities and deliverables concerning Transport and Installation of the 338 operational converters (+ relative spare units/parts). It includes both INDSERV and MATERIAL.
6B.10	Warm Powering of IT STRING	Management of all activities and deliverables to successfully provide “warm powering” for the IT String, including operation during 2025 and coordination for de-installation
6B.11	Circuit Disconnecter Boxes	CDBs for all 32 HL-LHC circuits powered from URs (including PLC controls and spare units). CDBs for the IT String WCBBs for the 12 HL-LHC circuits : 18 kA and 14 kA

* : deliverables other than **operational converters** are given as “equivalent” units.