

# **MKI Cool**

Miguel Diaz Zumel

Acknowledgements:

M.J. Barnes, C. Bracco, W. Bartmann, O. Bjorkqvist, L. Ducimetière, B. Goddard, T. Kramer, T. Maurin, V. Namora, A. Porret, T. Stadlbauer, P. Trubacova, L. Vega Cid, V. Vlachodimitropoulos, W. Weterings

Uppsala – September 19<sup>th</sup> to 22<sup>nd</sup> 2022

## Outline

#### 1. Context

- MKI purpose and design
- $Cr_2O_3$  coating
- Damping element and MKI cool

#### 2. Issues – now solved

- HV breakdowns
- Unsuccessful conditioning

#### 3. Issue – understood


- Mis-manufactured alumina tubes
- Present work
- 4. Status of first MKI cool to be installed in LHC

#### 5. Conclusions



#### 1. Context


#### MKI: Injector kicker magnets for the LHC




#### Planning of MKI cool installation

1 MKI cool (proto)	2 MKI cools	2 MKI cools	2 MKI cools	1 MKI Cool
YETS 22/23	YETS 23/24	YETS 24/25	Start of LS3	During LS3

## C Typical MKI pulse









## 1. Context Screen conductors inside MKI

Alumina tube (installed in MKI)

- Screen conductors **carry image current** of **circulating beam** U
- Lower beam induced heating
- Conductors are supported and electrically insulated by alumina tube (high SEY)
- 2017-18 YETS upgrade of MKI8D: Alumina tube is coated on the inside with Cr<sub>2</sub>O<sub>3</sub>: has a low SEY, does not produce UFOs and is high voltage compatible






Vacuum tank

24 screen conductors (one each 15 degrees, since LS1)



# **1. Context** $Cr_2O_3$ coating in MKI8D, installed in YETS 17-18



with **Cr<sub>2</sub>O<sub>3</sub> coating** on the inside Before:

**Pressure** in **MKI8D** interconnect used to be a factor of  $\sim$ **3** (2012, 2015 and 2017) and  $\sim$ **12** (2016) **higher than** that of **Q5-MKI2D** 

After:


This **factor** is **not observed** anymore.

No other vacuum modifications were done, so pressure reduction is attributed to  $Cr_2O_3$  coating

## **1. Context** Damping element: the origin of MKI cool

- Redesigned ferromagnetic rings


   (damper), placed on the alumina tube
   outside of the magnet aperture, re Inject
   locates beam induced power
   deposition from the ferrite yoke to the
   damper
  - Damper is **not at** pulsed **high voltage** Post-LS1 45 Temperature [C] design 40 35 30 25 Upgraded, MKI8D, design of ferrites 20 07/05/2018 17/05/2018 <sup>06/06/2018</sup> 17/04/2018 27/04/2018 <sup>27/05/2018</sup> 16/06/2018 26/06/2018 Date





## **1. Context** <u>MKI cool = damping</u> element + water <u>cooling</u>

- Damping element fulfils the function of re-locating beam induced power
- **BUT, with HL-LHC beam**, it would reach the Curie temperature, and (temporarily) **stop working**
- The idea of the **MKI cool** is to cool the damper with **water** to remove heat






### **2. Issues – now solved** During 2019

Non-conformity of slots in alumina tubes purchased during 2017: slots were too wide. Thus, it was necessary to use screen conductors with a small zig-zag

[HL-NCR: https://edms.cern.ch/document/2440015/1.0]




Using wider screen conductors was discarded due to influence on magnetic field (eddy currents)

#### HV pre-conditioning of MKI cool failed:

[HL-NCR: https://edms.cern.ch/document/2440015/1.0]

- 18 strong sparks occurred over two weeks
   Conditioning plateaued at ~45kV (goal=56.1kV)
- Three **black marks** from HV **breakdowns to** alumina tube





#### **2. Issues – now solved** During 2019. Actions carried out

RF damper structure was modified to mitigate HV breakdowns:

1. Metal **supports** for **tube** replaced by **macor** 


**Cooling pipes** 

for RF damper

- 2. RF damper end cap inside diameter enlarged (from 56mm to 60mm), to increase distance to alumina tube
- RF damper

 End-cap
 1 mm radius

3. Sharp edge on stainless steel short eccentric tube removed (manufacturing error)




#### Sharp edge chamfered



#### **2. Issues – now solved** During 2020. HV conditioning

Conditioning **completed** and **target** of 56.1kV\* and 8.8µs flattop **reached**, **BUT:** 

- Conditioning required 230k
   pulses (usually 50k to 100k)
- 18 strong sparks were observed (usually <6)</li>
- For the first time, two strong sparks during microdischarge test
- Hence, magnet was not installed, but opened and inspected instead



\*: 56.1kV is ~10 % above Point 8 operational voltage (51.3kV)




System reset

Strong spark


#### **2. Issue – now solved** Inspection after conditioning (November 2020)

First observation: Still one black mark seen on the tube, at the end (3 marks in 2019)




Alumina tube outside of magnet

The reason was a sharp edge due to misalignment of HV busbar of the magnet



End of magnet, without tube






Enhanced electric field (~doubled) due to dealignment of HV busbar



#### **3. Issue – understood** Inspection after conditioning (November 2020)

Second observation: alumina tube was punctured, inside of the magnet (52cm from downstream end)







**3. Issue – understood: mis-manufactured alumina tubes** Puncture triggered study of tube thickness of 2017 batch


All 2017 tubes were measured

Magnetic gauge measures wall thickness all along the tube





A dedicated **Python programme** was developed, to **show the inner profile** of the **tubes** 






MKI Cool - M. Diaz Zumel - 12th HL-LHC Collaboration Meeting 13

**3. Issue – understood: mis-manufactured alumina tubes** Discussions with manufacturer + conclusions of study

For manufacturing, tube is **extruded with final inner profile**, but larger outer diameter

#### Afterwards, the outside surface is machined

- No tubes, from 2017 batch, with required minimum wall thickness (2mm)
- 2. Axis for machining the tube could be better chosen, to have more uniform wall thickness



3000

**3. Issue – understood: mis-manufactured alumina tubes** Current work: determining the optimal machining axis

Shape of tube after extrusion is imperfect

(before machining) -uture Outer profile characterisation Before Machined tube Optimal axis for machining optimal axis machining.py  $= \{x_1, y_1, x_2, y_2\}$ 




Extruded tube exaggerated deformation) Wall thickness measurement

#### **3. Issue – understood: mis-manufactured alumina tubes** Optimization of tube rotational angle for installation

- Angle for installing of the tube can be chosen
- Electric field data, predicted by simulations, depends on:
  - Wall **thickness** of the tube (*d*)
  - Angular position of screen conductor  $(\theta)$
- **Python** programme to check every orientation (0, 15, ... 345 deg.) and calculate electric field
- **Orientation** with lowest E field is chosen for installation








#### 4. Status of first MKI cool to be installed in LHC

Installation planned for YETS 22/23

Successful HV pre-conditioning

Planning has been delayed due to a vacuum leak.
 The seal is being replaced.
 But still in schedule, for YETS 22/23, at location MKI8C





MKI cool in test cage




### **5. Conclusions**

- High voltage issues during 2019 and 2020 have been successfully solved
- The remaining issue is the risk of puncture due to non-conforming alumina tubes:
  - The issue is well **understood** and a there is good **collaboration** with the manufacturer
  - **Detailed measurements** of the tubes <u>prior</u> to machining will result in achieving minimum of 2mm wall **thickness** 
    - Remeasuring the tubes <u>after</u> machining will validate correct machining, and therefore thickness
  - **Optimizing angular** position, for installation in an MKI, will serve as an extra **protection** against HV breakdowns through the tube wall







18

#### Thanks for your attention !


# **Spare slides**



MKI Cool - M. Diaz Zumel - 12th HL-LHC Collaboration Meeting

#### **Context** MKI conditioning information

Simplified conditioning schematic




- Operational voltage of MKIs is 49.6 kV at Point 2 and 51.3 kV at Point 8
- All MKIs are conditioned to ~10 % above Point 8 voltage = 56.1 kV
- During HV conditioning:
- Voltage is ramped up to 56.1kV at a fixed pulse length of 1.5µs;
- Ramping is followed by a plateau (1.5µs at 56.1kV for 1200 pulses);
- Plateau is followed by enlarging mode (1.5µs to 8.8µs) at 55.1kV;
- Finally, a plateau with 8.8µs at 55.1kV for 1200 pulses
- HV conditioning is followed by a micro-discharge test, for validating the MKI:
- Voltage is quickly ramped up to 55kV\* at a fixed pulse length of 8.6µs, 500 pulses per step
- Notes:
- \*: 1 kV above the maximum SoftStart PFN voltage at Point 8
- A pressure rise is considered a micro-discharge (energy dissipated in the magnet or beam screen is relatively low) when the pressure takes a few minutes (e.g. 3 minutes) to recover to its pre-breakdown level.




#### **Alumina tube measurements summary**

	Absolute	Longitudinal position				
mininum (cm) of the minimum		Average	Average offset	Relaxed criteria	Exigent criteria	
thickness thickness (starting		hole radius	of centre of	Thinnest point on critical angles (±	Thinnest point on critical angles (±	
Tube	(mm)	from Ø56mm end)	(mm)	hole (mm)	15° inc.) after optimization (mm)	30° inc.) after optimization (mm)
s MKI2B	1.98	112	22.85	0.43	2.24	2.24
LS1-1 LS1-2	1.75	22	22.93		2.25	1.955*
- LS1-2	1.36	202	22.96		1.75	1.48
L31-5	2.04	112	22.86			
LS2-1	1.23	52	23.12		1.79	1.65
LS2-2	0.95	202	23.23			
LS2-3	1.44	232	23.11	0.42	1.72	1.72
LS2-4	1.42	232	23.09	0.57	1.82	1.82
LS2-5	1.68	82	23.12	0.52	1.84	1.84
សូ LS2-6	1.15	262	23.08	0.51	1.85	1.56
ទួ LS2-6 ក្នា LS2-7	1.04	262	23.08	0.91	1.32	1.18
≩ LS2-8	0.78	262	23.08	0.61	2.06	1.36
Ž LS2-9	0.93	202	23.08	1.06	1.21	1.00
LS2-10	1.34	262	23.07	0.65	1.62	1.34
LS2-11	1.43	262	23.12	0.49	2.04	1.61
LS2-12	0.82	262	23.08	0.59	1.93	1.45
LS2-13	0.70	262	23.13	0.91	1.16	1.16
LS2-14	0.98	262	23.11	0.52	2.06	1.35
				(2 of 3 2013 + 3 of 14 2017)	(2 of 3 2013 + 0 of 14 2017)	
Number of good tubes					= 5	=2

Notes: LS1-? = 2013 batch LS2-? = 2017 batch









#### **Reminder of the HL-LHC Goals**

From FP7 HiLumi LHC Design Study application in 2010

