



Zanon Status for Series


Manuele Narduzzi - FNAL

12th HL-LHC Collaboration Meeting – Sep 19th - 22nd, 2022



Outline

- Raw Materials Procurement
- Bare Cavities Fabrication
 - Documentation approval status
 - 2x Pre-series and 10x Series
- Jacketed Cavities Fabrication
- Upcoming plans




Raw Materials Procurement

- Dressed RFD mat. specs **agreed** between CERN - AUP
 - ✓ RRR300 Niobium
 - ✓ Sheets – CERN spec. 3300 ed.4 ([EDMS 1095252](#))
 - ✓ Bars & Plates – CERN spec. 3301 ed.4 ([EDMS 1476934](#))
 - ✓ Seamless Tubes ([EDMS 2367297](#))
 - ✓ Ultrasonic Inspection Procedure ([EDMS 1971779](#))
 - ✓ Nb-55Ti
 - ✓ Bars & Plates - CERN spec. 4055 ed.4 ([EDMS 1485727](#))
 - ✓ Ultrasonic Inspection Procedure ([EDMS 2116737](#))
 - ✓ Stainless Steel 1.4429 (316LN)
 - ✓ Forged Blanks - CERN spec. 1001 ed.5 ([EDMS 790775](#))
 - ✓ Other materials for Dressed Cavity
 - ✓ (Ti, Cu, SS, Cryophy, Alumina & Gapasil)

- Sizes & quantities **optimized** by ZRI* after protos experience


- **Purchased** according to the HL-LHC requirements (*Pre-series & Series production*)
 - ✓ PO 657756 (Ningxia) Nb Sheets
 - ✓ PO 671157 (Ningxia) Nb Rods & Plates, NbTi Rods & Discs
 - ✓ PO 671490 (Ningxia) Nb Tubes
 - ✓ ZRI* PO (Ningxia) additional Nb for welding tests
 - ✓ PO 686821 (ANL) extra brazed joints for pre-series



Raw Materials QC

- Pre-series
 - ✓ Nb and NbTi QC **approved** by CERN. **Available** at ZRI.
 - Brazed Joints **qualified** to CERN specs. **Ongoing QC** at FNAL
- Series
 - ✓ Nb sheets QC **approved** by CERN. Stored at FNAL.
 - Nb & NbTi other materials: QC **are being approved** by CERN.
 - Nb tubes: **not yet received**. Shipping after CERN approval.
 - Brazed Joints and extra Nb: **are being procured by ZRI**
- All the materials certificates, UT and QC on [EDMS](#)

UT Report of Niobium Sheet





2244070 v.1.1	★	🛒	Material certificates and UT report, Order 657756 . Niobium RRR300. (Preseries production)
2422456 v.1.1	★	🛒	Material certificates and UT report, Order 657756. Niobium RRR300. (Series production)
2470058 v.1.4	★	🛒	Material certificates and UT report, Order 671157. Nb Rods & Plates, NbTi Rods & Disks. (Preseries production)
2476239 v.1.6	★	🛒	Material certificates and UT report, Order 671490. Nb Tubes. (Pre-series production)
2655931 v.1	★	🛒	FNAL materials qualification for Niobium Sheet (Series production)
2733735 v.1.4	★	🛒	Material certificates and UT report, Order 671157. Nb Rods & Plates, NbTi Rods & Disks. (Series production)
2733738 v.1.5	★	🛒	Material certificates and UT report, Order 671490. Nb Tubes. (Series production)
2753455 v.1	★	🛒	Material certificates and UT reports, ZRI procurement of Niobium tubes and rods (Pre Series production, welding qualification)



AUP RFD Prototypes (ZRI)

- ✓ 2 x RFD Prototypes manufactured at ZRI (PO 647590) to HL-LHC specs
- ✓ Exceeded functional requirements
(*Frequency, Deflecting Voltage, Q_0*)
- ✓ ZRI developed all the dwgs, DFMA* & tooling
- ✓ ZRI QA documentation exercised on MTF
- ✓ FNAL established QC & VTS tests
- ✓ Paved the way for Series manufacturing



* DFMA = Design For Manufacturing & Assembly

AUP Pre-series Fabrication Recap (ZRI)

- ✓ Adopted [CERN Eng. Spec.](#) & [Dwg](#) for pre-series
- ✓ Approved [Fab. Dwgs](#), [MIP](#) & [QA/QC Procedures](#)
- ✓ Approved [Weld Test Plan](#)
- Partially approved [Welding book](#)
- ✓ Addressed all the PRR recommendations

Documentation prior to Manufacturing

- ✓ Adopted the [HL-LHC quality system](#) (MTF/EDMS)
- ✓ Enhanced QC, Inspections & VTS tests at FNAL


QA/QC during production

- ✓ Validated manufacturing tooling & strategy
- ✓ Solved Pole forming issues after extensive testing

Validation of DFMA

63% of 2x Pre-series RFD completed at ZRI (Delivery to FNAL Mar 2023)

Documentation Prior To Manufacturing: Pre-series RFD Design & Fabrication Strategy





- ✓ Adopted [CERN specification drawing](#) for Pre-series RFD fabrication
- ✓ Extremities tubes machined from Nb **seamless pipes** (no roll-forming)
- ✓ **Single design** for all the Transitions (machined from a block)
- ✓ CNC interfaces and EBW joints handled as **ZRI know-how**

Documentation Prior To Manufacturing: Technical Documentation Status



- ✓ Fabrication drawings (68) **approved** by CERN

 **2080712 v.6** ● Released 🔒 Restricted access Drawing Folder
Manufacturing Drawings RFD Bare Cavities by *Manuele Narduzzi* 
Created on 2022-03-11
Last Modified on 2022-03-11


- ✓ Welding Test Plan PQR **approved** by CERN

 **2479595 v.5** ● Released 🔒 Restricted access Procedure
Test Plan PQR by *MANUELE NARDUZZI* 
Created on 2021-09-20
Last Modified on 2021-11-10

- Welding Book **partially approved** by CERN

 **2397280 v.2** ● Draft For Discussion 🔒 Restricted access Procedure
Welding book by *Manuele Narduzzi* 
Created on 2022-06-28
Last Modified on 2022-07-18

- ✓ 6 of 9 PQRs **approved** by CERN after internal qualification [EDMS 2726311](#)
- ✓ 3 x missing coupons will be ready for end of Sep 2022 (ZEN01, 07, 09)



First ZEN007 PQR was **rejected** for under penetration (2.7 instead of 3.2mm) and angular misalignment around 2°.

ZRI will provide **new sample** to CERN.

Documentation Prior To Manufacturing: QA/QC Procedures Status

- ✓ Manufacturing & Inspection Plan **approved** by CERN


2069490 v.6
● Released
🔒 Restricted access
Procedure

Manufacturing Inspection Plan - MIP
by AUP


Created on **2021-09-08**
Last Modified on **2021-09-08**

- ✓ QA & QC Procedures **approved** by CERN

- ✓ All the procedures are well established for series production
- ✓ All the PRR recommendation have been addressed (MIP & Welding Plan approval)

2069492 v.4	Cleaning and Etching Procedure	🔒 1	● Released	2021-09-20
2069496 v.1.2	Identification, Marking and Traceability Procedure	🔒 1	● Released	2021-09-20
2069497 v.3	Procedure for Radiographic Examination of Welds	🔒 1	● Released	2021-09-20
2080831 v.4	Leak Test procedure	🔒 1	● Released	2021-09-20
2080834 v.1.1	Dimensional Control Procedure	🔒 1	● Released	2021-09-15
2100569 v.2.2	Visual Testing	🔒 1	● Released	2021-09-20
2630567 v.3	Grinding Procedure	🔒 1	● Released	2021-09-30
2080833 v.2	RF measurements & Trimming Procedure	🔒 1	● Released	2021-10-13
2642947 v.1	Packing Procedure	🔒 1	● In Work	2021-10-06

QA/QC During Fabrication: Quality Approval Process

- All QC reports are uploaded on FermiCloud by ZRI

Projects > LHC-AUP > Crab Cavities > Uploads > Zanon Uploads > RFD Bare Cavities - PRE-SERIES (Z20008)

Name ↑ ▾	Modified ▾	Modified By ▾	File size ▾	Sharing
Fermilab docs & tracking	May 20	Manuele Narduzzi	2 items	Shared
NCR	July 20	Manuele Narduzzi	1 item	Shared
Pictures	A few seconds ago	Manuele Narduzzi	13 items	Shared
RFD Pre-series Drawings	May 17	Manuele Narduzzi	2 items	Shared
RFD Pre-series Manufacturing Pictures	May 17	Manuele Narduzzi	5 items	Shared
RFD Pre-series QA documents	May 17	Manuele Narduzzi	12 items	Shared
RFD Pre-series QC Reports	July 20	Manuele Narduzzi	26 items	Shared
RFD Pre-series Weldings	May 17	Manuele Narduzzi	5 items	Shared

- The documentation is **checked and approved** by FNAL (189 QCs per RFD) before it can be uploaded on EDMS/MTF for final CERN approval.

QA/QC During Fabrication: NC management

- ✓ **Guidelines** provided in AUP Quality Plan*
 - ✓ For vendors and FNAL Incoming Inspections NCs
- ✓ **Agreed** AUP-WP4 NCRs handling ([EDMS 2384617](#))
- The NC Impact is assessed by AUP team:
 - Based on Technical, Schedule, Financial and Reputational impact
 - [Collaborations Impact Matrix](#) can be used for assessment or escalate to CERN
- ✓ *All NCs are communicated to CERN upon completion of sub-assy.*
- Non-critical NCs are managed internally by AUP
 - NC documents *can* use vendor's templates
 - Special attention to Welding NCs to be discuss with CERN
- Critical NCs will be managed according to HL-LHC NC Policy (WPL^{**})
 - Critical NCs will be shared within days to CERN
 - HL-LHC NC template is used
 - AUP to provide all the info (**What, Where, When, Who, Why**)

QA/QC During Fabrication: NCR management

Example of NCRs handling

Impact assessment	Assessment scale	Financial loss	Reputation	Alignment with Business Objectives (WP Deliverables)	Who I shall inform in the project	When
Catastrophic / Extreme	5	Requiring resources outside the collaboration that can not be covered by the project	Large media (or scientific media) coverage - International coverage	Occurrence of the risk will significantly deter the achievement of all the objectives (ex, delay of the full project, not delivery of a component fully under the responsibility of the collaboration, ...)	PL, WPL, WPE	As soon as detected
Major	4	Requiring resources outside the collaboration that can be covered by the project	Host MS press coverage - Scientific media - Escalating community activism	Occurrence of the risk will significantly hamper the achievement of the objectives (ex, delay beyond the collaboration margin but not yet the WP margin, request of a permanent deviation permit for a component, engineering change request affecting the WP, ...)	PL, WPL, WPE	As soon as detected
Moderate	3	Requiring resources outside the collaboration but that can be covered inside the WP	Local press coverage - Neighbourhood reputation (public, suppliers, etc.)	Occurrence will have some adverse effect on the achievement of the objectives (ex, delay eliminating at the margin, request of a deviation permit for a component, engineering change request, ...)	WPL, WPE	In the 3 days
Minor	2		No one has heard of the occurrence of risk outside CERN; Problem dealt with at CERN's management level.	Occurrence of the risk will have minimal impact on the achievement of the entity's business objectives (magnet, cold mass, cryoassembly)	WPE	During periodic feedback
Negligible	1		No one has heard of the occurrence of the risk outside the department who owned the risk; problem dealt at department management level	Occurrence of the risk will have very little or no impact on the achievement of the entity's business objectives (magnet, cold mass, cryoassembly)	WPE	During periodic feedback


Main	Made of	Equipment data	Manufacturing	Operation	Non-conformities	Documents	History	Map
Actions :								
Failed Step		Non-conformity Document			Status			
30445898		▶ 2697012 (ver.1)			Evaluation			
Metrology (2D + 3D) + thickness measurement (MIP 8.7)		Metrology (2D + 3D) + thickness measurement (MIP 8.7) - HCACFCA002-UP000001						
30445959		▶ 2698852 (ver.1)			Evaluation			
Metrology + thickness measurement (MIP 12.7)		Metrology + thickness measurement (MIP 12.7) - HCACFCA002-UP000001						

- Non-critical NCRs upload to MTF using Vendor's template

Zanon RESEARCH & INNOVATION SRL		QUALITY CONTROL SERVICE	
NON CONFORMITY REPORT RAPPORTO DI NON CONFORMITÀ		Report N. Rapporto N. Z20008.NCR.001	Sheet 1 of 11 Pag 1 di 11
Customer Client	FNAL	P.O. No. Ordine N°	PO647590
Project Progetto	US HL-LHC Accelerator Upgrade Project	Job No. Commessa	Z20008
Drawing Disegno	3326.12.121.100 3326.12.131.200 3326.12.200.000 3326.14.121.000	Serial No° N° identificativo	HHP004 - HHP005 FP003 - FP004 FBW003 VHPW004
NON CONFORMITY DISCOVERED Emissione di non conformità			
Incoming Material Inspection <input type="checkbox"/> During NDT / control <input checked="" type="checkbox"/> During fabrication process <input type="checkbox"/> At Customer premises <input type="checkbox"/>			




QA/QC During Fabrication: Incoming Inspections at FNAL

- ✓ **Finalized** all the incoming inspections QC:
 - ✓ Visual Inspection of external surfaces and crates
 - ✓ CMM metrology and UT thickness inspection
 - ✓ Optical Inspection of RF surfaces
 - ✓ RF QC before leak check
 - ✓ Leak Check
 - ✓ RF QC after leak check



- **CMM v2: optimization ongoing**


- ✓ Inspection drawings **developed** with CERN collaboration (LHCACFCA0565)
- Simplification of CMM: the data points can be used for "as-build" 3D models



Validation of DFMA: Design and Manufacturing Tooling at ZRI


■ Forming & Calibration Tooling

- ✓ Formerly based on CERN prototypes' experience
- ✓ **Enhanced** from lessons learned after protos fabrication at ZRI
- ✓ Case study of Pole forming issues (see next slides)




■ CNC Machining & EBW Tooling

- ✓ **Developed** from ZRI expertise on SRF Cavity fabrication
- ✓ **Refined** according to ZRI know-how and lessons learned



■ Trim Tuning, Leak Test and final EBW Tooling

- ✓ **Developed** according to ZRI expertise




Validation of DFMA: Pole Forming Case Study

- Poles formed from pre-series Nb showed “orange peel” appearance and **serious thickness reductions**
- Held the production for weeks!



- Further tests with different materials provided **much better results** (shape, thickness, appearance)



Validation of DFMA:


Pole Forming: Raw Materials or Procedure Issue?

- Raw Materials checks:
 - Mechanical tests on three different materials: results **within specs** (up to 15% variation!)
 - Series Nb showed results **more suitable** for deep drawing
- Forming tooling and procedure:
 - CERN & ZRI formed a Pole from the same Nb sheet
 - ZRI's Pole showed **better results**: thickness and shape accuracy acceptable
- **Conclusion:**
 - Pre-series materials showed results **less suitable** for forming
 - Series production showed **better formability** (lower $R_{p0.2}/R_m$)
 - ZRI forming procedures **effective** even for non-ideal materials
 - ZRI adopted **CERN CMM and thickness templates** for metrology


$R_{p0.2}$ = Yield Strength
 R_m = Ultimate Tensile Strength



Validation of DFMA: ZRI Poles: Shape Accuracy history



AUP RFD Pre-Series Advancement



V-HOM Port Weldment	V-HOM WG with Insert	V-HOM WG Weldment	FPC Port Weldment	FPC WG with Insert	FPC WG Weldment
87%	88%	0%	87%	88%	0%




H-HOM & V-HOM waveguides




FPC waveguides

AUP RFD Pre-Series Advancement




H-HOM Port Weldment	H-HOM WG with Insert	H-HOM WG Weldment	V-HOM Beam Line Weldment	FPC End Group Beam Line Weldment
100%	100%	0%	100%	100%



Sub-components & Brazed Joints ready for weld

AUP RFD Pre-Series Advancement





End Cap	V-HOM End Group	FPC End Group	Main Body Weldment
100%	25%	25%	42%




End Caps, Bowls and Half Main bodies

AUP RFD Series Contract (ZRI)


- ✓ PO 685322 placed for 10 x RFD fabrication at ZRI (CERN specifications)
- Fabrication will benefit from previous manufacturing experience
 - ✓ All the QA/QC/ Manufacturing procedures have been already validated
- ✓ Kick-off meeting held on Jul 2022
- FNAL will provide most of the materials.
- Brazed Joints and testing materials will be procured by ZRI

 		<table border="1"> <tr> <th>EDMS NO.</th> <th>REV.</th> <th>VALIDITY</th> </tr> <tr> <td>1389669</td> <td>2.6</td> <td>VALID</td> </tr> </table>	EDMS NO.	REV.	VALIDITY	1389669	2.6	VALID
EDMS NO.	REV.	VALIDITY						
1389669	2.6	VALID						
REFERENCE : LHC-ACFDC-ES-0002								
ENGINEERING SPECIFICATION								
DRESSED BULK NIOBIUM RADIO-FREQUENCY CRAB CAVITIES								
Abstract The present document concerns a general description of the engineering specifications of superconducting niobium radio-frequency crab cavities of two types (DQW and RFD) to be installed in HL-LHC.								
TRACEABILITY								
Prepared by: L. Alberty, S. Atieh, L. Dassa, G. Favre, P. Freijedo Menendez, M. Garlaschè, C. Parente, N. Valverde, C. Zanoni		Date: 2021-11-19						
Verified by: G. Arduini, I. Bejar Alonso, K. Brodzinski, G. Burt, O. Capatina, S. Claudet, P. Fessia, H. Garcia Gavela, J. Gascon, F. Gerigk, T. Jones, R. Laxdal, H. Mainaud Durand, E. Montesinos, T. Otto, D. Perini, L. Ristori, L. Taviani, D. Wollmann		Date: 2021-11-30						
Approved by: Said Atieh, O. Bruning, R. Calaga, K. Foraz, F. Gerigk, B. Goddard		Date: 2021-12-08						
Distribution: HI-LUMI-LHC-WP4-MEMBERS								
2.6	22/03/2022	Rev. 2.6 set to Valid						






RFD Magnetic Shields Prototypes (Ad-Vance)

- ✓ 3D/ 2D Fabrication Drawing made at FNAL (F10129735)
 - ✓ based on STFC 253-10570-G approved by CERN
 - ✓ Subcomponents Fabrication Drawings by FNAL (50+ dwgs)
 - CERN approval for Series
- ✓ PO 667755 placed with *Ad-Vance Magnetics*
 - ✓ 3x prototypes available at ZRI for Jacketed Cavities integration
 - ✓ 11x shields on option for series



RFD He Tank Prototypes Fabrication (ZRI)

- ✓ PO 681514 **placed** for 2x He Tanks prototypes fabrication at ZRI
 - PO for 11x Series He Tanks imminent
- ✓ ZRI fab. dwgs, MIP, Weld Test and LT **checked** by FNAL for prototypes
 - CERN approval (for all QA/QC procedures) before Series fabrication.
- ✓ **Majority of materials** available at ZRI.
- ✓ **Most** of the Sub-components have been manufactured
- ✓ **Welding tests** will start shortly
- ✓ RFD proto#1 and Magnetic Shields **available** at ZRI for integration
 - **Processing** will start Nov up to Jan 2023. **Integration** will follow.



Summary & Plans

Raw materials:

All materials were purchased to approved documentation.

Pre-series materials are available at ZRI, except the extra Brazed Joints.

Most of the Series materials are at FNAL; ZRI will provide Brazed Joints.

RFD Bare Cavities:

2x Prototypes qualified at FNAL. Exceeded functional requirements.

2x Pre-series RFD are being manufactured to CERN's requirements.

QA/QC procedures approved. Welding book close to full approval.

PO placed for 10 x Series RFD at ZRI.

RFD Jacketed Cavities

PO Placed for 2x Protos at ZRI. Majority of He Tanks components ready.


CERN approval required for series production.

PO for 11 x Series He Tanks estimated in spring 2023.

Thanks for the attention!







ZRI Fabrication Strategy




ZRI welding coupon tested at CERN

- ✓ The ZEN02 and ZEN05 coupons showed **acceptable results**
- The Tuning Pin weld ZEN07 showed **some issues**



RF surface



- FNAL provided ZRI with CERN qualification results (EDMS 2726311)
- ZRI will provide a **new coupon** for CERN evaluation ETA Oct 2022