

Overview and Baseline Changes of the HL-LHC Circuits Alvaro Santiago Ferrer, Shruti Seshadri and <u>Samer Yammine (CERN)</u> on behalf of the HL-LHC Magnet Circuit Forum 12th HL-LHC Collaboration Meeting, 2022-09-21

Contents

- Updates from the HL-LHC Magnet Circuit Forum
- Design of HL-LHC Circuit-related Equipment
- Updates on HL-LHC Circuit Protection
- Documentation
- Concluding Remarks






Updates from the HL-LHC Magnet Circuit Forum

Magnet Circuit Forum


Mandate of the MCF includes:

- *MCF* is the meeting where all aspects related to powering and protection of the HL-LHC magnet circuits are discussed.
- *MCF* is mandated to follow the instrumentation and quench detection scheme of the superconducting components of HL-LHC circuits.
- *MCF, also, is mandated to validate the polarities of the HL-LHC circuits in collaboration with Polarity Controller (M. Pojer).*




- MCF has the responsibility to keep up to date the circuit configurations and parameters
- This is done through updates of the Circuit Table and the Electrical Layout (see MCF Sharepoint)
- So far 108 meetings (since June 2016), documented with minutes, follow-up of actions, etc.
- MCF is also organizing topical meetings with reduced attendance, 46 meetings have taken place so far
- MCF took responsibilities for the preparation of Engineering Change Requests and other documents related to circuit aspects
- About 50 members are regularly invited with an average participation of 25 members

Magnet Circuit Forum



HL-LHC General Instrumentation Drawings & General Quench Detection Signal Representation

HL-LHC Magnet Circuit Layout



Discussed Topics in the MCF







Updates on the Design of HL-LHC Circuit-related Equipment from last Collaboration Meeting

Splices for WP3 Superconducting Busbars

WP3 splice catalogue EDMS no. 2492410






Courtesy of R. Principe – MCF no. 108

Tests include resistance measurements at RT, mechanical tests and tests at LT in SM18 @ CERN



More info in R. Principe's Talk on THU AM

Inner Triplet Circuit Crowbars



2 kA Trim Power Converter Crowbar




18 kA Main Power Converter Crowbar with ~ 2400 Schottky Diodes in 168 parallel branches in 4 racks – could be discharged with electrical blackout and without water-cooling


Courtesy of L. De Mallac – MCF no. 107

More info on Quench Simulations E. Ravaioli's Talk

Design of Room Temperature High Current Busbars



Strong Collaboration between WP6a and WP6b – Simulations courtesy of J. Fleiter




Design of the High Current Busbars has advanced with a first validation in test bench F2 at SM18 and a pre-series design in the HL-LHC IT String

Scope and responsibilities have been defined in the ECR on EDMS no. 2453935

More information in S. Seshadri's presentation

Water-Cooled Cables Configuration



Optimisation of the WCC configuration with WP6b and WP17 – MCF no. 99 Courtesy of L. Tavian – ECR on EDMS no. 2386350



More information in S. Bertolasi's presentation

Simulations and testing to define the cooling configuration of the WCCs


Powering System – UR side (WP6a/b)

Warm Powering system and interface to DFHX/M now fully defined, incl

Adaption to latest UR layout and DFHX/M design


New UR layout: impact on DC cables and ventilation

- Optimisation and standardisation of DC cables and ventilation needs
- Definition of high current DC copper busbars, their cooling system and interfaces with DFHX/M




LHC-DFH-EC-0006 Copper busbars and water cooled plates LHC-RP-EC-0006 Courtesy of M. Zerlauth Power converters and EE systems Circuit Disconnector Boxes Change of Conceptual design of DFHX/M LHC-RP-EC-0005 LHC-DFH-EC-0006

Current Lead Heating System for HL-LHC



More information in G. D'Angelo's presentation on THU PM

DFH Instrumentation Flanges and Proximity Equipment




Prototypes at CERN under tests and validation




More information in J. Fleiter's presentation on THU PM

DFH Instrumentation Flanges and Proximity Equipment



DSL Refurbishment for the HL-LHC


- Cut DSL at 2 locations:
 - Sleeves connections, ≈ 12.3 m apart
 - \approx 7.6 m before the Q5 branch
- Installation of new connection box:
 - New splices with the expertise from TE-MSC team
- Analysis on the protection deemed the non-necessity of new V-taps and IFS for the refurbishment





Updates on HL-LHC Circuit Protection

CLIQ Efficiency Tests at Low Current in the MQXF



CLIQ Efficiency Tests at Low Current in the MQXF


	dI/dt in the time window 0.35 s <t<0.45 [a="" s="" s]<="" th=""></t<0.45>											
	No pro	tection	80	0 V CLIQ or	nly	1000 V CLIQ only						
Current [A]	Measured	Simulated	Measured	Simulated f _{rho,eff} =0.75			Simulated f _{rho,eff} =0.75	Simulated f _{rho,eff} =1.5				
3300	-36	-41	-39	-41	-161	-321	-192	-331				
2500	-30	-32	-38	-32	-60	-122	-87	-160				
2000	-34	-27	-39	-27	-27	-46	-43	-98				
1647	-3	-23	-22	-23	-23	-15	-23	-63				
1000	-23	-17	-12	-17	-17	-19	-17	-25				
	[used to d rm circuit		f _{rho,eff} =(0.75 fits bet 1.5	ter than	f _{rho,eff} =0.75 fits better than 1.5 for I≤2 kA, and vice versa						

• Effective transverse resistivity ($f_{rho,eff}$) influences coupling loss and is a key parameter for CLIQ at low current

- All simulations performed with STEAM-LEDET using f_{rho,eff} as the only fitting parameter
- Before the tests, $f_{rho,eff}=1.5$ was assumed, which resulted in overestimating CLIQ performance for I \leq 2.5 kA

Current Measurement Solutions for the QDS


 Current measurement schemes have been defined for QDS (i.e. symmetric quenches and current-dependant thresholds)



Energy Extraction of the MOSXF

Align the EES discharge resistances of the HL-LHC RQSX3 with the HL-LHC RCDRB circuits (1.4 Ω) in the aim to reduce the variants of the HL-LHC resistances.

HL-LHC Circuits (IP 1 and 5)	RQSX3
Number of circuits for HL-LHC	4
Magnets per circuit	1x MQSXF
Magnetic length [m]	0.401
I _{nom} [A]	174
L at I _{nom} [mH]	1530
E _{stored} at I _{nom} [kJ]	30.8
Previous Protection baseline	1.5 Ω EES
Present Protection baseline	$1.4 \Omega EES$



1% larger quench load

R.2: Quench protection with Rd = 1.4Ω **/oltages** Nominal current RRR = 100 (design value) 1.4 Ohm 1 Ohm 232 I Time (s) 242 -1.5 Ohr -1.4 Ohm 1 Ohm

1 Time (s)

April 6th 2022

22

Courtesy of M. Prioli – WP3 Meeting - link

HILUMI) INFN 2 K higher hot spot temperature but still within the 250 K target 10 V higher voltage to ground



HL-LHC Electrical Design Criteria for the High Order Corrector Magnets has been accordingly updated on EDMS no. 2060633 - link

Signal Interfaces between HL-LHC Circuit Equipment

Powering Failure	Quench	Discharge	Сгуо	UPS	AUG	GPM	Operator
SPA	FPA	FPA	SPA	FPA	FPA	FPA	SPA FPA

Index	CIRCUIT NAME	SYSTEM	Interface Type
1	RQX	18kA	B1 🗲
2	RTQX1	2kA	N/A
3	RTQXA1	60A	B1
4	RTQX3	2kA	N/A
5	RCBXH1	2kA	B1
6	RCBXV1	2kA	B1
7	RCBXH2	2kA	B1
8	RCBXV2	2kA	B1
9	RCBXH3	2kA	B1
10	RCBXV3	2kA	B1
11	RD1	14kA	B1
12	RQSX3	0.6kA	B1
13	RCSX3	120A	
14	RCSSX3	120A	0
15	RCOX3	120A	С
16	RCOSX3	120A	
17	RCDX3	120A	
18	RCDSX3	120A	0
19	RCTX3	120A	С
20	RCTSX3	120A	

HL-LHC change

PIC Interfaces for HL-LHC defined – based on LHC EDMS no. 1001985


Courtesy of A. Antoine – MCF no. 90



Signal Interfaces between HL-LHC Circuit Equipment

In contrast to LHC, the CL TS is routed to the PIC (vs. to the PC in the LHC)

Powering Failure	Quench	Discharge	Сгуо	UPS	AUG	GPM	Operator	CL TS
SPA	FPA	FPA	SPA	FPA	FPA	FPA	SPA FPA	SPA





Courtesy of A. Antoine and J. Fleiter – MCF no. 101

ElQA Program for the HL-LHC IT String Circuits

- Validate circuits during assembly.
- Validate the circuits for cool-down and powering.
- Acquire working experience on HL-LHC circuits.
- Acquire reference values for complete HL-LHC circuits.
- Validate ElQA test procedures and ELQA test equipment and ensure that the qualification is as tight as possible.
- ElQA in the IT String will be as similar to the final ELQA in the tunnel as possible.



Courtesy of M. Bednarek, G. D'Angelo and J. Ludwin, MCF no. 104

(CERIN)) 🖌 Hilur	ni	EDMS NO. 2746933	REV. 0.1	VALIDITY DRAFT
N	HL-LHC PROJ		REFERENCE : I	HC-XMS-OP	-0004
ELOA C	UALIFICAT	PROCEDUR		UITS IN	THE HL-
		LHC IT STRIP			
safety rules	for the successful	uence of qualification tests, tech ELectrical Quality Assurance (ELQ, assembly and commissioning pha	A) of superconducting		
		TRACEABILIT	Y		
Prepared by	: M. Bednarek, J. L	TRACEABILIT udwin, G. D'Angelo	Ŷ	Date: 202	22-06-15
Verified by:	S. Yammine, D. Bo	udwin, G. D'Angelo zzini, A. Ballarino, P. Cruikshank, I	P. Fessia,		22-06-15 (Y-MM-DD
Verified by: S. C. Hopkin	S. Yammine, D. Bo s, Y. Leclercq, M. N	udwin, G. D'Angelo	P. Fessia, list	Date: 20	
Verified by: S. C. Hopkin: Approved b	S. Yammine, D. Bo s, Y. Leclercq, M. N	udwin, G. D'Angelo zzini, A. Ballarino, P. Cruikshank, Iodena, H. Prin, MCF distribution	P. Fessia, list	Date: 20	(Y-MM-DD
Verified by: S. C. Hopkin: Approved b	S. Yammine, D. Bo s, Y. Leclercq, M. N y: M. Bajko, E. Tod	udwin, G. D'Angelo zzini, A. Ballarino, P. Cruikshank, Iodena, H. Prin, MCF distribution	P. Fessia, list teos	Date: 201 Date: 201	(Y-MM-DD (Y-MM-DD
Verified by: S. C. Hopkin: Approved by Distribution	S. Yammine, D. Bo s, Y. Leclercq, M. N y: M. Bajko, E. Tod : HL-LHC-WP	udwin, G. D'Angelo zzini, A. Ballarino, P. Cruikshank, Idodena, H. Prin, MCF distribution esco, A. Verweij, F. Rodriguez Ma	P. Fessia, list teos	Date: 201 Date: 201	(Y-MM-DD (Y-MM-DD
Verified by: S. C. Hopkin: Approved by Distribution Rev. No.	S. Yammine, D. Bo s, Y. Leclercq, M. N y: M. Bajko, E. Tod : HL-LHC-WP Date	udwin, G. D'Angelo zzini, A. Ballarino, P. Cruikshank, Iddena, H. Prin, MCF distribution esco, A. Verweij, F. Rodriguez Ma Description of Changes (n	P. Fessia, list teos	Date: 201 Date: 201	(Y-MM-DD (Y-MM-DD
Verified by: S. C. Hopkin: Approved by Distribution Rev. No.	S. Yammine, D. Bo s, Y. Leclercq, M. N y: M. Bajko, E. Tod : HL-LHC-WP Date	udwin, G. D'Angelo zzini, A. Ballarino, P. Cruikshank, Iddena, H. Prin, MCF distribution esco, A. Verweij, F. Rodriguez Ma Description of Changes (n	P. Fessia, list teos	Date: 201 Date: 201	(Y-MM-DD (Y-MM-DD
Verified by: S. C. Hopkin: Approved by Distribution Rev. No.	S. Yammine, D. Bo s, Y. Leclercq, M. N y: M. Bajko, E. Tod : HL-LHC-WP Date	udwin, G. D'Angelo zzini, A. Ballarino, P. Cruikshank, Iddena, H. Prin, MCF distribution esco, A. Verweij, F. Rodriguez Ma Description of Changes (n	P. Fessia, list teos	Date: 201 Date: 201	(Y-MM-DD (Y-MM-DD

ElQA Program for the HL-LHC IT String Circuits

	SLC	MIC-W	IT-PAQ	ΙΤΙΥ	ITIC
HVQ	~	 ✓ 	>	~	~
TFM	~	~		~	
IRC	~	~		>	
ICC	~	~	~	>	
TDR	~	 ✓ 			~
COC	~			~	~
QHR		~			
DVC		~			
TSQ	~	~			

ELQA tests during assembly

SLC – Superconducting Link Check MIC-W – Magnet Instrumentation Check IT-PAQ – Inner Triplet Partial Assembly Qualification ITIV – Inner Triplet Interconnection Verification ITIC – Inner Triplet Instrumentation Check

HVQ – High Voltage Qualification TFM – Transfer Function Measurement IRC – Instrumentation Resistance Check ICC – Instrumentation Configuration Check TDR – Time Domain Reflectometry COC – Continuity of Conductor check QHR – Quench Heater Resistance measurement DVC – Diode opening Voltage Check

TSQ - Temperature Sensor Qualification



TP4-A – Test Procedure 4 type A MIC-W – Magnet Instrumentation Check at warm TP4-B – Test Procedure 4 type B TP4-C – Test Procedure 4 type C TP4-D – Test Procedure 4 type D MIC-D – Magnet Instrumentation Check at 80 K MIC-C – Magnet Instrumentation Check at cold TP4-E – Test Procedure 4 type E

	TP4-A	MIC-W	ТР4-В	TP4-C	TP4-D +MIC-D	MIC-C	ТР4-Е
	At	At	After	During cool-down/	At 80 K	At cold	At cold
	warm	warm	flushing	warm-up	AL 80 K	AL COID	AL COIU
HVQ		~	~	~	optional	>	<
TFM	~	~			optional	>	<
IRC	~	~			optional	>	<
ICC	~	~			optional	~	<
TDR		~			optional	~	
QHR		~			optional	>	
DVC		~				>	
TSQ	~	~			optional	>	~

ELQA tests during commissioning

ELQA tests during commissioning & operation


Qualification	At warm	At warm after flushing	Cool-down 300 K to 80 K	At 80 K	Cool-down 80 K to 1.9 (4.5) K	At cold	At cold after powering	Warm-up	At warm	Cool-down	At cold	At cold after powering	Warm-up	At 80 K	Warm-up 80 K to 300 K	At warm	
TP4-A	\checkmark								\checkmark							\checkmark	
MIC-W		\checkmark							\checkmark							~	
ТР4-В		\checkmark							\checkmark							~	
ТР4-С			\sim		\checkmark			\checkmark		\checkmark			\checkmark		\checkmark		
TP4-D				~										~			
MIC-D				\checkmark										\checkmark			
MIC-C						\checkmark	\checkmark				\checkmark	\checkmark					
ТР4-Е						~	~				~	~					

More info in M. Bednarek's Talk THU AM




Documentation

Instrumentation Feedthrough Systems (IFSs)




HL-LHC General Instrumentation Drawings



29

General Quench Detection Signal Representation




Courtesy of Jens Steckert and Reiner Denz

Done for all magnet circuits in close collaboration with WP7



<u>HL-LHC General Quench Detection Signal Representation</u> <u>MCF Sharepoint</u>

MCBXFB.A General Quench Detection Signal Representation



Example for the MCBXFB.A Corrector Circuits


Circuit Description in CERN Databases

Powering ci.

Powering ci.

Powering ci..

Powering ci.





Circuits for the machine are introduced in <u>CERN Layout DB</u> Courtesy of Uwe Epting, Pedro Pinheiro, Pascal Le Roux and Markus Zerlauth

DFUXA3R1 (DFUX3R1.1)

RPHFCUL16.ROKR1 (RPHFC., B

T.DFLX.3R1.1

RSEG.ROK.R... 28-01-2013 LS3 1.5

RSEG.RQK.R., 28-01-2013 LS3 1.5

RSEG.RQK.R... 28-01-2013 LS3 1.5

RSEGROKR., 17-02-2014 L53.1.5

DOID3R1.2

TOFIX 3P1

DFLXA3R1 (DFLX3R1.1)

DWWCF.02UI16.ROX.R1





Concluding Remarks

Concluding Remarks

- During the past year, the MCF concentrated increasingly on the detailed design and implementation of magnet circuits powering and protection in line with the preparation of the HL-LHC IT String and the pre-series and series components manufacturing.
- This detailed approach and studies will continue for the next year, in view of the important validation of the circuit design in the HL-LHC IT String.
- An instrumental work was done on the General Instrumentation Drawings and the General Quench Detection Signal Representation and the introduction of the circuits in the CERN databases.

References

MCF meetings no. 92-108 (<u>indico page link</u>)
MCF Sharepoint (<u>link</u>)

HILUN MONET	Magnet Circuit Forum			Search this site • D	-LHC M cuits Fo	-		Navigate
Home Documents HL-HC Circuits Layout. LHCS:D Drawings for HL-HC Circuits Table HL-HC Circuits Table HL-HC Circuits Table HL-HC Circuits Table HL-HC Circuits Table HL-HC Circuits Table Circuit Table Circuit Table	pertaining to the optimization of circu • The MCF, also, is mandated to validate • Subjects in the agenda are defined in • Interface aspects between systems are • The aim is to prepare a set of function • Assessment of realistic failure scenario • The MCF is the meeting where aspect	e meeting where all aspects related it layouts and definition of protectio te the polarities of the HL-HL-Criccitu close collaboration with the relevant e clarified through meetings at the fc nal interface specifications that can b os and required mitigation strategies s related to high voltage withstand I	n means. s. WPs. orum. To this end, a e used as input for on a global basis i evels are discussed		Septemb	06 Sept	2 HL-MCF Meeting #108 : Design Status of the HL-LHC WP3 Splices + Instrumentation Signal Routing and Interfaces for the DFHX/M and Current Leads + Optimisation of Inner Triplet Current Monitoring Schen for HL-LHC	ne
MCF Indico Page Members List MCF EDMS Page	MCF Team				****	23 Aug	HL-MCF Meeting #107 : HL-LHC Power Converter Crowbar Design + ECR of the HL-LHC Current Leads Heating System Scope and	
Site Contents	Chair and Documentation	Samer Yammine	TE-MPE	samer.yammine@cern.ch			Responsibilities	
🖋 EDIT LINKS	Scientific Secretary	Shruti Seshadri	SV-EPC	shruti.seshadri@cem.ch	July 2022	2		
	General Instrumentation Drawings	Alvaro Santiago Ferrer	TE-MPE	alvaro.santiago.ferrer@cern.ch	,			
	Members			HI-LUMI-LHC-WP1.WG-MCF-MEMBERS@cem.ch	12 Jul HL-MCF Meeting #106 : Updates on the Insertion of the Layout DB + Follow-up on the HL-LHC LHCLSE			
	Info List			HI-LUMI-LHC-WP1.WG-MCF-FOR_INFO@cern.ch		Update of the MCF Circuit Parameters Table + AOB: Follow-up of MCF Actions		



Thank you to the participants and collaborators of the MCF for all their efforts

Thank you for your attention