



# Highlights of MCBXF Activities at Elytt Energy

O. Durán, C. Martins, **F. Toral** (CIEMAT)

J. C. Pérez (CERN)



12<sup>th</sup> HL-LHC Coll. Meeting – 21<sup>th</sup> Sept. 2022

# Index

- MCBXF series contract
- Production of components
- First short magnet assembly MCBXFB02
- Quality assurance
- Conclusions

# Let's start with a reflection...

- The **key question** is: Should a magnet prototype be developed in house or in industry?
- In the case of MCBXF magnets, I have no doubt:
  - **Short experience** on nested magnets in the community
  - Some **novel problems** to overcome:
    - Hard radiation resistance requirement for a nested superconducting magnet
    - Coil wound with a high number of Rutherford-cable turns
  - Some **surprises**:
    - Cables at coil heads are not laying down
    - Internal stresses in slim 3D-printed stainless steel spacers
    - Tolerances in large fine-blanked collars
  - An **enemy** more dangerous than initially expected: torque at coil heads

# Let's conclude from the reflection...


- Series contract strategy is based on **accumulated experience**:
  - Clear mitigation of risks
  - Shorter learning curve
  - Precise definition of manufacturing procedures
  - Easier choice of quality assurance methods
- **Last but not least**:
  - Overall cost is lower
  - Long lead times of some components is overcome with stocked ones
  - The traveling distance to the company is time-consuming and follow-up cannot be so close

# MCBXF series contract

- Contract signed with **Elytt Energy** at **March 2021**: delivery of 6 long (A) and 11 short (B) MCBXF magnets.
- All **documents** and **templates** (technical specification, acceptance criteria, manufacturing and inspection plan, quality documentation...) have been agreed with CERN.
- CIEMAT has prepared detailed **procedures** for each step of production: coil winding, binder, impregnation, assembly, parts production (ground insulation, collar packages, collaring shoes). They are uploaded to EDMS. There are thousands of photos to help **know-how transfer**.
- **CIEMAT staff** has been at Elytt premises during six months for know-how transfer on coil production. Daily support for production follow-up, questions and incident solving. **CIEMAT and CERN staff** has supported the first magnet assembly at Elytt.
- CIEMAT is supporting Elytt to contact **suppliers** for components, tooling and materials.

# MCBXF series contract: parts exchange

- **CIEMAT** is supplying the copper wedges, the end spacers and the collars (fine blanked). It means an important effort for quality assurance.
- **CERN** is supplying the insulated superconducting cable, the steel for the collars, the iron for the yokes, the keys for the outer dipole collars and the instrumentation of the collars.
- **CERN** has supplied the warm magnetic measurement bench and training.
  - CERN has trained a CIEMAT colleague during three months.
- **CERN** will take care of powering tests (at SM18 or FREIA).
- **CIEMAT** and **CERN** are supplying some components for series production that are not arriving at Elytt in time.



*Magnetic measurement bench  
(Courtesy J. C. Pérez)*

# Index

- MCBXF series contract
- Production of components
- First short magnet assembly MCBXFB02
- Quality assurance
- Conclusions

# MCBXF series: Elytt Energy facilities

- Two closed **clean rooms** with controlled humidity and temperature:
  - Coil production:** two lines (winding machine + binder mould + impregnation), component preparation (preforming ground insulation and collaring shoes, collar package assembly, collared coil assembly).
  - Magnet assembly:** collaring press, yoke assembly, magnetic and final electrical measurements.



Hall with two clean areas:  
coils (left) and magnets  
(right)



Coil production area

Magnet assembly area




Courtesy: Elytt Energy



# MCBXF series: coil production at Elytt




*IL Winding*





*IL Binding*



*Impregnation mould assembly*




*OL Winding*



*OL Binding*

Courtesy: M. Oñate  
(Elytt Energy)



*First  
finished  
coil*

# MCBXF series: coil production

- Delicate production process with a **long learning curve**: in-site support with detailed procedures.
- Three inner coils and one outer coil are in quarantine because of **faulty impregnation**.
- Two inner coils were used for reassembly of second prototype (MCBXF BP2c) to **validate** the production techniques.
- Only B-type coils up to now. **A-type coil** production is being set-up.



*Coil winding*



*Binder curing*



*Impregnation mould assembly*

*Courtesy:  
Elytt Energy*

# MCBXF series magnets: other components

- Elytt is following **CIEMAT procedures** to produce ground insulation, collaring shoes and collar packages.
- **CIEMAT** provides **support** to find suppliers for other magnet components, like the iron laminations.



*Shimming plan for inner dipole*



*Collar packages for inner dipole*

# Index

- MCBXF series contract
- Production of components
- **First short magnet assembly MCBXFB02**
- Quality assurance
- Conclusions

# MCBXF series magnets: first magnet assembly

- CERN and CIEMAT have provided in-site support for the assembly of the first magnet last Summer.



*Inner dipole ready for collaring press*



*Inner dipole entering the collaring press*

# MCBXF series magnets: final measurements

- CERN and CIEMAT have provided support for electrical, mechanical and magnetic measurements.



*Electrical measurements*



*Magnetic measurement bench*

# Index




- MCBXF series contract
- Production of components
- First short magnet assembly MCBXFB02
- **Quality assurance**
- Conclusions

# MCBXF series: quality assurance

- Quality controls of each step of production are defined in the manufacturing and inspection plan (MIP), both for coils and magnets.
- A third-party inspector will follow-up production till the end of the contract.



EDMS NO. 2335157	REV. 0.0	VALIDITY DRAFT
REFERENCE: LHC-MCBXF-FP-0001		

HL-LHC: Quality Manufacturing and Inspection Plan – MCBXF Coil												
Prepared by: R. Diaz Vez, J.C. Perez (CERN) Date: 24/02/2020		Project: HL-LHC		Executing Entity: TBC Supplier: CIEMAT		Item Eq. Code: HCMCBXFB002 HCMCBXFB006		Asset Code (LHC Part Identifier): HCMCBXFB002-E90000 __ HCMCBXFB006-E90000 __		EDMS Report No:		
Verified by: _____ Date: _____		Work Package: WP03		Client: CERN (HL-LHC WP03)		Item description: MCBXF OUTER COIL OCBS11 (HCMCBXFB0073-E5000009)						
Approved by: _____ Date: _____												
No	ACTIVITY / OPERATION	APPL. STANDARDS / NORMES APPL.	APPLICABLE DOCUMENTS / DOCUMENTS APPLICABLES	REV. DOC.	INSPECTION / CONTRÔLE				3 <sup>rd</sup> PARTY / SURVEILLANCE	NOTES / COMMENTAIRES / REPORTS		
					EXECUTING ENTITY		SUPPLIER				CLIENT	
					Code	Signature/Date	Code	Signature/Date	Code	Signature/Date	Code	Signature/Date
A	PRODUCTION START-UP											
A.1	Magnet Procedures version 805688000.		All Magnet 805688000.		IN	 15-06-2022						Check if all applicable 805688000 are in the last version available
A.2	Production start-up				IH	 15-06-2022	H	 28-06-2022	N			Notification by email

MIP for coil production



EDMS NO. 2335158	REV. 0.0	VALIDITY DRAFT
REFERENCE: LHC-MCBXF-FP-0002		

HL-LHC: Quality Manufacturing and Inspection Plan – MCBXF Magnet												
Prepared by: R. Diaz Vez, J.C. Perez (CERN) Date: 24/02/2020		Project: HL-LHC		Executing Entity: TBC Supplier: CIEMAT		Item Eq. Code: HCMCBXFB001		Asset Code (LHC Part Identifier): HCMCBXFB001-E90000 __				
Verified by: _____ Date: _____		Work Package: WP03		Client: CERN (HL-LHC WP03)		Item description: MCBXF MAGNET		EDMS Report No:				
Approved by: _____ Date: _____												
No	ACTIVITY / OPERATION	APPL. STANDARDS / NORMES APPL.	APPLICABLE DOCUMENTS / DOCUMENTS APPLICABLES	REV. DOC.	INSPECTION / CONTRÔLE						NOTES / COMMENTAIRES / REPORTS	
					EXECUTING ENTITY		SUPPLIER		CLIENT			
					Code	Signature/Date	Code	Signature/Date	Code	Signature/Date	Code	Signature/Date
A	INNER COLLARING COMPONENTS											
A.1	Acceptance of Inner Collaring components				N			N				Upload to EDMS all Traceability & dimensional reports (components)
A.2	Inner Coils Acceptance				IH							Inner Coils Acceptance Documents
B	INNER COLLARED COIL											
B.1	Shimming plan for Inner collared coils		Inner Dipole Assembly procedure		N			H		H		Upload to EDMS the Shimming Plan Report
B.2	Inner Collared Coils, Electrical test (before collaring)		Electrical Test procedure		N			N				Upload to EDMS the Electrical Test Report

MIP for magnet assembly





# MCBXF series: documentation

- Traceability is guaranteed thanks to documentation stored in **MTF**.
- Drawings, minutes, measurements and other documents are stored in **EDMS**.

**MTF**  
Equipment Management Folder

Actions: Show NCR Report Search: Equip

**Assembly Tree** **Equipment Folder : Made Of**

HCMCBXF012-E5000001 - Dipole Orbit Corrector Q2 SERIES ELYTT  
 HCMCBXF214-E5000001 - Yoke Stacks  
 HCMCBXF217-E5000001 - Endplates assembly  
 HCMCBXF230-E5000001 - Connection Plates assembly  
 HCMCBXF072-E5000001 - Outer Collared Coil  
**HCMCBXFBC073-E5000001 - Outer Coil**  
 HCMCBXF\_C001-E9000025 - Insulated Cable  
 HCMCBXFBC074-E5000001 - Outer Wedges  
 HCMCBXFBC075-E5000001 - Outer Spacers  
 HCMCBXFBC076-E5000001 - Fiber Glass Insulation  
 HCMCBXFBC077-E5000001 - Interlayer Insulation  
 HCMCBXFBC078-E5000001 - Outer loading Plate  
 HCMCBXFBC067-E5000003 - Cable supplement  
 HCMCBXF\_C033-E5000003 - Cable reinforcement  
 HCMCBXF\_C045-E5000001 - End filler  
 HCMCBXFBC073-E5000002 - Outer Coil  
 HCMCBXFBC079-E5000001 - Outer Collaring Shoo  
 HCMCBXFBC080-E5000001 - Outer Collar Sets  
 HCMCBXFBC091-E5000001 - Outer Ground Insulation

**Equipment Identifier:** HCMCBXFBC073-E5000001  
**Other Identifier:** OCB504  
**Description:** Outer Coil

Order #	Type	Id / Material Part Number	AltS Comparison	Show
10	Equipment	HCMCBXF_C001-E9000025 Insulated Cable	101EC034E	
20	Batch	HCMCBXFBC074-E5000001 Outer Wedges	1 Unit(s)	
30	Batch	HCMCBXFBC075-E5000001 Outer Spacers	1 Unit(s)	
40	Batch	HCMCBXFBC076-E5000001 Fiber Glass Insulation	1 Unit(s)	
50	Batch	HCMCBXFBC077-E5000001 Interlayer Insulation	1 Unit(s)	
60	Batch	HCMCBXFBC078-E5000001 Outer loading Plate	1 Unit(s)	
70	Equipment	HCMCBXFBC067-E5000003 Cable supplement		
80	Equipment	HCMCBXF_C033-E5000003 Cable reinforcement		
90	Batch	HCMCBXF_C045-E5000001 End filler	1 Unit(s)	

Example of coil data stored at MTF

Signed in as: f

Mailbox: Inbox | Caddio Search

CERN-000162400 Public access  
**Manufacturing procedures**

Info


More info

#	Id	Title	Files	Status	Created on	Author	Document type	Ta
10	LHC-MCBXFBC-F	MCBXF Series Inner Coil Inne...	1	Released	2020-09-21	Jesus Garcia M	Fabrication ...	
20	LHC-MCBXFBC-F	MCBXF Series Inner Coil Out...	1	Released	2020-09-21	Jesus Garcia M	Fabrication ...	
30	LHC-MCBXFBC-F	MCBXF Series Outer Coil Inn...	1	Released	2020-09-21	Jesus Garcia M	Fabrication ...	
40	LHC-MCBXFBC-F	MCBXF Series Outer Coil Out...	1	Released	2020-09-21	Jesus Garcia M	Fabrication ...	
50	LHC-MCBXFBC-FP	Connection Box Assembly	1	In Work	2021-07-01	Elena Fernand	Fabrication ...	
60	2575045 v.1	Assembly operation of the MC...	1	Released	2021-05-04	Elena Fernand	Report	

Example of procedures stored at EDMS

# MCBXF series: coil dimension measurements

- Coil dimension is measured with accuracy in a **coordinate measurement machine**.
- The coil is **clamped** to the winding mandrel to reduce the deformation due to internal stresses in free state.
- Those measurements are used to define the **shimming plan** (0.1 mm shim -> 15 MPa preload).



Outer coil at CMM

# MCBXF series: electrical measurements (I)

- Electrical design criteria are defined in [EDMS 2363905](#).

Maximum expected coil-to-ground voltage at quench (V)	$V_{sim (ground)}$
Test voltage at NOC at 'Manufacturing Facilities and Test Stations' stage (V)	$V_{test1 (ground)} = 2 * V_{sim (ground)} + 500$
Test voltage at warm <sup>(1)</sup> before first helium bath (V)	$V_{test2 (ground)} = 2 * V_{test1 (ground)}$
Test voltage at warm <sup>(1)</sup> after helium bath (V)	$V_{test3 (ground)} = V_{test1 (ground)} / 5$
Test voltage at NOC at 'Tunnel' stage (V)	$V_{test4 (ground)} = 1.2 * V_{sim (ground)}$

<sup>(1)</sup> T = 20±3 °C and humidity lower than 60%

**Table 2. Maximum voltages to ground for MCBXFA/B corrector magnets with energy extraction resistance of 0.15 Ω.**

Magnet		Nominal current (A)	Maximum voltage to ground (V)
MCBXFA	Inner Dipole (ID)	1584 A	238
	Outer Dipole (OD)	1402 A	210
MCBXFB	Inner Dipole (ID)	1625 A	244
	Outer Dipole (OD)	1474 A	221

# MCBXF series: electrical measurements (II)

Table 3. Nested orbit correctors electrical test values at 'Manufacturing Facilities and Test Stations' stage.

Test name	Test voltage	Value
Test voltage at NOC at 'Manufacturing Facilities and Test Stations' stage (V)	$V_{test1 (ground)}$	1000
Test voltage at warm <sup>(1)</sup> before first helium bath (V)	$V_{test2 (ground)}$	2000
Test voltage at warm <sup>(1)</sup> after helium bath (V)	$V_{test3 (ground)}$	200
Maximum leakage current ( $\mu$ A) – not including leakage of the test station		10
Test voltage duration (s)		30

Table 4. Nested orbit correctors electrical test values at 'Tunnel' stage.

Test name	Test voltage	Value
Test voltage at NOC at 'Tunnel' stage (V)	$V_{test4 (ground)}$	300
Test voltage at warm <sup>(1)</sup> after helium bath (V)	$V_{test3 (ground)}$	200
Maximum leakage current ( $\mu$ A)		10
Test voltage duration (s)		30

# MCBXF series: magnetic measurements

- Magnetic measurement **bench** developed by CERN.
- CIEMAT staff has been **trained** at CERN to handle the bench and post-process the measurements.
- CIEMAT staff is **supporting** the first measurements at Elytt and training them to use the bench.



# Conclusions

- The series magnets are in production at **Elytt Energy**.
- **CIEMAT** and **CERN** have provided **support** to set up the production: in-site help, procedures and know-how transfer.
- The **first two valid inner dipole coils** have been assembled into **MCBXFBP2c** magnet, which has been successfully tested. It validates the coil production process at the company.
- The **first short magnet** is being shipped to CERN today.
- **A-type** coil production is being set-up.





## Acknowledgements to:

Manuel Domínguez, Óscar Durán, Jesus Angel García Matos, Luis González, Jesús Jiménez, Carla Martins, José Antonio Pardo, Pablo Sobrino from **CIEMAT**

Hugues Dupont, Nicolas Eyraud, Michael Guinchard, Lucio Fiscarelli, Sylvain Mugnier, Juan Carlos Pérez, Ezio Todesco from **CERN**

**All the Elytt Energy staff participating in this project**

