



## HL-LHC Upgrade Project

Corfu Summer Institute 2022

Markus Zerlauth with acknowledgements to O.Brüning, M.Lamont, L.Rossi, J. Wenninger and many other CERN colleagues



## HL-LHC Upgrade Project

Corfu Summer Institute 2022

Markus Zerlauth with acknowledgements to O.Brüning, M.Lamont, L.Rossi, J. Wenninger and many other CERN colleagues

# Outline

- LHC design performance and HL-LHC upgrade goals
- Completion of LIU, start of LHC Run 3 and lessons learnt for HL-LHC era
- Status of key (technological) deliverables towards the HL-LHC upgrade
  - Civil engineering
  - Final focusing magnets for lower beta\*
  - Superconducting Link
  - Crab cavities
  - IT String
- HL-LHC as a truly international project (with recent challenges)
- Current Project planning and performance ramp-up

# Introduction: LHC Performance Goals

Collision energy: Higgs discovery requires  $E_{\text{CM}} > 1 \text{ TeV}$

p collisions  $\rightarrow E_{\text{beam}} > 5 \text{ TeV} \rightarrow \text{LHC: } E = 7 \text{ TeV} \quad [3.5/4\text{TeV}; 6.5\text{TeV}; 6.8\text{TeV}]$

Instantaneous luminosity: rate of events in detector  $= L \times S_{\text{event}}$

rare events  $\rightarrow L > 10^{33} \text{ cm}^{-2} \text{ sec}^{-1} \rightarrow L = 10^{34} \text{ cm}^{-2} \text{ sec}^{-1} \quad [2 \cdot 10^{34} \text{ cm}^{-2} \text{ sec}^{-1}]$


Integrated luminosity: total number of events  $L = \int L(t) dt$

$300 \text{ fb}^{-1}$  with  $1 \text{ barn} = 10^{-28} \text{ m}^2$  and femto =  $10^{-15}$  [205 fb<sup>-1</sup>]

depends on the beam lifetime, the LHC cycle and  
'turn around' time and overall accelerator efficiency

# CMS Integrated Luminosity, pp

Data included from 2010-03-30 11:22 to 2018-10-24 04:00 UTC



# Goal of High Luminosity LHC (HL-LHC):

The main objective of the HL-LHC is to determine and build a hardware configuration and a set of beam parameters that will allow the LHC to reach the following targets:

Prepare machine for operation beyond 2025 and up to **2040**

Devise beam parameters and operational scenarios for:

# enabling at total integrated luminosity of **3000 fb<sup>-1</sup>**

 # implying an integrated luminosity of **250 fb<sup>-1</sup> per year**,

# design oper. for  $\mu \leq 140$  ( $\rightarrow$  peak luminosity **5 x 10<sup>34</sup> cm<sup>-2</sup> s<sup>-1</sup>**) 


$\rightarrow$  **Operation with levelled luminosity!**

$\rightarrow$  **10 x the integrated luminosity reach of first 10 years of LHC operation!!**

# Outline

- LHC design performance and HL-LHC upgrade goals
- **Completion of LIU, start of LHC Run 3 and lessons learnt for HL-LHC era**
- Status of key (technological) deliverables towards the HL-LHC upgrade
  - Civil engineering
  - Final focusing magnets for lower beta\*
  - Superconducting Link
  - Crab cavities
  - IT String
- HL-LHC as a truly international project (with recent challenges)
- Current Project planning and performance ramp-up

# CERN accelerator complex



▶ p (proton)   ▶ ion   ▶ neutrons   ▶  $\bar{p}$  (antiproton)   ▶  $\leftrightarrow$  proton/antiproton conversion   ▶ neutrinos   ▶ electron



# LHC Injector Upgrade Project (LIU)




- HL-LHC performance relies on more intense and brighter bunches from the injector complex (2.2E11p / 2um at SPS extraction wrt to LHC nominal of 1.15E11p / 1.5um)
- 25ns beam limited by space charge in PS, PSB, SPS; SPS RF and SPS longitudinal instabilities
- 50ns beam limited by PS longitudinal instabilities due to space charge and SPS TMCI

Linac4 in for Linac2	<ul style="list-style-type: none"> <li>H<sup>-</sup> injection into PSB at 1.3 GeV</li> <li>Expected double brightness of LHC beams out of the PSB</li> </ul>
Booster	<ul style="list-style-type: none"> <li>Increase energy to 1.3 GeV</li> <li>New RF system</li> <li>New main power supply</li> </ul>
PS	<ul style="list-style-type: none"> <li>Injection at 1.3 GeV</li> <li>Production schemes</li> <li>Feedback systems: new wide-band longitudinal feedback; transverse feedback against head-tail and e-cloud instabilities</li> </ul>
SPS	<ul style="list-style-type: none"> <li>Power upgrade of the main 200 MHz RF system</li> <li>Electron cloud mitigation through a-C coating (baseline) or beam induced scrubbing</li> </ul>

Successfully deployed during LS2 in 2019/2020

# PS Booster : LHC Beam Production


- PSB managed to achieve the LIU target for the **LHC brightness already in 2021**
- **Performance re-established in 2022** after
- ✓ **BCMS**: operating on emittance plateau
- Flexibility for lowering the brightness



# PS : LHC multi-bunch Beam Status - BCMS


- Measurements shown from 3<sup>rd</sup> of June in parallel with PSB and SPS
  - Values at c2843 (h84) before extraction (only 1 measurement)
  - Using PSB cycle with reduced tails
- Both BCMS and LHC 25 ns cycles are ready
- Target brightness demonstrated

Intensity	H emittance	V emittance
1.66e11 p/b	0.98 $\mu\text{m}$	0.90 $\mu\text{m}$
1.80e11 p/b	1.01 $\mu\text{m}$	0.98 $\mu\text{m}$
1.94e11 p/b	1.03 $\mu\text{m}$	1.19 $\mu\text{m}$




# SPS : LHC multi-bunch Beam Status - BCMS

- Measurements shown from 3<sup>rd</sup> of June in parallel with PSB and SPS
  - Values at c2843 (h84) before extraction (only 1 measurement)
  - Using PSB cycle with reduced tails





Excellent brightness for both Standard and BCMS beams

## Beam for high intensity MDs: BCMS




Brightness can be slightly improved at the expense of transmission

# LHC schedule coming out of Long Shutdown 2




# Training quenches RB Circuits



**Collision energy of (HL-)LHC is strictly linked to achievable current of the 1232 (= 8 x 154) LHC main dipole magnets**

- 5 sectors reached 6.8 TeV equivalent, 3 sectors reached 7 TeV
- No sign of permanent degradation.

# Training history RB.A23



- The 64 quenches in S23 after the 2<sup>nd</sup> additional TC came as a surprise, as usually training goes faster after a TC
- Detailed analysis of the dipole training campaigns is ongoing, including results from reception tests in SM18.

# Total nr of quenches in LHC main dipoles

Nr of quenches in the same dipole magnet	Nr of dipole magnets
5	3
4	11
3	56
2	154
1	446
0	562




## Conclusion:

- Still 562 dipole magnets (45%) never experienced a training quench in the LHC since 2008.
- Some circuits (including corrector circuits) showed much longer training than in previous campaigns, and their behavior will be closely monitored in the coming years.
- Desired operating currents can still be reached (with only a few exceptions) 14 years after the start of the LHC, with several thermal cycles, numerous current cycles, radiation, and large number of quenches.
- a quench is a very violent process (especially in the high-current circuits), and that each quench implies a certain unavoidable risk (short-to-gnd, internal short, quench heater failure, etc).




# UFOs and their interactions with the LHC beams

- Dust particles are inevitably present in the LHC vacuum chamber
- They get charged and can travel along the electric and magnetic fields of the beam and the surrounding magnets
- Interactions with the high intensity proton beams generate fast, localised beam losses that affect operation (and can generate magnet quenches)




(a)




(b)

Dust samples from the ceramic tube of an injection kicker magnet. (b) shows an enlarged view of an Al<sub>2</sub>O<sub>3</sub> particle with a radius of about 5 μm




Examples of orbits of charged dust particulates around the LHC beam. Beam screen height is ~37 mm

# UFO conditioning in Run2 compared to 2022



Blue dots = **UFO rate**, red dots = **fill-averaged intensity**, orange crosses = **quench**

# UFO rate 2015 vs 2022



- In general, situation much better than in Run 2 due to the very fast conditioning of the UFO rate
- But the impact of UFOs evidently depends on the BLM threshold strategy

## Conclusion:

- Expected re-conditioning of UFOs at the start of Run3.
- Much lower quench margins at 7 TeV and with HL-LHC beam parameters
- (Part) of physics behind UFO mechanism still not fully understood


# Electron cloud and cryogenic heat load

- Electrons are inevitably produced inside the LHC beam chamber. Seed electrons come e.g. from synchrotron radiation hitting the chamber's walls and ejecting electrons, or from the ionization of the residual gas.
- These electrons can subsequently be accelerated by the proton bunches. When they hit the vacuum chamber wall, they have a probability of ejecting more electrons, the cycle continues, and the electron cloud (e-cloud) is created.
- Parameter of interest is the Secondary Emission Yield (SEY), which is the average number of electrons produced per impact
- E-cloud both affects beam quality and considerable increases heat load on cryogenic system -> Potential limitation + electricity cost!
- Mitigation: 'Scrubbing' runs where increased bunch intensity and train lengths are injected to condition the beam screens

# Electron cloud and cryogenic heat load


Evolution of the secondary emission yield (SEY) over the 2022 scrubbing run has shown a

- A clear reduction of the average SEY is observed in every sector
- Conditioning is initially fast and gets slower as the SEY decreases



# SEY evolution over scrubbing run


- Significant conditioning has taken place in every sector
  - Sector 78 showed significantly higher SEY than the other sectors from the beginning, and stays higher even after conditioning
  - Sectors 34 and 45 continue to show the lowest SEYs, as in Run 2




# SEY comparison to 2018


A first analysis has been performed to compare the present cell-by-cell SEY to 2018

- In most sectors, the SEYs are currently very close to their 2018 values (at 450 GeV)
  - The differences are within the error bars of the analysis
- Sectors 67 and 78 still show much higher SEY than in 2018
- Sector 56 shows a mildly higher SEY than in 2018





# LHC / HL-LHC Plan



**Run3 (physics production) started in July 2022!**

**Beam Energy for Run3 fixed @ 6.8 TeV**

**Long EYETS 2024-25**

**LS3 shifted by 1 year and extended to 3 years**

**→ HL-LHC keeps the construction schedule unchanged where possible to keep the momentum!**

**→ But shifts the IT String operation to 2025**




# Outline

- LHC design performance and HL-LHC upgrade goals
- Completion of LIU, start of LHC Run 3 and lessons learnt for HL-LHC era
- **Status of key (technological) deliverables towards the HL-LHC upgrade**
  - Civil engineering
  - Final focusing magnets for lower beta\*
  - Superconducting Link
  - Crab cavities
  - IT String
- HL-LHC as a truly international project (with recent challenges)
- Current Project planning and performance ramp-up


# HL-LHC technology landmarks

No accelerator project has so many challenging novelties covering such a broad technology spectrum

**Technology intensive project!**



CERN February 2022



Civil Engineering work for HL-LHC will be completed by end of 2022!

# HL-LHC civil engineering status (Point 1)


Overall progress Sep '21: **69%**

## Underground

## Surface


**STATUS: 2021.05.21**

- EXISTING STRUCTURES
- TO BE EXCAVATED
- ALREADY EXCAVATED
- FINAL LINING



**STATUS: 2021.05.21**


- TO BE CONSTRUCTED
- COMPLETED STEEL STRUCTURES
- COMPLETED PRECAST CONCRETE
- COMPLETED CIP CONCRETE



Expected completion by **October 2021**  
(including + ~1 month due to Covid-19)

**STATUS: 2021.05.21**

- TO BE CONSTRUCTED
- COMPLETED STRUCTURAL ELEMENTS
- COMPLETED ARCHITECTURAL FINISHES



Expected completion by **September 2022**  
(Including + ~1 month due to Covid-19)


# HL-LHC civil engineering status (Point 1)

Overall progress today: **98%**

## Underground

STATUS: 2022.02.28

- TO BE CONSTRUCTED
- COMPLETED STEEL STRUCTURES
- COMPLETED PRECAST CONCRETE
- COMPLETED CIP CONCRETE




Completed 2021  
(including + ~1 month due to Covid-19)

## Surface

STATUS: 2022.05.20

- TO BE CONSTRUCTED
- COMPLETED STRUCTURAL ELEMENTS
- COMPLETED ARCHITECTURAL FINISHES



Expected completion by September 2022  
(Including + ~1 month due to Covid-19)

# HL-LHC civil engineering status (Point 1)

SD17 Building



Green Spaces



# SF (cooling tower) building

SF17



SF57



L. Taviani, HL-LHC TCC, WP17, 09 Jun'22

# SHM (cryo-compressor) buildings

SHM17



SHM57



CV room  
(plenum installation)



# Inauguration Ceremony planned for December 2022



# Underground works at P5



US57 cavern



UR55 gallery

PM57 shaft

# Delivery of the SF57 & SHM57 buildings


SHM57

SF57

SD57

SU57

SE57




# Technical galleries

Point 1



Point 5






Requires novel cold powering system to connect equipment in new UR galleries to tunnel

# New interaction region layout


- New insertion and final focusing magnets
  - Main quadrupole magnets MQXFA (Q1, Q3) from AUP and MQXFB (Q2) from CERN
  - Superconducting separation and recombination dipoles, D1 from Japan and D2 from Italy
  - Higher Order Corrector package (CP) and orbit correctors (MCBX) from Italy and Spain

ATLAS  
CMS



LHC


ATLAS  
CMS




HL-LHC

# Update on MQXFA Cryo-Module Assembly

*Fitting of bottom SS shell and longitudinal welding*







# Update on MQXFB cold tests

- August 2022: MQXFBP3 test @ SM18:  
Re-welded cold-mass from MQXFB01 with lower pre-stress of stainless-steel shell  
But still using coils from initial production



# Testing of D1 Prototype at KEK

- Lifting up the D1 magnet




- Insertion into vertical cryostat



# MCBXFBP2c: Cold Powering tests results

*Design iteration on length of the inner coil produces successful performance increase!*



**Ciemat** Centro de Investigaciones Energéticas, Medioambientales y Tecnológicas



# D2 Cold-Mass Assembly


*D2 Prototype on the test bench in SM18*

*D2 Prototype Cold-*




# Timeline: Main Milestones in 2022

- July 2022: Canted Cosine Theta Corrector production at BAMA in China → Iteration on former grooves and assembly procedure: CB09 and CB12 train faster ✓




Training History of the HL-LHC CCT Coils



# Higher Order Corrector Package


- November 2021: HO corrector manufacturing and assembly completed ✓



*Sequence of corrector packages and preassembled cold mass*

## Timeline: Main Milestones still upcoming in 2022

- Fall 2022: cold test of first MQXFA horizontal Cold Mass
- Fall 2022: Cold test D2 Cryo Module
- End 2022: delivery of D1 Prototype to CERN
- End 2022: Cold test of MQXFB02 in SM18 [**still using coils from initial production!**]



Requires novel cold powering system to connect equipment in new UR galleries to tunnel



# MgB<sub>2</sub> Cable Assemblies (1/2)


Received from ICAS 2<sup>nd</sup> (Triplets) and 3<sup>rd</sup> (Matching Sections) MgB<sub>2</sub> series cables



**Successfully HV tested both in industry  
and at CERN**



To be produced: 5+5 Units



- Wire grading and cable map approval procedures established
- Continuous tests at CERN of extracted strands from each constituent cable before approving further operations – **694 test pieces in 2021**
- Production planned to be completed by end 2022

# SC Link Cryostats

Received first series SC Link cryostat for Triplets – produced in industry

Leak/pressure tests at the company



Delivery & Reception @ CERN







**Final length for Triplets: 74.5 m**

Optimization of leak test **procedure**

Visual and endoscopic inspections, dimension controls


# First DFHX constructed @ CERN (2/3)



Completed blank assembly of DFHX and studied of MgB<sub>2</sub>/HTS routing

# DFX Cryostat

Completed pre-series DFX by SOTON (UK1) !




**CERN-UK1 collaboration** under addendum #4 of KE3299/TE/HL-LHC

Design, Manufacturing, QC & CE certification under the responsibility of **Southampton University**

**PRR** 3 March 2020. 1.5 intense years from raw material procurement to completion of qualification and **CE certification** by notified body

**Completed in March 2022** at LTI Metaltech & delivered to CERN



# Update on RFD Cryo-Module





*RFD Cavity in Transport Frame on arrival at Daresbury Laboratory*

*Completed RFD Cryo-Module to be installed in SPS for final beam validation in 2024*

*Outer vacuum Chamber*

*Cavity String prior to Cleanroom assembly*



**Corfu, September 2022**

**Markus Zerlauth, CERN**

# Outline

- LHC design performance and HL-LHC upgrade goals
- Completion of LIU, start of LHC Run 3 and lessons learnt for HL-LHC era
- **Status of key (technological) deliverables towards the HL-LHC upgrade**
  - Civil engineering
  - Final focusing magnets for lower beta\*
  - Superconducting Link
  - Crab cavities
  - **IT String**
- HL-LHC as a truly international project (with recent challenges)
- Current Project planning and performance ramp-up


# HL-LHC testing facilities in SM18

IT Test Area

Magnet Testbenches

SRF Section

Cold-powering Test Area






## Important milestones

- Overall integration
- Vacuum and cryogenics
- Electrical systems



# New IT String Schedule


End of STRING test: April 2025




# Outline

- LHC design performance and HL-LHC upgrade goals
- Completion of LIU, start of LHC Run 3 and lessons learnt for HL-LHC era
- Status of key (technological) deliverables towards the HL-LHC upgrade
  - Civil engineering
  - Final focusing magnets for lower beta\*
  - Superconducting Link
  - Crab cavities
  - IT String
- **HL-LHC as a truly international project (with recent challenges)**
- Current Project planning and performance ramp-up


# HL-LHC is a world-wide collaboration!



# Truly International Collaboration offering exiting opportunities!



# Truly International Collaboration offering exiting opportunities!




# Russian in-kind contributions

- HL-LHC included a collaboration agreement with the Russian federation for the provision of
  - Construction of Low impedance collimators
  - Construction of crystal collimators
  - Copper part of HTS current leads
  - Upgrade of the HL-LHC beam dumping system (dilution kickers and dump cores)
  - Hollow electron lenses for beam halo control
  - Beam Loss monitors
  - Construction of Beam position monitors
  - Experimental passive absorbers
  - Crab cavity powering system and distribution
- The agreement being left without funding from the Russian ministry, critical milestones could not be met for these deliverables, and CERN recently had to terminate the agreements for (the majority) of deliverables to avoid schedule risks for the project
- Despite partial descoping of some items and exploration of new in-kind contributions, this has a major impact on the CtC of project


# Outline

- LHC design performance and HL-LHC upgrade goals
- Completion of LIU, start of LHC Run 3 and lessons learnt for HL-LHC era
- Status of key (technological) deliverables towards the HL-LHC upgrade
  - Civil engineering
  - Final focusing magnets for lower beta\*
  - Superconducting Link
  - Crab cavities
  - IT String
- HL-LHC as a truly international project (with recent challenges)
- **Current Project planning and performance ramp-up**





# LHC / HL-LHC Plan




## HL-LHC TECHNICAL EQUIPMENT:



## HL-LHC CIVIL ENGINEERING:



# Expected HL-LHC performance




# TDR V1.0 - The last version of the TDR including the added scope - 2020



**V0.1 Published in electronic version for the October 2016 Cost & Schedule review**

[EDMS: 1723851](https://cds.cern.ch/record/1723851)

and as CERN Yellow Book in October 2017



Updated Version V 1.0 published as  
CERN Yellow Book in December 2020


<https://e-publishing.cern.ch/index.php/CYRM/issue/view/127>




HiLumi  
HL-LHC PROJECT

Thank you for your attention!  
Question?

# Operational Scenario for HL-LHC




# LHC Injector Upgra



- HL-LHC performance relies on more intense and brighter bunches from injector complex (2.2E11p / 2um at SPS extraction wrt to LHC nominal of 1.15E11p / 3.4um)
- 25ns beam limited by space charge in PS, PSB, SPS; SPS RF power and SPS longitudinal instabilities
- 50ns beam limited by PS longitudinal instabilities & SPS space charge and SPS TMCI

# Peak luminosities of Hadron colliders




Worldwide Integrated Luminosity prior to LHC: ca.  $11 \text{ fb}^{-1}$

x 35

LHC Design Goal:  $300 \text{ fb}^{-1}$  → LHC likely to reach end of Run3:  $350 \text{ fb}^{-1}$  to  $400 \text{ fb}^{-1}$



HL-LHC goal:  $3000 \text{ fb}^{-1}$  to  $4000 \text{ fb}^{-1}$  !

x 10



# HL-LHC Upgrade Ingredients: Crab Cavities

- Attempt to claw back the very significant reduction in luminosity from the large crossing angle
- Create an oscillating transverse electric field that kicks head and tail of the bunches in opposite directions
- Serving to mitigate the effect of the crossing angle at the IP
- Challenging space constraints:
  - requires novel compact cavity design






# SPS Test Program for CCs

- The DQW module (2021 & 22) still to do
  - Demonstrate max stable voltage (nominal required 3.4 MV)
  - Intensity reach up to 4 batches of 72 bunches with LIU intensities
    - only possible in 2022 and beyond
- Swap to RFD module delayed until 2023-24 YETS. Validation program:
  - Max voltage, impedance, cavity alignment & operational aspects
  - Measurement of crabbed beams jitter & potential feedback
  - $\mu$ TCA development & deployment for crab LLRF (presently on VME)

# F2 Upgrade activities - May 2022

WP6a gratefully acknowledge the solid support of all teams involved

SC Link cable chain trials (SM18)




## System test main equipment:

- DFX – SM18 pre-assembly
- DFHX – SMI2 pre-assembly
- Cu current leads – Bld 100
- HTS cable – in manufacture
- Sc link cryostat – Flex building
- Sc link cable – Bld 927
- CL heater rack – SM18
- QDS racks – SM18
- CFB shuffling module – SM18

SM18 Cluster F2 Test Bench Safety Assessment, edms 2703683 by T.Otto.

Patch Panel is taking shape....



## Patch Panel Assembly:

- Support structures - installed
- CRG helium panel - installed
- WCC - installed,
- WCC cooling - ongoing
- ACC installed,
- Signal cabling installed,
- Cu parts PPI installed
- Cu parts 18kA busbar - delay
- IP2X cage - in manufacture



L Rossi & O. Brüning @ Director review for CD2 - 18 July 2018