

ISOLDE Technical Report

70th Meeting of the INTC – 22nd of June 2022

Joachim Vollaire (Technical Coordinator) on behalf of ISOLDE Technical Teams

22/06/2022



Outline

- Facility restart and operation (low energy physics)
- Target Production and RILIS highlights (PI-LIST)
- REX-HIE ISOLDE status
- Update on some projects
- Conclusions



SY

Accelerator Systems

(STI)

Low energy lines commissioning and operation

- Stable beam commissioning of low energy lines started on the 04/02
- Reference configurations saved for both Frontends, different target types and for all beam destinations. Facilitate beam tuning during operation period.
- Protons to the BTY line on the 07/03 (~2 weeks of online commissioning before physics)
- Physics started end of March.





Low energy lines operation





Non "standard" targets:

- 2 PI LIST targets online
- 2 quartz line targets

RILIS laser schemes high demand

~5E19 protons received so far



SY Accelerator Systems

(STI)

CÉRN



Quartz line and PI-LIST targets production

Two PI-LITS targets online

Two quartz line targets produced (hot and cold line)





Assembly visualization



STI







SY

Accelerator Systems



199192 **PI-LIST: High-resolution in-source spectroscopy**

Standard

Spectroscopy

laser

laser



IS664, 05/2022: First experiment using PI-LIST at ISOLDE

- Additional operation mode of the LIST ion source featuring perpendicular laser/atom interaction
- Reducing spectral linewidth from few GHz to ~200MHz 0 (at cost of efficiency loss)
- Application for high resolution spectroscopy and isomer-pure RIB production
- New data on nuclear shapes in Ac isotope chain 0



RILIS + CRIS + COLLAPS + LISA network: Joint development of high-resolution versatile laser systems



SY

70th Meeting of the INTC – 22nd of June 2022



Status of REX-HIE ISOLDE

HIE-ISOLDE linac

22/06/202

Difficult recommissioning of REX-HIE ISOLDE Linac:

- 3 compressor station cuts (reconditioning required)
- End of May: 7GP1 (NC accelerating structure) can't hold the required accelerating gradient

The 7GP1 spiral resonator:

- Accelerating structure of the REX linac
- In operation for ~ 20 yrs
- Beam energy: from 1.2 to 1.55 MeV/u
- RF power: ~ 80 kW for A/q = 4.5

HEBT lines

Accelerator Systems

(STI)



wk. number	21	Beam through cryomodules (ahead of time thanks to D. Valuch who completed the hardware commissioning of the SRF cavities)
	21, 22	Beam commissioning of REX linac (phasing, reference set-ups)
	23, 24	Beam commissioning of HIE-ISOLDE linac
	25	Beam commissioning of the HEBT lines
	26	First stable beam to users
	28.29	Setup and first Radioactive Ion Beam (RIB) to users



Input:J.-A. Rodriguez Rodriguez, E. Siesling S. Ramberger, C. Gagliardi

REXEBIS

7GP1

REX linac

REX-ISOLDE 7gap1 investigations

- Extensive RF measurements to validate proper functioning of the amplifier and status of RF cables
- Cavity opened twice (endoscopy inspection). No defect found.
- Several external vibration measurements. Permanent measurement setup (data logging)
- Strong vibrations felt end of May in the tunnel have disappeared (most likely caused by cryogenic compressor in nearby building)

With low external vibration (for the moment) operation possible as is (not further investigations) Focus on beam commissioning



199192









New nano-laboratory (actinide target production)

- Glove boxes for the new nano-laboratory installed in MayNew laboratory for actinide target production (uranium and thorium).
- Fully enclosed process (currently done under fumehoods.)











SY

Accelerator Systems





ISOLDE Beam Dumps Replacement Study

- Project focuses on two concepts (BASIC and FLEXI)
- More detailed study for FLEXI ongoing (include costing)
- Detailed dismantling study launched (external consultant)



Accelerator Systems



Upgraded Frontends (beyond LS3)





Fire Safety upgrade (primary areas ventilation)

Follow-up of HSE recommendations to limit the radiological consequences of a fire in ISOLDE target area Implementation of iodine retention system (release of radioactive iodine during target changes)





SY

Accelerator Systems



STI



Conclusions

- Commissioning (extensive) and operation of low energy lines with no major problem
- Demanding physics program (targets diversity and RILIS schemes)
- First High-resolution in-source spectroscopy with the PI-LIST target/ Excellent synergies between RILIS/CRIS/COLLAPS/LISA network
- Recommissioning of REX-HIE ISOLDE Linac on the critical path:
 - 7gap1 instability seems to be under control since the last days
 - Different technical problems encountered have reduced the time allocated for beam commissioning (tunnel access, cavity reconditioning after cryo problems...)
- Other parallel activities for consolidation and upgrades (nano-lab, beam dumps, safety consolidation, PUMA@ISOLDE, target elimination....)





home.cern