


# Construction of the Scintillating Fibre Tracker


## Challenges and lessons learned




Ulrich Uwer  
Heidelberg University  
Krakow 26/09/2022

# SciFi Overview

3 m



11,000 km fibre




12 layers w/  $3 \times 5 \text{ m}^2$   
→  $340 \text{ m}^2$  active area

12 C-frames  
w/ 2 layers (x+u/v)  
each w/ 12 (10) mod.  
→ 128 modules



528k channels  
4096 optical links



2.3 TB/s (~40% LHCb)

Modular design (mechanics, modules, electronics) – very successful

# The Project Organisation (Production)




Frames	Services	Module & Coldbox Finishing	Services, Piping & Cabling
Modules	SiPMs	Mechanical Frame Assembly	SiPMs, Electronics & DAQ
Coldbox	Electronics	Survey & Alignment	Controls & Monitoring
Cooling Blocks	Cables & Pipes		




## Challenges:

- 11000 km
- Radiation hardness of fibres
- Light-yield & attenuation length
- Homogeneity
- Cladding
- Production & price

## Measure light yield and attenuation per spool (12km)




Scan every millimeter: measure diameter, check cladding.



Fast acceptance check of all fibres by one lab (CERN) was important!

# Biggest Problem: Bumps



Significant number of „bumps“  $>350 \mu\text{m}$ : destroy winding pattern of mats.


→ even w/ optimization of production process producer was unable to eliminate the “big” bumps (had to accept in average 8 bumps per 12 km)

Even experienced producers cannot always provide flawless products.

# Bump Removal



Automatic bump shrinkage using a “hot drawing” tool. Applied routinely.




Caveat:

1-2 bumps per spool are larger than 500 μm → shrinking fails.





Those were manually removed by cutting & gluing.

UV curing glue:  $t = 10-15s$  per bump.




# Production quality was excellent

– also as result of our fast feedback.



# Monitoring revealed another problem


Stored reference samples show a slight decrease of the attenuation length over time due to oxidation.



**-1.4%/year**



Extrapolation to 14 years:



Observed already before by producer and others.  
 Surprising for us. Not critical for the operation of SciFi.


The more you check the more problems you find!




# Fibre Mat Production

About 1100 + spares mats (130 mm × 2.5 m) needed → 4 production centres

Four equal winding machines produced in industry:



Threaded wheel to align:





Mat alignment:




# Optimization of Mat Production

## TDR design: Glue casting




## Production: Foil lamination



Be open for optimization steps even if they deviate from TDR design.





# Production Organigramm



To ensure the same quality of all production sites we used exactly the same tools, procedures and test stands (we verified test results by exchanging mats).



This sounds much easier than it was!

# Quality Assurance: Winding Pattern



# Light Yield & Mirror Reflectivity


For every mat:  
light yield  
before and after  
mirror glueing



Pre series → | ← main series




# Production Schedule

Fibre mat winding



8

# Module Production



## Initial problems:

- Lateral bending of mats
- Shrinkage of fibre mats
- alu endplugs incorrect


→ immediate feedback to winding centres







# Every step was monitored for every module

Cutting of fibre mats to the correct widths → damage fibres




Straightness of the mats after first gluing:



## Another light yield test – complete module


Cosmics  
Sr-90

Cosmic Test for FSM00005 analyzed 2016\_11\_14





# Module Production Schedule

Module production parallel to mat winding!









# Coldboxes



# Module Finishing & QA w/ Cosmics





# Electronics Readout



SciFi (528k channels) – 4096 GBT links (max. 2.3 TB/s)

Correct modularity important: yield versus number of connections!

# PACIFIC Frontend Chip (40 MHz)



## Minimal ASIC functionality:

- No ADC – 3 thresholds to access the pulse height
- No digital data-processing → use FPGA
- 338 registers (8 bits) for chip configuration

## History:

May 2013: PACIFICr0 (preamp)

Nov 2013: PACIFICr1 (analog FE)

Aug 2014: PACIFICr2 (8 chan analog)

Jul 2015: PACIFICr3 (full 8 chan, 130nm)

Sep 2016: PACIFICr4 (optimization)


Mar 2017: PACIFICr5 (production, different)

Test beams


If possible keep the ASIC simple. Chip designer should be involved in testing, the development of the carrier boards and in test beam studies!



## Packaging of preseries:



Company made mistake with unique QR codes in first batch: all chips are “Ser.No. 1”, human readable number missing → laser etched chip numbers in Heidelberg instead





Anything than can go wrong will go wrong.


- All chips have been tested and qualified (tuning parameters measured).
- Carrier boards have been developed and produced in parallel
- Carrier boards have undergone again a similar test as the chips.

# Cluster Boards using antifuse FPGA

Clustering for noise suppression and data compression ( $\rightarrow \times 0.5$ ):



Use antifuse FPGA (Microsemi IGLOO2)  
(expected radiation dose  $\sim 100$  Gy 10krad)



Remark:

CERN studies showed that these FPGAs still work at that level. Studies reported „problems w/ programmability“

$\rightarrow$  our own test at CERN's irradiation facility:  
programmability can be lost after 1krad ( $\sim 1$  year)



5100 FPGAs needed → international tendering required

## Tendering procedure via CERN (VAT):

- ~4 month of preparation with the CERN purchaser officer to agree on the "best" procedure and produce all the documents.
- 1 month for the publication
- 1.5 month between the opening of the offers and the sending of the order (price negotiation, etc.) and not smooth at all!


Order submitted: 25/07/2019

1st batch delivery: 25/10/2019

2nd batch delivery: 21/11/2019

Purchase process of expensive parts can easily take ~1 year.

# Master Board




Provide connections:  
 LV Power  
 HV (SiPM)  
 Optical transceivers:  
 Slow/Fast ctrl, data links  
 DC-DC power converter  
 House-keeping FPGA

Many connectors!



Mechanically and electrically very demanding board!

# Electronics Cooling

Power dissipation of full Readout Box: 120 W → 30 KW SciFi  
 Water cooling necessary – integrated in the mounting structure.  
 Cooling structure connected to water cooled cooling-plates.




Cooling must be integral part of the front-end design!



# Testing of finished Readout-Boxes



Only about 50% of the ~275 tested ROBs passed the tests w/o interventions: all other ROBs required exchange of boards / optical components or other interventions (all components have been tested before!!). Testing of the ROBs became a bottle neck for the C-frame assembly at the end of 2021.





All Readout Boxes have undergone a very detailed test (incl. bit error tests of all links).

Very time consuming: Required lengthy cleaning of the optical transceivers and the optical connectors (delicate operation).

Test developed as result of commissioning.




# „Slice test“ – test beam w/ full readout chain before launching serial production



(Nearly) final readout electronics:  
 PACIFIC-5q boards  
 Master Boards (v3)  
 4 x Cluster Boards (v2) + 12 (v3) w/ 2 different  
 clustering algorithms  
 MiniDAQ2 (PCI40 1<sup>st</sup> version)

32 optical links,  
 4096 channels




$\sigma < 70 \mu\text{m}$   
 $\epsilon > 99\%$



# Support Mechanics: C-Frames



Extruded aluminum I-profiles:



Company (world leader) was a real pain!  
 Extrusion quality sometimes very bad!  
 Company unable to machine the profiles.  
 Delivery schedules completely unreliable.


**Don't rely on a single industrial producer!**

# Detailed 3D CAD-model of the C-frame





Integration of all services was very difficult! Prototype was very helpful.

# Full C-Frame Prototype (frame #0)




Fullsize prototype including services, electronics and modules etc.  
 Extremely useful to test mechanics, cabling paths, electronics readout ...  
 Expensive but extremely valuable investment!



Condensation on vacuum insulated cooling pipes, cold-box, dry air exhaust.

Full commissioning and operation of the 1<sup>st</sup> C-frame revealed system problems which could not have not been before: noise on LV, condensation, <sup>36</sup>


# Mitigation of Condensation



We launched a detailed study mitigate the problem using active heating → after review in Oct 2019 we continued with the assembly.

Be prepared for system effects which only show up with final detector.

Commissioning of all service systems and of Electronics:






## COVID-19 Crisis:

	CF1	CF2	CF3	CF4	CF5	CF6	CF7
Location	Slot 2	Slot 1	Slot 4	TS-Cage	TS-Cage	Slot 3	Cavern
Mechanics	ok	ok	ok	ok	ok	In progress	ok
Water	ok	ok	ok	ok	ok		ok
NOVEC	ok	ok	ok				
Dry-gas	ok	ok	ok	ok			
Modules	ok	ok	ok				
Cabling	ok	ok	ok	ok	ok		ok
Heating	ok	ok	ok				
Electronics	ok		ok				
Optical Fibres	ok		ok				
Commissioning	ok	In progress (NOVEC)	In progress (Electronics)				


In February 2020 all components at CERN, work on 4 frames in parallel ...

# Installation - Prototyping





# Test Installation of 2 empty frames





# Installation of 1<sup>st</sup> 4 frames in May 2021



Installation and connection of C-frames went very smooth.  
Most time consuming was the connection of the optical links.

# First SciFi Data

mean TAE shift per SiPM (Run 241111)



Not working links:

0 / 1024 control links  
 ~8 / 4096 data links



High functionality a  
 result of the many tests  
 that have been done

## My tips:

Dense QA for all components: testing, testing, testing (many issues we had initially overlooked to monitor popped up during the many tests we were doing).

Early and full-size prototypes of all components: The knowledge gain easily balances the additional costs and efforts.

### Electronics:


Full chain tests already w/ an early version of the electronics. Realistic “slice test” of a larger system before serial production is launched.


Take Engineering Design and Production Readiness Review serious.

Purchase of material takes time.  
Don't trust quality of industrial suppliers..










~300 photons / MIP  
(only 2x5% are captured)

CERN-LHCb-PUB-2015-011



Light emission peak 460 nm  
Attenuation length ~3.5 m


Ionizing radiation degrades light transmission property:  
50 fb<sup>-1</sup> (35 kGy) → 40 % reduction for particles near the beam-pipe




*Fibre scanner, LHCb-PUB-2015-009*

- All fibre spools scanned for mechanical defects and irregularities (so far ~6000 km scanned).
- We observe “bumps” = local increase of diameter.
- Bumps  $>350 \mu\text{m}$  (typ. ~8 per 12500 m) produce irregularities in winding pattern and must be removed.
- Automatic bump shrinkage using a “hot drawing” tool. Applied routinely.

*LHCb-PUB-2016-010*








### Performance:

- peak PDE = 48% (at 3.5 V)
- direct cross-talk = 3 %
- delayed cross-talk = 2.5%
- afterpulses < 0.1%.


Dark count rate per channel after neutron irradiation:

[Characterisation of the Hamamatsu silicon photomultiplier arrays for the LHCb Scintillating Fibre Tracker Upgrade](#), Axel KUONEN, TIPP 2017

Direct x-talk prob.





dark count rate (DCR) per channel



DCR halved every -10 K:


$\Phi = 6 \cdot 10^{11}$  n<sub>eq</sub>/cm<sup>2</sup> → 14 MHz at -40C

# SiPM Cooling and Alignment - Coldbox




Coldbox 3D printed Ti cooling bar, carry/align 16 SiPMs

SiPM on flex print




- Cold box (3D printed nylon) at each end of fibre module; houses 16 SiPMs at -40°C, aligned and in optical contact to fibre ends.
- **Challenges:** thermal insulation, humidity management inside box (total length 130m)
- Pre-series under production.

# Clusterization



2 bit/channel  
 low, middle,  
 high threshold  
 passed



A readout ASIC for the LHCb Scintillating Fibre (SciFi) tracker, X. HAN at TIPP 2017

Clustering = key to noise / data reduction:

Dark count rate w/  $6 \times 10^{11} \text{ n}_{\text{eq}} / \text{cm}^2$   
 $\sim 14 \text{ MHz} / \text{channel}$



cluster rate  $0.8 \text{ MHz} / 128 \text{ channels}$   
 calculate x-position of clusters