Investigation and Considerations about Option #2 (install SuperFGD in ND280 w/o HA-TPC's: Install SFGD in ND280 – uninstall it – install Bottom TPC – install SFGD in ND280 again)

Option #2: considerations from WG1

Comments from Franck

- To be considered the cabling/uncabling work
 - not a big issue for SFGD (C.Mauger Electronics WG)
 - more complicated for ToF detector because it's more fragile and has a lot of cables to be plugged (F.Cadoux)
- It may be considered to install SFGD w/ partial ToF installation, i.e. that does not need to be removed later for Bottom-TPC installation
- Be careful to avoid shocks Typical risk during detector installation

Summary: Risk assessment of the crane acceleration in the lifting

• Acceleration measurement of the crane at the NM building were performed to evaluate the risk in the lifting detector.



- Comparable with the general standard value of 0.1G in every direction.
- · Lower acceleration than the seismic standard of 0.65G is confirmed.
- \rightarrow Relatively small risk w.r.t. the requirement for an earthquake.
- Other risk mitigations under discussion
 - A guide to the basket during the detector installation
 - Transportation between buildings (NA \rightarrow NM)

A.Gendotti





Static FEA analysis (worst-case scenario): all cubes move together along the same direction. Very unlikely

1 G along Z (gravity)

- Max deformation ~2.6mm bottom panel, smooth
 1.65G along Z (gravity + earthquake)
- Max deformation ~4.3mm bottom panel, smooth Near the box holes the deformation is almost 0

Still 1G along Z (gravity) and 0.65G along Y

- No change on bottom panel deformation.
- Max ~3mm side panel deformation but smooth
- Near the box holes the deformation is almost 0

Important consideration: the FEA static shows the worst-case scenario to be considered as a safety margin that the target (5mm max deformation) is achieved

A.Gendotti







4

A.Gendotti

Last Verifications:

• Threads calculations at the aluminum Frame

Threads have a relatively big safety marge in the ALU frame \rightarrow SF=8 for M6 and SF=3 for M8

• Stress Calculation with finer mesh at the Alu Frames

Stress calculated with finer mesh shows always a consistent low stress of 54 MPa

• Stress Calculation at Brackets during Lifting

By calculating the stress during lifting using only 2 lifting point, the stress is always inside the Margin of Safety MoS = 0.577 (MoS includes all the safety Factors i.e Material safety factor and load safety factor). If MoS is > or = to zero, it can be considered as safe.

- No major problems about mechanics and sagging
- Hard to say what happens about fibers inside the box as it can't be modeled. In general, people don't very worried about breaking fibers during the lifting
 - very low crane acceleration
 - conservative assumptions made about cubes in the FEA model (cubes are strong and when pressed it will be a rigid body)
 - However, it's not possible to make a precise model of cubes+fibers inside the box

Overall, the box design was done to be safe for earthquake with minimal deformation. However, it's not possible to model fiber+cube inside box, so there could be other boundary conditions (displacement of cubes from vibrations, variation of size and hole position of the cubes, etc.) that can't be taken into account precisely.

Run Plan JFY2022-2023 - (K.Sakashita-san @T2K bi-weekly 21/7/22)

Run plan based on discussions so far

 March beam time is important because lets ND280 check new beam, so

A. if March beam time is given, we request

- 1+a cycles in Jan. for beamline commissioning(w/o ND280),
- 1 cycle in Mar. w/ ND280
- 1 cycle in Jun. w/ ND280 partially upgrade, and
- 3 cycles after October w/ ND280 full upgraded
- B. if March beamtime is not given, we request
 - 1+a cycles in Jan. for beamline commissioning(w/o ND280),
 - 2 cycle in Apr.-Jun. w/ ND280 (possibly w/o upgrade), and
 - 3 cycles after October w/ ND280 full upgraded