


Available test beam facilities and specific infrastructure



Manuel Guittièrre
manuel.guittiere@ijclab.in2p3.fr



Time Resolution Pb/Polystyrene 3°+3°




Low energy
(below 6 GeV)




High energy
(up to 100 GeV)






- Location: Hamburg (Germany)
- DESY II electron/positron synchrotron:
 - Circumference: 292.8 m
 - Injector for 2.3 km-long PETRA III storage ring (High-brilliance X-ray source)
- **Test beam hall (bld. 27):**
 - 2 test beam campaigns with LHCb ECAL prototypes in 2022 (2 weeks in May + 1 week in November/December)



- Electron/positron accelerated by DESY II up to 7 GeV
- Bremsstrahlung photon beam generated by a carbon fiber target
- Photons converted to e^+/e^- pairs via a metal plate target (Cu or Al)
- Resulting beam momentum selected by setting the dipole magnet current before the collimator


- Electron/positron beam: rate up to $\sim 1\text{k part./cm}^2$
- Selectable energy from 1 to 6 GeV
- Momentum spread: 1.5 to 12.7%
- Divergence ~ 1 mrad
- Good availability of the beam (very rare interruptions)
- Good stability of the beam (very few variations of the rate)

Testbeam 24 (e- @ 6 GeV)




B (T)	\bar{p} (GeV/c)	σ (GeV/c)	$\frac{\sigma}{\bar{p}}$ (%)
0.12	0.907	0.116	12.7
0.30	2.162	0.197	9.1
0.44	3.001	0.111	3.7
0.59	3.989	0.128	3.2
0.75	5.078	0.163	3.2
0.90	6.003	0.093	1.5

Link: [The DESY II test beam facility](#)




- Setup installed at TB line 24 (May 2022):
 - **2 MCP-PMTs**: time reference
 - **Telescope**: tracking
 - 1 pair of **organic scintillators**: trigger signal
 - Dark box with ECAL prototype, connections, rotating axes to incline the module






- 6 planes of Mimosa26 silicon pixel sensors
- Operated by EUDAQ framework and analyzed by Corryvreckan offline reconstruction software
- Spatial resolution on reconstructed tracks $\sim 2\mu\text{m}$




- 1 pair of organic scintillators downstream of the telescope providing a trigger signal in coincidence

- 2 MCP-PMTs providing a reference for time measurements: intrinsic time resolution $\sim 15\text{ps}$






- ECAL Prototypes placed in a dark box designed to fix them, set their angular inclination with remotely-controlled rotating axes and manage connections with HV power supply and DAQ system (more details in Matteo's talk)
- Box fixed on a 2-axes moveable support, remotely controlled from the control room (maximum load: 1t, sub-millimeter (x,y) precision)



- Location: CERN (Switzerland)
- Super Proton-Synchrotron
 - Circumference: 7 km
 - Injector for LHC
- Test beam hall (North Area) located in Prévessin (France)
 - 2 test beam campaigns with LHCb ECAL prototypes in 2022 (2 weeks in May + 2 weeks in October)



- Protons (primary) accelerated by SPS up to 450 GeV
- Interaction with primary target (Be) initiating hadronic cascades followed by electromagnetic cascades (hadrons, muons, electrons produced)
- Neutral beam selected with magnets and collimator and converted into e^+/e^- pairs or hadrons
- Type and momentum of the particles in the experiment area selected using a series of adjustable magnets and collimator

Parameters	T2		T4	
	H2	H4	H6	H8
Beam Line	H2	H4	H6	H8
Maximum Momentum [GeV/c]	400 / 360	400 / 330	- / 205	400 / 360
Maximum Acceptance [uSr]	1.5	1.5	2	2.5
Maximum $\Delta p/p$ [%]	$\pm 2.0\%$	$\pm 1.4\%$	$\pm 1.5\%$	$\pm 1.5\%$
Maximum Intensity / spill * (Hadrons / Electrons)	$10^7/10^5$	$10^7/10^6$	$10^7^{**}/10^5$	$10^7^{**}/10^5$
Available Particle Types	Primary protons ^{***} OR electrons OR muons OR mixed hadrons (pions, protons, kaons)			



- Available particles: electrons, muons, primary protons, mixed hadrons
- Selectable energy from ~20 and up to ~300 GeV (electrons measured during last test beam campaign in October)
- Momentum spread below ~2%
- Divergence ~ 2 μ rad
- Variable availability and stability of the beam (relies on main users activities e.g. LHC)



- Setup installed at TB line H2 (October 2022):
 - **2 MCP-PMTs**: time reference
 - 1 pair of **organic scintillators**: trigger signal
 - **3 Delay Wire Chambers**: tracking
 - Dark box with ECAL prototype, connections, remotely controlled rotating axes to incline the module (more details in Matteo's talk)



- DWC: X-Y Multi Wire Proportional Chambers with cathode delay line readout
- Working area: 120 x 120 mm²
- Gas: Ar (80%) and CO₂ (20%)
- HV: 2.25 kV
- Readout: CAEN TDC V1290N
- Resolution (one chamber): ~100 μm



- Beam facilities at DESY II and CERN SPS accelerators allow to perform measurements with ECAL prototypes on a wide range of energy ($\sim 1\text{-}300$ GeV)
 - ➔ Important measurements to characterize the prototypes, the PMTs, the cables and for the readout electronics R&D
- 4 test beam campaigns (2 at DESY + 2 at SPS ~ 7 weeks) already achieved in 2022 in addition to 2020 and 2021 campaigns (many results presented yesterday) → more to come next year
 - ➔ Beam time requests at DESY and SPS already discussed
- Follow Matteo's talk for more details about the inside of the prototype box and on the DAQ operations!

Thank you!