

Progress on the new beam telescope


Ettore Zaffaroni
ECAL Upgrade II Workshop
13/12/2022

Outline

- Current telescope setup
- Requirements
- The SciFi telescope
- Status and plans

Current telescope setup

- 2 x MCP PMT for time reference
 - ~ 14 ps average time resolution
- 2 x (Scintillator + PMT) used for trigger (discriminated and in coincidence)
- Light tight experimental box with the module inside.
- 3 x DWC for tracking and shower/multiple hits rejection
 - SciFi telescope will replace these!




Requirements

- Spatial resolution $< 500 \mu\text{m}$ on both axes
- Surface covered $> 120 \times 120 \text{ cm}^2$
- Compact
- Up to 1 kHz acquisition rate
- $> 90\%$ efficiency with all the planes combined
- Low material budget $< 0.1 X_0$



The telescope

- Build using small SciFi mats
 - 2 perpendicular mats, x-y coordinates
 - 13x13 cm²
 - Completely light-tight
- Dedicated readout electronics
 - Developed for SND@LHC, different from LHCb
- < 100 μm resolution, ~ 250 ps time resolution
- $\sim 0.007 X_0$ thickness per module
- 2 modules will be enough for this setup




The SciFi mats

- Same concept as the ones in LHCb, just way shorter
- 2 mats assembled together at 90°
- Mirrors glued on one side, to increase light yield



The SiPMs

- Same SiPMs used in LHCb SciFi
- H2017 multichannel arrays from Hamamatsu
 - 250 μm pitch, 512 channels per side




The electronics

- One DAQ board and 8 front-end chips per side
- Data sent over Ethernet to a computer
- Boards run synchronously
 - Clock delivered via optical fibre
- SiPMs biased via the board

To SiPMs


Front-ends

CycloneV
FPGA + CPU





The DAQ software

- Software used in SND@LHC
- DAQ data server
 - Online event builder and noise suppression
 - ~100 kHz max event rate
- VME server-client
 - Controls a VME crate for clock and synchronous reset
- System controlled with python scripts
 - Should be easy to integrate in existing DAQ



Status

- Mechanical pieces ready
- Fibre mats are being finalized
- SiPMs glued on supports and tested
- Assembly will begin this week



Plans

- Assemble 2 modules at EPFL
 - This week
- Take part of the setup to EPFL to test integration of the DAQ systems
 - 2nd half of December
- Debug the system and take cosmic runs
 - To have it ready for the next testbeam
- Develop tracking software

Conclusions

- New telescope based on small SciFi modules is being built
- Software already available
 - Used in SND@LHC
- Setup assembled at EPFL between December and January