Upgrade of ATLAS Hadronic Tile Calorimeter for the High Luminosity LHC

DIS2023 28/03/2023

Ahmed Tarek On behalf of the ATLAS Collaboration





High Luminosity LHC conditions

- The high-luminosity LHC (HL-LHC) aims to provide $3000 4000 \text{ fb}^{-1}$ of integrated luminosity (factor 10 w.r.t integrated luminosity of the first LHC runs!)
 - LHC will increase the instantaneous luminosity a factor 5-7 times the current instantaneous luminosity
 - With an average number of interactions per-bunch crossing of 140 to 200 ⇒ extremely challenging conditions for the detectors
 - Full detector upgrade is needed to withstand these conditions and maintain physics performance
 - Extensive HL-LHC upgrade programs are developed, usually labelled as *Phase-II upgrades*



ATLAS Upgrade plans

• ATLAS is planning an extensive upgrade program for HL-LHC (Phase-2 upgrades)

- L1 Trigger upgrades at 1 MHz, 5.2 TB/s, 10 μ s latency
- Electronics upgrade for the electromagnetic and hadronic calorimeters
 - Fast readout at 40 MHz and new electronics to withstand high radiation
- New High Granularity Timing Detector to improve pile-up separation, with 30 ps timing precision
- New RPCs, sMDTs and TGCs Muon chambers to improve momentum resolution and trigger efficiency
- New All silicon Inner detector with finer segmentation and reduced material budget



ATLAS hadronic calorimeter: TileCal

- TileCal is the Hadronic calorimeter covering the most central region of ATLAS
 - Using plastic scintillating *tiles* as active material and iron plates as absorber
 - Light produced in the tiles is transmitted via wavelength shifting fibres to photomultiplier tubes (PMTs).
 - Electronic signals from ~10k PMTs are measured and digitised every 25 ns and signals transfer to data-acquisition systems.
- Divided into long barrel LB ($|\eta| < 1.0$) and 2 extended barrels EB ($0.8 < |\eta| < 1.7$), composed of 64 modules in ϕ
- Calorimeter cells range from 10 MeV to 2 TeV dynamic range with hadrons energy resolution:

$$\frac{\sigma}{E} = \frac{50\%}{\sqrt{E}} \oplus 3\%$$



A quick overview of the TileCal systems

On-detector

- Mechanical: **Super drawers** (SD) divided to **4 mini-drawers** (MD)
- Each MD hosts 12 PMTS each with its Front-End Boards (FEBS)
- A MainBoard (MB) digitises the output from the 12 FEBS then a DaughterBoard (DB) transfers data to the backend
- The **LVPS** systems (monitored with ELMB2) provide power for frontend electronics

Off-detector

- TilePPr (Preprocessor) buffers data from MDs, evaluates signal and provides reconstructed energy per cell for TDAQi
- **TDAQi** calculates trigger objects and communicates with TDAQ via the FELIX



TileCal Phase-II upgrades

TileCal planned upgrades for the HL-LHC

- Full replacement and redesign of on- and off-detector readout electronics to accommodate HL-LHC data-flow (new TDAQ architecture) and radiation conditions
 - Providing low-latency, continuous readout at 40 MHz
 - Fully digital input for the ATLAS trigger system
 - New low- and high-voltage power supply systems withstanding the high radiation requirements
- New modular mechanical design with (4 mini drawers) for better accessibility and maintenance
- Replacement of ~10% of the PMTs (degraded from previous runs)

Strategy: Add layers of redundancies to avoid one-point failures, increase radiation to bustness of the TileCal system



Mechanical upgrades

- SuperDrawer (SD) for Phase-II are composed of
 - 4 MiniDrawers (MD) for the long barrels (a total of 128 SDs + spares)
 - 3 MD and 2 MicroDrawers for the extended barrels (a total of 128 SDs + spares)
 - Each with 2 independent sections for redundancy
 - Mechanical design to facilitate accessibility
- <u>Production of 264 SDs is completed and shipment</u> to CERN ongoing













MD Services

SuperDrawer (SD)

- Associated and dedicated tools for installation, extraction and services (LV/HV cables, Fibre optics fan out and cooling distribution)
 - Production is completed

7

Front-End electronics

- Replacement of ~10% PMTs (9852 PMTs) due to ageing effects with new Hamamatsu R11187 model
 - Dedicated test benches developed and ready to test new PMTS

- High Voltage Active Dividers (HVADs) will replace passive HV dividers for better response stability
- Tests for irradiated HVAD in dynamic operating conditions ongoing
 - Production completed (10828 HVADs)

Front End board for the New Infrastructure with Calibration and Signal Shaping

- Shaping and amplification (2 gains) of the PMT signal and calibration (9852 boards in total)
- Built in charge injection systems for ADC calibration
- Planning to produce 11k boards
- Fully operational Burn-in Test Repair (BTR) stations
- Assembly started in Q1 2023

8





HVD in PMT Block



HVAD

FENICS

PMTs

MainBoard and DaughterBoard

- Digitisation of analog signals from FENICS and provides control for the FENICS cards
- In addition to high speed path to the daughter board
- Distributes 10 V power independently on each side for redundancy and reliability
- 12-bit dual ADCs at 40 MS/s for the 2 gain signals
- 16-bit ADCs at 50 kS/s for integrated readout
- Undergoing TID radiation tests
- Produced approximately 50% of 896 required
 - High speed interface with off detector electronics
 - Sends detector data to TilePPr electronics via high speed links (GBT)
 - 896 boards in total, used for clock and command distribution to FENICS
 - 2 GBTx chips for clock recovery and distribution
 - 2 Kintex Ultrascale FPGAS for communication and data processing (SEL tolerance)
 - 2 QSFP high speed optical modules
 - Final design expected this year
 - NIEL tests performed (post-irradiation tests ongoing) with negligible effects in most components



1 MainBoard

SEU 54 MeV proton beam (IFJ, Krakow

896 in total





•4x Uplink TX @9.6 Gbps

9

MainBoard

Low voltage power supply system

LVPS: provides power to on-detector electronics

- On-detector: LVPS box (Bricks and electronics)
- Off-detector (service cavern USA15): Aux boards, 200 VDC power supplies.
- LVPS box houses the 10 V power supplies (Bricks) and all associated electronics and cooling, 1 box per SD
 - Preparation for final design review ongoing
- LVPS bricks: 8 individual power supplies (200 VDC → 10 VDC), 8 per each SD
 - Proceeding towards pre-production with all components ordered (pending PCBs).
 - Test-station ready at CERN and Burn-in stations produced
 - Ongoing radiation tests for bricks isolation amplifiers
 - 104 Bricks planned to be produced and tested.
- ELMB2-MotherBoard: mounting of ELMB2 (Embedded Local Monitor Board 2), 1 per LVPS box
 - breakout for bricks tri-state control with very robust new design
 - <u>Production and test complete now in BTR, 156 boards</u> <u>tested</u>
- Vertical slice tests performed successfully at CERN



High-voltage system

- HV power supplies in crates in USA15 service cavern at 100 m from the detector
- High voltage power for each individual PMT
- Distance protects it from radiation related problems
- **HVremote**: 256 boards to regulate and control system off-detector at USA15, providing stable HV for the the PMTs
 - Average applied voltage ~750 V for the PMTs, stability <0.5 V rms, current 400 μA
 - Board extensively tested (all tests passed)
 - Prototypes produced and tested
- Finalised design for HV Bus (1024 boards)
- Vertical slice tests performed at lab and testbeam and showing good results so far
- Final prototype tests are planned for summer test beam 2023.







Off-detector Electronics

TileCal off-detector electronics are formed by Tile PreProcessor (PPr) and TDAQi systems

stores digitised data in large pipelines, and transmits to FELIX system upon trigger acceptance signal

- Each PPr consistent of: 1 Carrier + 4 Compact Processing Modules (CPM) + TileCoM ⇒ 32 PPr in total
 - Performs real-time data processing and reconstruction from ondetector electronics
 - Provides clock and configuration to TileCal modules
- 32 Tile TDAQi interfaces with L0Calo, Global, L0Muon and Felix system
- Error free communication achieved at 9.6 Gbps between the CPM and the TDAQi
- **Carrier**: Power distribution, communication between CPM, TileCoM, TDAQi, DCS
- Compact Processing Module (CPM) Readout and control TileCal modules, Energy reconstruction, calibration and transmission to TDAQi
 - Each CPM operates 2 TileCal modules (up to 8 modules per PPr)
 - Data handling from on-detector electronics and signal reconstruction
 - Real time reconstruction at 40 MHz per PPr
 - Communication with timing trigger and control system for the LHC
 - Tests (thermal) and test-beams planned at CERN





Off-detector Electronics

- Tile Computer on Module (TileCoM) Interfaces the TDAQi system and the TilePPr with DCS, sensor monitoring
 - Post-layout simulations performed for different components, pending validation
- **TDAQi:** transmits trigger objects (tower or groups of cells) to the ATLAS trigger system
 - Building and synchronous transmission of trigger objects to the different trigger sub-stems
 - Sends monitoring data to FELIX
 - Final design ready and production-readiness planned next year
- Front End Link eXchange (FELIX) used for all ATLAS subdetectors as primary interface between FE and DAQ.





Calibration system and Qualification

- New DAQ and control electronics are needed for the laser calibration system
 - A continuous light source to simulate pile up will be used in addition to the pulsed laser source
- ILANA (Interface for the LAser system to the New Acquisition infrastructure) New DAQ and control electronics
 - First tests of prototype with LASER system replica performed
- Cesium system: redesign using EMCI/EMP*
 - Prototypes designs of new EMCI splitter boards and Cs-boards are ready, some prototypes are under-production

- PROMETEO (Portable Read Out ModulE for Tilecal ElectrOnics):
 - Prototype ready and functional







Tile Demonstrator

• A demonstrator system of the TileCal upgrades was implemented

- A TileCal module (LBA14) equipped with prototype mechanics and upgrade electronics
- It is backwards compatible with current and Phase-II readout systems
- It was inserted in ATLAS in July 2019 and is/will be kept in ATLAS for Run-3
- Has proven to be very useful to test the electronics and identify problems early on
 - Demonstrator gives stable performance, low noise and good CIS and laser signal
- Was used to record ATLAS data during 2022 run, in addition to cosmic data and beam splash events



Test beam

- 8 Test beam campaigns were performed using the CERN SPS beam line from 2015-2022
 - Performing hardware tests and validation, and performing physics studies
- 3 modules from the calorimeter (two Long-Barrel and one Extended-Barrel) are used in the setup
 - A half of LB module equipped with a prototype of the new Phase-II upgrade electronics.
- TileCal setup in SPS beam line includes both old and current electronics
 - EBC module is equipped with an EB SD with including phase-II electronics (since June 2022)
- Different particle species were used in the tests: electrons, muons and different hadronic beams at different energies



TileCal setup in CERN SPS beam line



Test beam results

• Muons (160 GeV) traverse the TileCal modules at 90° angle to test equalisation of the cell response

17

- Excellent agreement between data and simulation for layer uniformity (within 1%)
- Electrons at different energies to determine calorimeter response in pC/GeV
 - Used to determine linearity of response with energy and test uniformity and energy resolution



- Hadron beams are used to validate and improve the modelling for jet and tau measurements
 - Challenging to identify with high precision beam contents
 - Energy response determined as function of beam energy
 - Data MC variation are within 1-2% for the different particle types
 - Results published in EPJC 81 (2021) 549



Summary

- The HL-LHC will bring a lot of challenges to the ATLAS TileCal detector
 - Radiation damage
 - Higher pileup conditions
 - Higher luminosity and readout rates
- A comprehensive plan for TileCal Phase-II upgrades is progressing very well and on-time to accommodate HL-LHC conditions
 - Upgrades include full replacement and redesign of on- and off-detector readout electronics and replacement of 10% of the PMTs
 - New modular mechanical design for better accessibility and maintenance
- Many parts of the project already in production (passing all design and validation tests)
- A test-beam campaign has helped to test validation of Phase-II electronics using latest prototypes/preproduction and full system integration
- A working demonstrator with phase-II electronics is in place in the ATLAS detector for continuous testing and validation using Run-3 data

Thank you for your attention!