

Hardware/Software Co-Design with Gitlab CI

CROME: CERN RadiatiOn Monitoring Electronics


Amitabh Yadav, Hamza Boukabache, CROME Team amitabh.yadav@cern.ch


SoC Interest Group Meeting

23/11/2022

Reference: https://codimd.web.cern.ch/s/7VHssRXbY#









Agenda

- Gitlab CI what and why?
- CI and Docker Overview
- CROME CI Pipeline
- Key Features Dependencies and CI Special Variables
- Building Xilinx Petalinux Image through CI
- Future Steps Verification and Continuous Deployment.





Continuous Integration (CI)




23/11/2022



Gitlab CI - what and why?



Continuous Integration (CI) is the practice of continuously integrating and verifying the code changes automatically through CI pipelines.



Gitlab CI - what and why?




Continuous Integration (CI) is the practice of continuously integrating and verifying the code changes automatically through CI pipelines.

Advantages:

23/11/2022

- Ensures successful HW and SW build/compilation.
- Automatic code quality and performance testing.
- Early detection of errors, bug tracking, reduced integration problems, and faster deployment.
- Reproducible builds using Docker containers [1]
- Code packaging and deployment.



[1] SY-EPC-CCE Gitlab container-registry: https://gitlab.cern.ch/cce/docker_build/container_registry





CI Pipeline

• CI Pipeline:

- A pipeline is a sequence of scripted steps that will be executed on the code in repository.
- The steps are defined in the file .gitlab-ci.yml and is placed in the root of the project repository.
- Gitlab detects the YAML file and initiates the GitlabCI script.
- No modifications to the project repository.
- At the end, any new files/outputs created during the process of execution of a CI script are called **artifacts**.




Image source: docs.gitlab.com



CI Pipeline - continued

• CI pipeline components - Jobs and Stages:

- A pipeline is composed of independent **jobs** that execute scripts.
- Jobs are grouped into stages.
- Stages run in sequential order, but jobs within stages run in parallel.

• Artifacts:

- Archive of generated output files and directories.
- Accessible through GitLab UI or the API.




Image source: docs.gitlab.com



Gitlab CI Workflow




Image source: docs.gitlab.com






Gitlab CI Backend

• Gitlab Runner:

- Runners are computers/virtualmachines where we Gitlab CI scripts get executed.
- For specialized/large software that require configurations of our own, we make use of CERN OpenStack virtual machine.
- For this we need to install a runner on the system and register it as a gitlab-runner for our repository.



https://docs.gitlab.com/runner/install/ https://docs.gitlab.com/runner/register/




23/11/2022




















List of stages for jobs, and their order of execution stages: - build - test build-software: # This job runs in the build stage, which runs first. stage: build before script: - yum -y install doxygen script: - gcc --version - cd CMPU/zyng/sw/ROMULUSlib/ - make RUN_ON_PC=1 - echo "Building ROMULUSlib for x86 architecture." - export LD_LIBRARY_PATH="CMPU/zynq/sw/ROMULUSlib/" - cd ../embedded_linux_userspace_app - make RUN ON PC=1 - echo "Embedded_Application and ROMULUSlib Compiled Successfully" artifacts: paths: - CMPU/zynq/sw/ROMULUSlib/ - CMPU/zynq/sw/embedded_linux_userspace_app/ expire_in: 7d










stages: # List of stages for jobs, and their order of execution - build - test build-software: # This job runs in the build stage, which runs first. stage: build before script: - yum -y install doxygen script: - gcc --version - cd CMPU/zynq/sw/ROMULUSlib/ - make RUN_ON_PC=1 - echo "Building ROMULUSlib for x86 architecture." - export LD_LIBRARY_PATH="CMPU/zynq/sw/ROMULUSlib/" - cd ../embedded_linux_userspace_app - make RUN ON PC=1 - echo "Embedded_Application and ROMULUSlib Compiled Successfully" artifacts: paths: - CMPU/zynq/sw/ROMULUSlib/ - CMPU/zynq/sw/embedded_linux_userspace_app/ expire_in: 7d







```
# List of stages for jobs, and their order of execution
stages:
  - build
  - test
build-software:
                       # This job runs in the build stage, which runs first.
  stage: build
  before script:
    - yum -y install doxygen
  script:
    - gcc --version
    - cd CMPU/zyng/sw/ROMULUSlib/
    - make RUN ON PC=1
    - echo "Building ROMULUSlib for x86 architecture."
    - export LD_LIBRARY_PATH="CMPU/zynq/sw/ROMULUSlib/"
    - cd ../embedded_linux_userspace_app
    - make RUN ON PC=1
    - echo "Embedded_Application and ROMULUSlib Compiled Successfully"
  artifacts:
    paths:
      - CMPU/zynq/sw/ROMULUSlib/
      - CMPU/zynq/sw/embedded_linux_userspace_app/
    expire_in: 7d
# Build Hardware job defined to run in Docker container based on Vivado 2021.2 image.
   image: gitlab-registry.cern.ch/cce/docker_build/vivado:2021.2
       - echo "Creating Project"
       - cd CMPU/zynq/hw/
       - make create_project
       - echo "Vivado 2021.2 project created successfully."
       - make synthesis
       - echo "Vivado 2021.2 Project SYNTHESIS completed successfully."
       - make implementation
       - echo "Vivado 2021.2 Project IMPLEMENTATION completed successfully."
       - echo "Bitstream generated successfully."
   artifacts:
       - CMPU/zynq/hw/outputfiles
```





In a simple .gitlab-ci.yml file, we define:

- The commands need to run in sequence (Stages) and those that need to run in parallel (Jobs).
- The scripts that need to be run.
- before_script, after_script and variables.
- Artifacts: the built files that needs to be saved.
- Specification of whether to run the scripts automatically or trigger manually.
- Specification on which specific branch the pipeline should be executed automatically.

```
# List of stages for jobs, and their order of execution
stages:
 - build
 - test
build-software:
                      # This job runs in the build stage, which runs first.
 stage: build
 before script:
   - yum -y install doxygen
 script:
   - gcc --version
   - cd CMPU/zynq/sw/ROMULUSlib/
   - make RUN ON PC=1
   - echo "Building ROMULUSlib for x86 architecture."
   - export LD_LIBRARY_PATH="CMPU/zynq/sw/ROMULUSlib/"
   - cd ../embedded_linux_userspace_app
   - make RUN ON PC=1
   - echo "Embedded_Application and ROMULUSlib Compiled Successfully"
 artifacts:
   paths:
      - CMPU/zynq/sw/ROMULUSlib/
      - CMPU/zynq/sw/embedded_linux_userspace_app/
   expire_in: 7d
```

```
# Build Hardware job defined to run in Docker container based on Vivado 2021.2 image.
build_hw:
    stage: build
    image: gitlab-registry.cern.ch/cce/docker_build/vivado:2021.2
    script:
        - echo "Creating Project"
        - cd CMPU/zynq/hw/
        - make create_project
        - echo "Vivado 2021.2 project created successfully."
        - make synthesis
        - echo "Vivado 2021.2 Project SYNTHESIS completed successfully."
        - make implementation
        - echo "Vivado 2021.2 Project IMPLEMENTATION completed successfully."
        - echo "Bitstream generated successfully."
        artifacts:
        paths:
        - CMPU/zynq/hw/outputfiles
```





Docker Executor

Using image keyword executes the CI jobs in Docker containers.

```
build sw:
  stage: build
  image: gitlab-registry.cern.ch/cce/docker build/petalinux:2018.1
```

The Docker executor divides the job into multiple steps:

- Prepare: Create and start the services.
- Pre-job*: Clone, restore cache and download artifacts from previous stages.
- Job: User build. This is run on the user-provided Docker image.
- Post-job*: Create cache, upload artifacts to GitLab.

*pre-job and post-job are run on a special docker container based on Alpine Linux.

Prebuilt docker images for Vivado, Petalinux, QuestaSim, ModelSim, Doxygen etc. are available through Gitlab Container Registry at SY-EPC-CCE's repository^[1]



Using Docker executor with image gitlab-registry.cern.ch/cce/docker_build/petalinux:2018.1 ...

Using locally found image version due to "if-not-present" pull policy

Reinitialized existing Git repository in /builds/CROME/CROME/.git/

Running on runner-mlqhtxyw-project-27912-concurrent-1 via (rn.ch...

unning with gitlab-runner 15.5.1 (7178588d)

Using docker image sha256:b0bfa0820c48e652f034f4c85ac0

t gitlab-registry.cern.ch/cce/docker_build/petalinux@sh

Checking out ab38b2ef as refs/merge-requests/41/head...

Downloading artifacts for check linting (25921706)... Downloading artifacts from coordinator... ok

on cs8crome1;ansible-started M1qHTXyW

Preparing the "docker" executor

Getting source from Git repository

Removing CMPU/zynq/hw/aclocal.m4 Removing CMPU/zynq/hw/autom4te.cache/ Removing CMPU/zyng/hw/build/ Removing CMPU/zynq/hw/configure Skipping Git submodules setup Downloading artifacts

Resolving secrets

f for gitlab

de59901d9dd6

id=25921706 responseStatus=200 OK token=ocLhtsa8


CROME CI Pipeline



23/11/2022



CROME CI Pipeline






merge request pipelines runs when a merge request is open for the branch.





CROME CI Pipeline: Syntax Check and Linting




```
check_vhdl_syntax:
    stage: pre-checks
    image: gitlab-registry.cern.ch/cce/docker_build/vivado:2018.1
    allow_failure: false
    before_script:
        - sudo yum 'y install autoconf automake
    script:
        - cd CMPU/zynq/hw/
        - autoreconf -i
        - mkdir -p build
        - cd build
        - ../configure --enable-triplication --enable-frontend=ion --enable-sem=repair
        - make check_syntax
```

before_script: use for initial setup of docker container and resolve missing dependencies. Upon final testing this can be packaged in the original docker image.





CROME CI Pipeline: Syntax Check and Linting





```
check_vhdl_syntax:
    stage: pre-checks
    image: gitlab-registry.cern.ch/cce/docker_build/vivado:2018.1
    allow_failure: false
    before_script:
        - sudo yum -y install autoconf automake
    script:
        - cd CMPU/zynq/hw/
        - autoreconf -i
        - mkdir -p build
        - cd build
        - ../configure --enable-triplication --enable-frontend=ion --enable-sem=repair
        - make check_syntax
```

```
check_linting:
    stage: pre-checks
    image: vsg:latest
    allow_failure: false
    script:
        - cd CMPU/zynq/hw/
        - autoreconf -i
        - mkdir -p build
        - cd build
        - ../configure --enable-triplication --enable-frontend=ion --enable-sem=repair
        - make lint
        artifacts:
        when: always
        paths:
        - CMPU/zynq/hw/build/linting/lint_junit.xml
        reports:
        junit: CMPU/zynq/hw/build/linting/lint_junit.xml
        codequality: CMPU/zynq/hw/build/linting/lint_quality_report.xml
```


allow_failure: allows for a CI job to fail and continue executing the pipeline.

artifacts: built files and executables that are passed on to the next job.






CROME CI Pipeline: Build Stage







CROME CI Pipeline: Build Stage



```
build hw:
 stage: build
 image: gitlab-registry.cern.ch/cce/docker build/vivado:2018.1
 allow failure: false
 before script:
   - sudo yum -y install autoconf automake
 script:
   cd CMPU/zynq/hw/
   - autoreconf -i
   - mkdir -p build
   - cd build
   - ../configure --enable-triplication --enable-frontend=ion --enable-sem=repair

    make implementation


   - echo "Vivado 2018.1 Project IMPLEMENTATION completed successfully."
 artifacts:
    - CMPU/zynq/hw/build/CMPU.hdf
```





Key Features

needs is used needs to execute jobs out-of-order.





23/11/2022



Key Features

needs is used needs to execute jobs out-of-order.

variables can be defined in .gitlab-ci.yml or in the project settings. They can be made global or local to a job and are used in similar way as shell variables.

```
build_sw: # This job runs in the build stage, which runs first
  stage: build
  needs: [sw_linting]
  image: gitlab-registry.cern.ch/cce/docker_build/vivado:2021.2
  allow_failure: false
  variables:
    XILINX_PATH: /opt/Xilinx/
    XILINX_VERSION: "2021.2"
    ROMULUSLIB_MAJOR_VERSION: "7"
    ROMULUSLIB_MINOR_VERSION: "2"
  before_script:
    #- yum -y update
    - yum -y install doxygen
    script:
    - source $XILINX_PATH/Vitis/$XILINX_VERSION/settings64.sh
```





Key Features

needs is used needs to execute jobs out-of-order.

variables can be defined in .gitlab-ci.yml or in the project settings. They can be made global or local to a job and are used in similar way as shell variables.

when is used within a job to specify if the job needs manual intervention to start.

- Stages such as formal_verification for license availability reasons.
- Linux image build.

```
build_sw: # This job runs in the build stage, which runs first.
   stage: build
   needs: [sw_linting]
   image: gitlab-registry.cern.ch/cce/docker_build/vivado:2021.2
   allow_failure: false
   variables:
        XILINX_PATH: /opt/Xilinx/
        XILINX_VERSION: "2021.2"
        ROMULUSLIB_MAJOR_VERSION: "7"
        ROMULUSLIB_MINOR_VERSION: "2"
   before_script:
        #- yum -y update
        - yum -y install doxygen
   script:
        - source $XILINX_PATH/Vitis/$XILINX_VERSION/settings64.sh
```

```
when: manual
allow_failure: true
rules:
   - if: '$CI_COMMIT_BRANCH == "gitlabci2021.2"'
artifacts:
   when: on_success
   paths:
    - images/linux/
```

```
$° gitlabci2021.2 → 131f57b7 

i stage dependencies

§° gitlabci2021.2 → 60d07d5b 

i stage dependencies
```





CROME CI Pipeline: Artifacts

Status	Pipeline	Triggerer	Stages	
 passed 00:32:33 3 days ago	Dummy commit #4780028 \$\$ 41 •• ab38b2ef latest merge request	2 3	\odot	□
 passed 00:32:58 4 days ago	Dummy commit #4778234 \$\$ 41 •• 4a121f43 \$# merge request	2	\odot	Q Search build_hw:archive build_sw:archive check_linting:archive check_linting:junit
 passed 00:32:45 6 days ago	cosim/README.md: updated prepare_sdcard, minor impr #4768540	2	\odot	
★ failed ★ 00:33:31 ★ 6 days ago	sw: WIP change of file structure #4764416 % allModifClyde → 898e3ce4 &	23	▼	check_linting:codequality





Building Linux Images through Gitlab CI

• Currently testing: Building of Embedded Linux Image alongwith bit bake bootscript applications.

```
C FILES CHKSUM = "file://${COMMON LICENSE DIR}/MIT;md5=0835ade698e0bcf8506ecda2f
                               herit update-rc.d
                              NITSCRIPT NAME = "bootscript"
ite=${colors[White]}
```





Building Linux Images through Gitlab CI

- Currently testing: Building of Embedded Linux Image alongwith bit bake bootscript applications.
- kernel and hw configuration through
 --silentconfig option on Xilinx/Petalinux
 2021.2

```
uild linux:
  stage: build cromix
  needs: []
  image: gitlab-registry.cern.ch/cce/docker_build/petalinux:2021.2
    - echo "Run cromix21 Build Petalinux Image"

    cd CMPU/zynq/hw

    petalinux-create --type project --template zynq --name cromix21

    - petalinux-config --get-hw-description ../hdf/ --silentconfig
    - petalinux-config -c kernel --silentconfig

    petalinux-build

  when: manual
    - if: '$CI COMMIT BRANCH == "gitlabci2021.2"'
  artifacts:
    when: on success
      images/linux/
                                                 *in development
    expire in: 7d
```





Conclusion

- CI can be efficiently adopted for heterogeneous development for SoCs.
- We have currently deployed Gitlab CI in development branch is currently used for HDL linting using vsg docker image.
- Gitlab CI is proving elemental during migration of our Xilinx HDL codebase + IPs from version 2018.1 to 2021.2
- Has helped in resolving dependency issues through GNU Autotools and Docker containers to execute CI jobs.

In the works is Gitlab CI for:

- Formal Verification scripts to be added to the CI pipelines to be executed automatically.
- Continuous Deployment through gitlab-runner through ssh into devices.

