

MAGIS-100 Overview

VLB Atom Interferometry Workshop

Robert Plunkett, Fermilab

13 March, 2023



MAGIS-100 Collaboration

- US/UK International Collaboration to bring LB Atom Inteferometry to Fermilab.
- Collaboration initiated 2017.
- Funding Sources: Gordon and Betty Moore Foundation, US DOE, STFC/AION, Kavli Foundation. Our thanks!
































MAGIS-100 experiment design overview

Matter wave Atomic Gradiometer Interferometric Sensor



- 100-meter baseline atom interferometry in existing shaft at Fermilab
- Major sub-systems:
 - Clock atom sources (Strontium) at three positions
 - Interferometry laser system
 - 100-meter vacuum system and infrastructure



























MAGIS-100 Scientific Objectives

- Quantum Science: Demonstrate/test quantum superposition over distances of several meters and times of several seconds.
- <u>Dark Matter</u>: Search for DM in the mass range 10^{-15} eV 10^{-14} eV, based on DM effects that result in time dependent changes to the atomic energy levels. Demonstrate/establish the sensitivity of this method.
- <u>Dark Matter</u>: Search for DM in the mass range 10^{-17} eV 10^{-15} eV, for DM that causes time dependent accelerations, based on a dual Sr isotope interferometer with maximal launch height.
- <u>Gravitational Waves</u>: Within the frequency range 0.3 Hz 3 Hz, establish a record sensitivity to gravitational waves, corresponding to a strain sensitivity of $\leq 10^{-14} / \sqrt{\text{Hz}}$.



March 13, 2023


Strontium Clock Transition



Metastable, nearly forbidden, long-lived transition



MAGIS-100 operating modes



Mode A: Maximum gradiometer drop time.

Mode B: Maximum gradiometer baseline.


Mode C: Gravity gradient noise (GGN) characterization.

Mode D: Dual-isotope launch for alternative dark matter searches.

For additional information, see 2021 publication linked at magis.fnal.gov.



Systems overview






March 13,

Location – MINOS building






Laser lab to be built behind this wall.

Ground level of MINOS building.





Location – shaft in MINOS building





Top and bottom of ~100m shaft. Proposed experiment location follows orange line.




Modular sections

- Modular assembly concept uses 17 sections, each ~5.2m (17') long and ~2,000 lb. weight.
- Eight sections between each atom source and one section above the top atom source.
- Each section has a support frame containing a 6" diameter vacuum tube, heating/insulation system with controls and temperature sensors, bias field coils, octagonal mu metal shield with support frame, and magnetometer.

Vacuum pumps and viewports with cameras will be placed between

tube sections.




Single module with adjustable supports.


lau

华Fermilab


Modular connection nodes



Cameras mount inside re-entrant viewports with light tight covers.



Detail of modular connection node.




Two modules connected.




Stanford 10-meter Sr prototype

Two assembled Sr atom sources









Prototype tower section assembly



Vacuum tube




Insulation



Magnetic field


- Magnetic field is controlled with mu metal shielding and optimally placed magnet coils.
- Mu metal cannot have mechanical stresses creates magnetic "holes" in shield.
- Sections are longer than typical mu metal annealing furnaces.
- Adapted from an existing design, octagonal shield chosen with four layers of staggered seams using flat and angled pieces.
- Fixtures required for successful tight-fitting assembly.





Above right: Magnetic coupler and additional coils will be

placed around modular connection nodes.

Atom source details









Atom sources

Top, middle, and bottom of shaft

Last components installed.

Designed and built at Stanford








Connection node – Stanford


Three special "connection nodes" are at the interface between each atom source and the 100 meter interferometer region.


Functions:

- Horizontal atom shuttle
- Optical lattice atom launch
- State prep
- Atom detection and imaging
- Vacuum pumping
- 100m module connection
- Thermal expansion joint (bellows)














Laser System



- 22 lasers


8 wavelengths

 On surface and in shaft

 Integrated via optical comb



March 13.






Laser Laboratory

 Holds Interferometry Lasers, many others.


- Houses Optical Comb
- Support system for transport system.
- Safety Interlocks.
- Utilities on second level
- Finalizing contract. Expect construction in summer.





March 13,


Laser transport system layout





March 13,

Laser Transport Details - Top




Retro-reflection Phase-shear Platform

- UHV chamber housing retro-reflection mirror
- Mirror needs precise control for

 Interferometry beam monitoring and alignment

- Coriolis corrections
- Phase-shear imaging
- Designed together with Stanford














Strongbacks and Support Hardware

















Top View of Shaft, Showing Installation Concepts




L. Valerio, Fermilab





Modular section assembly


- Assembly will be done at Fermilab.
- Rotisserie fixture and magnetometer shuttle already tested at Stanford.



Above: Schematic of assembly on rotisserie fixture. Right: Prototype assembly at Stanford University.

Below: Schematic of complete assembly.









Component installation plan

- Wall supports will be installed through a civil construction contract.
- Plan to land components on wall supports with dagger system.
- Use cameras (with lights) for crane operator feedback instead of people in basket above load.
- Then people descend in basket to firmly connect components to supports and disconnect auxiliary crane hook and cameras.
- Concern about two cranes entangling is minimized with this approach.
- Work ongoing to stabilize crane loads.
- Mock-up will be tested.









Modular section adjustable wall support.











Status and Conclusions

- Many components are in hand, others are in either advanced design or prototyping state.
- Collaboration close-knit and participation outstanding.
- Laser lab construction will occur soon.
- Installation remains challenging but progress is occurring.
- The future of MAGIS-100 is bright!

Backing

Alignment conceptual plan

Optical plummets will be mounted at the bottom of the shaft to achieve required alignment.

Mounting base must be sturdy.


 Bottom of shaft has metal plates which will flex and is also a "stay clear" zone. Original plan was to use concrete block.


Consider if mounting base to elevator wall would


work better.

Details still developing.













Bake out controls system




Bake controls system uses Raspberry Pis and thermocouples with a temperature module box on each section in the shaft and power control modules at the top of the shaft.

All images from Sergei Nagaitsev.



Top of shaft

In shaft



Controls network

Ethernet from 15 - 40 RPis measuring

16 temperatures each



16-channel SSR


Computing activities

- Move away from the crunchy hardware details to software and resources.
- Participation and organization of software workshop.
- Simulation activities
- Organizational
 - Biweekly meeting forum (Geer).
 - Proposal for collaboration software organization.
- Much of this familiar to many here, who are very active.



Production Simulations and Analysis

Production simulation: pick some set of signals with chosen parameters, simulate the phase shift, detector effects, up to creating images (in same format as real



Production analysis: starting from the images, fit the patterns and extract a phase shift. Should be able to run on both simulation and real data with minor user input. These algorithms used in both Online and Offline processing

8/3/22 D. Temples | MAGIS-100 Science & Simulation | Production Simulations & Analysis Update



☆ Fermilab

Dark Matter Simulation Results – Docdb 1290




Figure 3: First cycle of a simulated DM background wave produced from an incoherent sum over 1000 indiv sinusoidal waves with the frequency distribution shown in Fig. 2. The individual points are spaced with the anticipated cadence of the MAGIS-100 interferometer measurements. The curve shows the expected sinusoida variation.





Figure 4: Comparison of two cycles of a simulated DM background wave for a DM particle with $m_0 = 10^{-15}$ eV. The cycles are separated by a time interval of 10^7 sees which $\approx \tau_{coh}$. The red points are the late cycle, and the blue curve shows a fit to the early cycle (shown in Fig. 3) projected forward in time. The green curves indicate the uncertainty on the projection. Note that both the amplitude and phase of the wave howe evolved.




Horizontal shuttle optical lattice - Stanford

- Long shuttle distance (0.6m)
- Use two tilted lattices to null vertical acceleration



Prototype delivery optics




- Overlapping paths maximizes acceleration distance
- Nearly independent control over lattice angle/position
- Delivery optics on custom stainless steel breadboard
- Picomotors for remote control of all required DC MAGIS-100
- Next step: demonstration with atoms

Ultra high vacuum (UHV)

- Required pressure e-11 Torr or better for interferometry region.
- Dual pumps (ion pump + titanium sublimation pump OR non-evaporable getter pump + small ion pump) will be on each modular section.
- Vacuum bake required to reach this pressure.
- Minimally magnetic 316L stainless steel tubes and non-magnetic heaters required.
- Tubes have been electropolished and will be hydrogen degassed.





Excerpt from bake test e-log.



6" OD vacuum tubes.





Fermilab

16-channel bake test setup.

Progress on bakeout system (Fermilab, Chicago)

Setting up for test at CMTF facility.







17 boxes needed. Big job!



Large amount of vacuum testing.


Example: Control Box and Optics Mounts





Achieved required pressure with optics coatings after some work.

Prototype atom source at Stanford University



One billion strontium (Sr) atoms are captured in the blue dot in the magneto-optical trap (MOT).



Optics in the top layer of the atom source.