




VeLo Commissioning Status and Plan

Victor Coco (CERN) for the Velo group

Velo project institutes:



What is still needed to close the VELO?



- **Check temperature and vacuum behaviour during closing**
 - checking SMOG / RFFoil temperatures and vacuum evolution
 - time spent in closed position to see temperature evolution
⇒ **Intensity ramp-up**
- **Cross-checked of detector alignment and metrology with particles**
 - The RFFoil is closest element to the beam
 - Metrology performed on-site to be confirmed by tomography from reconstructed hadronic interaction with the material
⇒ **Partial closure at 2mm before going to full closure**

Partial Closure

- **Sept 30th, rehearsal behind closed position @1200b**
 - moved between 29.7mm and 25mm
- **Tuesday Oct 4th:**
 - power cut in data center at FLAT TOP
 - could not get back 40% of the VELO \Rightarrow asked to postpone
- **Thursday Oct 6th:**
 - Fill 8232, 12b
 - Fill 8233, 300b \Rightarrow 218b (injector issue)
- **Used the final closing manage (with manual handshake)**
 - check DAQ states, HV current, vertex reconstruction, compatibility with BPM, ...
 - check in parallel the monitoring (position of vertices, currents) to verify validity of inputs
- **No Y movement:**
 - Offset in vertex reconstruction understood from metrology but preferred to check with data at various x to validate.

System: VELO_Position, State: CLOSING, Thu 22-Sep-2022 10:09:28

VELO Closing Manager

Motion: ALLOWED, PARTIALLY IN/OUT

Beam Position: X: 0.00 mm, Y: 0.05 mm

Motion System Position: XA: 10.00 mm, Y: 0.05 mm, XC: -10.00 mm

Status: ELOG

Do you want to move the VELO to:
XA = 5.000mm, XC = -5.000mm and Y = 0.050mm ?

Buttons: ReCheck, Ok, Cancel

Reference Values

BPM: last update on 23-Jul-2022 at 14:44:52
BPV: waiting for Velo fully closed...

#	Quantity	ActualValue	Criterion	Status
1	BCM: S0_RS02	0.010 %	< 5.000 %	OK
2	BCM: S0_RS32	0.004 %	< 5.000 %	OK
3	BCM: S1_RS02	0.038 %	< 5.000 %	OK
4	BCM: S1_RS32	0.014 %	< 5.000 %	OK
5	BPM: D(B1L8H)	0.013 mm	< 0.200 mm	OK
6	BPM: D(B1L8V)	0.039 mm	< 0.200 mm	OK
7	BPM: D(B2L8H)	0.011 mm	< 0.200 mm	OK
8	BPM: D(B2L8V)	0.026 mm	< 0.200 mm	OK
9	BPM: D(B1R8H)	0.063 mm	< 0.200 mm	OK
10	BPM: D(B1R8V)	0.107 mm	< 0.200 mm	OK
11	BPM: D(B2R8H)	0.006 mm	< 0.200 mm	OK
12	BPM: D(B2R8V)	0.035 mm	< 0.200 mm	OK
13	BPM: [B1_Xav]	0.386 mm	< 4.000 mm	OK
14	BPM: [B1_Yav]	0.328 mm	< 4.000 mm	OK
15	BPM: [B2_Xav]	0.370 mm	< 4.000 mm	OK
16	BPM: [B2_Yav]	0.275 mm	< 4.000 mm	OK
17	BPM: [B1_Xdr]	0.000 mm/s	< 0.100 mm/s	OK
18	BPM: [B1_Ydr]	0.000 mm/s	< 0.100 mm/s	OK
19	BPM: [B2_Xdr]	0.000 mm/s	< 0.100 mm/s	OK
20	BPM: [B2_Ydr]	0.000 mm/s	< 0.100 mm/s	OK
21	VTX: [XVA + XVC]	1.583 mm	< 10.000 mm	OK
22	VTX: [XVA+XVA-XC-XVC] - 310um	0.001 mm	< 0.300 mm	OK
23	VTX: SXVA	0.046 mm	< 0.600 mm	OK
24	VTX: SYVA	0.046 mm	< 0.600 mm	OK
25	VTX: SXVC	0.042 mm	< 0.600 mm	OK
26	VTX: SYVC	0.046 mm	< 0.600 mm	OK
27	VTX: DXVA	973.792 mm	< 9999.000 mm	OK
28	VTX: DYVA	1000.116 mm	< 9999.000 mm	OK
29	VTX: DXVC	1027.791 mm	< 9999.000 mm	OK
30	VTX: DYVC	1000.088 mm	< 9999.000 mm	OK
31	HV: bias current (A-side)	7411.712 uA	< 15000.000 uA	OK
32	HV: bias current (C-side)	9398.467 uA	< 15000.000 uA	OK

Plots and Trends: SELECTION

BCM (%)

S0_RS2	S0_RS32	S1_RS2	S1_RS32
0.010	0.004	0.038	0.014

BPM (mm)

B1L8(hor)	B1L8(ver)	B2L8(hor)	B2L8(ver)
3.820	0.462	-4.436	0.732
B1R8(hor)	B1R8(ver)	B2R8(hor)	B2R8(ver)
-4.593	0.194	3.696	-0.183
B1_Xav	B1_Yav	B2_Xav	B2_Yav
-0.386	0.328	-0.370	0.275
B1_Xdr	B1_Ydr	B2_Xdr	B2_Ydr
0.000	0.000	0.000	0.000

VELO Resolvers (mm)

XA	XC	YAC
27.090	-27.000	-0.001

VELO Halves distance (mm)

Δ X	Δ Y
53.998	0.028

Beam Position A-side (mm)

XVA	YVA	ZVA	time elapsed
-26.200	0.116	-5.316	1
SXA	SYA	SZA	
0.046	0.046	50.003	

Beam Position C-side (mm)


XVC	YVC	ZVC
27.791	0.088	5.891
SXC	SYC	SZC
0.042	0.046	50.008

Close


Partial Closure

- **Several steps**

- 27mm jaw position \Rightarrow 25mm centered on beam (check mechanism works)
- \Rightarrow 20mm \Rightarrow 15mm \Rightarrow 10mm \Rightarrow 8mm \Rightarrow 6mm \Rightarrow 5mm [only @218b] \Rightarrow 4mm [stayed ~15min] \Rightarrow 3mm \Rightarrow 2mm [stay 1h] \Rightarrow 4mm [only @ 12b] \Rightarrow 27mm




Temperature and vacuum evolution



- **Temperature increase @4mm**
 - ~0.3K
 - Fast then slower and quickly less when moving to 3mm
- **Small vacuum increase at some point during closure**
 - ~1e-10 mbar

RFfoil temperature decrease by

Temperature and vacuum evolution



- **Temperature increase still @4mm**
 - ~1K, not scaling with intensity
- **Vacuum increase when moving**
 - 3e-9 to 6e-9 mbar
 - scaling with intensity?
 - Probing some temperature increase elsewhere?
 - Decrease when movement is idle (linked to movement itself?)
 - Sharp decrease when moving out.


Foil (and SMOG) opening



- **Foil temperature drops while closing**
 - cooling of the foil by the foil




Hadronic interaction

- **Using interaction with material to check the position of the foil**
 - reconstruct tracks
 - reconstruct vertex from the tracks
⇒ pp interaction and interaction with material
- **Analysis on going**
 - interplay with alignment (rotation/translation of modules wrt. foil can be seen as rotation/translation of the foil wrt. the global frame)
 - local (from halves) vs. global (wrt. beam position) studies
 - A-side foil seen from C-side modules and opposite give as little bias information as possible



Hadronic interaction

- **Bulging compatible with metrology results**
- **Should still understand the positioning of the halves**
- **Effective aperture radius may be reduced by $\sim 0.5-0.7\text{mm}$ (really still preliminary, to be confirmed)**



Conclusion


What are the next steps?






The LHCb Vertex Locator (VeLo)

- **LHCb and the VELO were upgraded during LS2**
 - Instantaneous luminosity $4 \cdot 10^{32} \rightarrow 2 \cdot 10^{33} \text{ s}^{-1} \text{ cm}^{-2}$
 - Increase in luminosity needed 40MHz readout with full software trigger
- ⇒ Full upgrade of the DAQ and readout electronics as well as of the tracking detectors and RICH



- The VELO allows LHCb to **reconstruct with high precision the trajectory** of charged particles and their **origin vertices**
- ⇒ key instrument for **B,D hadron reconstruction**

With respect to Run 1&2 LHCb: **to be upgrade/ to be kept**



VeLo commissioning

Towards automatic closure

- Repeat the sequence with automatic closure procedure but manual handshake between steps for a few times
- Need for the detector to be in global mode... probably not routinely before TS1
- Move from online monitoring to dedicated task out of Hlt1 selected events.
- Software side of the procedure tested with MC injection
 - communication computing farm → winCC → motion system

Reference Values

BPM: last update on 23-Jul-2022 at 14:44:52
 BPV: waiting for Velo fully closed...

Plots and Trends

SELECTION ▾

#	Quantity	ActualValue	Criterion	Status
1	BCM: S0.R502	0.010 %	< 5.000 %	OK
2	BCM: S0.R532	0.004 %	< 5.000 %	OK
3	BCM: S1.R502	0.038 %	< 5.000 %	OK
4	BCM: S1.R532	0.014 %	< 5.000 %	OK
5	BPM: D(B1L8H)	0.013 mm	< 0.200 mm	OK
6	BPM: D(B1L8V)	0.039 mm	< 0.200 mm	OK
7	BPM: D(B2L8H)	0.011 mm	< 0.200 mm	OK
8	BPM: D(B2L8V)	0.026 mm	< 0.200 mm	OK
9	BPM: D(B1R8H)	0.063 mm	< 0.200 mm	OK
10	BPM: D(B1R8V)	0.107 mm	< 0.200 mm	OK
11	BPM: D(B2R8H)	0.006 mm	< 0.200 mm	OK
12	BPM: D(B2R8V)	0.035 mm	< 0.200 mm	OK
13	BPM: B1 Xav	0.386 mm	< 4.000 mm	OK
14	BPM: B1 Yav	0.328 mm	< 4.000 mm	OK
15	BPM: B2 Xav	0.370 mm	< 4.000 mm	OK
16	BPM: B2 Yav	0.275 mm	< 4.000 mm	OK
17	BPM: B1 Xdr	0.000 mm/s	< 0.100 mm/s	OK
18	BPM: B1 Ydr	0.000 mm/s	< 0.100 mm/s	OK
19	BPM: B2 Xdr	0.000 mm/s	< 0.100 mm/s	OK
20	BPM: B2 Ydr	0.000 mm/s	< 0.100 mm/s	OK
21	VTX: XVA + XVC	1.583 mm	< 10.000 mm	OK
22	VTX: XA+XVA-XC-XVC - 310um	0.001 mm	< 0.300 mm	OK
23	VTX: SXVA	0.046 mm	< 0.600 mm	OK
24	VTX: SYVA	0.046 mm	< 0.600 mm	OK
25	VTX: SXVC	0.042 mm	< 0.600 mm	OK
26	VTX: SYVC	0.046 mm	< 0.600 mm	OK
27	VTX: D(XVA)	973.792 mm	< 9999.000 mm	OK
28	VTX: D(YVA)	1000.116 mm	< 9999.000 mm	OK
29	VTX: D(XVC)	1027.791 mm	< 9999.000 mm	OK
30	VTX: D(YVC)	1000.088 mm	< 9999.000 mm	OK
31	HV: bias current (A-side)	7411.712 uA	< 15000.000 uA	OK
32	HV: bias current (C-side)	9398.467 uA	< 15000.000 uA	OK

BCM (%)

S0.R52	S0.R532	S1.R52	S1.R532
0.010	0.004	0.038	0.014

BPM (mm)

B1L8(hor)	B1L8(ver)	B2L8(hor)	B2L8(ver)
3.820	0.462	-4.436	0.732
B1R8(hor)	B1R8(ver)	B2R8(hor)	B2R8(ver)
-4.593	0.194	3.695	-0.183
B1 Xav	B1 Yav	B2 Xav	B2 Yav
-0.386	0.328	-0.370	0.275
B1 Xdr	B1 Ydr	B2 Xdr	B2 Ydr
0.000	0.000	0.000	0.000

Velo Resolvers (mm)

XA	XC	YAC
27.000	-27.000	-0.001

VeloHalves distance (mm)

Δ X	Δ Y
53.998	0.028

ver. 4.1

Beam Position A-side (mm)

XVA	YVA	ZVA	time elapsed 1
-26.208	0.116	-5.316	
SXA	SYA	SZA	
0.046	0.046	50.003	

Beam Position C-side (mm)


XVC	YVC	ZVC
27.791	0.088	5.891
SXC	SYC	SZC
0.042	0.046	50.008

Close


VeLo commissioning

Readout and reconstruction


All vertices in run (X) - VELO A side




All vertices in run (Y) - VELO A side




All vertices in run (Z) - VELO A side




All vertices in run (X) - VELO C side




All vertices in run (Y) - VELO C side



All vertices in run (Z) - VELO C side





RF-foil



- **New foil shape wrt. Run1&2**
- **Same mechanical system for the motion (motors, position measurement, ...) but new control HW**

Motion system limits



 reference switch

A-side surface test



April 30th to May 9th

- **Mechanical preparation**

- installation of removable shims
- base plate removal
- test of balancing

- **Metrology**

- 3D laser scan in horizontal position
 - ⇒ absolute position at room temperature
- check for collision with RFFoil 3D laser scan
- with Liv. metrology data provides reference for alignment




A-side installation schedule

May 10th to 17th

ACCESS @ P8

- Team from Nikhef, Manchester, Santiago, Liverpool, Warwick, Oxford at CERN to help with installation
- Support from the pit infrastructure team
- Huge thanks to the LHC team to have organised a week of access to allow for installation!





Vacuum operations

May 10th to 12th and May 25th

- **Venting to allow for VELO insertion**
- **Pump down on Thursday morning, 2.3×10^{-8} mbar in primary and 6.5×10^{-5} mbar in sec. achieved after 24h**
- **Last week first part of SMOG injection commissioning**
 - test with **open VELO** no beam
 - useful to provide particles out of stable beam interaction
 - next test with open VELO and beam during a period of “quiet” beam
- **Many thanks to TE-VSC group for the support during installation and in getting SMOG system commissioned**


From Josef Sestak



A-side electrical connectivity

May 12-13th


- **Cabling following mechanical installation**
 - Installation of the optoelectronic boards
 - Routing of the LV and temperature sensor cables
 - Connection to the detector patch panel
- **Checked mapping of ~350 temperature measurements**
 - 4 not working \Rightarrow 3 fixed, one redundant sensor not recoverable
- **Validation of the safety system mapping**
 - full VSS system installed
 - As for C-side checked that each temperature sensor above limit trigger the proper LV/HV interlock \Rightarrow ready to put CO₂ and power-up
- **Gluing of C-side tertiary vacuum PT100**



A-side fiber connectivity

May 13th



- **Connection of the fibers to the patch panel done in April.**
- **A and C-side spares routed during installation**
- **676 LC connections on the A-side**
 - Two teams of 2 persons for 10h
 - Checked cleanness with microscope and connect
- **Optical link quality test**
 - run PRBS test to quantify the quality of the link and check presence of light
 - a few MPO swap to fix in the data center
 - a few swap of LC on the detector
 - a few LC needed to be recleaned
 - for several modules DCDC convertor replaced to higher values
 - not an optical link issue but some GBTx recieves too low voltage and link can't be tested



A-side cooling commissioning

May 12-16th

- **CO₂ connection to local box completed on Thursday**
- **Module under vacuum for 24h**
 - while finalising the safety system testing
- **Connection to the plant on Saturday**
 - boiling at warm setpoint
 - tested powering modules and quality of optical links
 - going cold prevented by dry-out in one module
- **Intervention to replace gasket of module 47**
 - Sunday vented tertiary vacuum and removed hood
 - replaced gasket
 - gasket itself obstructed by a flake (composition to be determined)
 - Cold on Monday
 - ***All module could be powered!***



Alignment from metrology preliminary

Black: Design
Yellow: Actual

