

*Mexico laboratory
Weizmann Institute*

Meir Shoa

Some History

OPAL DETECTOR

- OPAL (Omni-Purpose Apparatus at LEP) - one of four large detectors at the [Large Electron-Positron collider](#) (LEP)
 - Started operation with the collider in August 1989
 - Data taking ended - 2 November 2000
 - Detectors dismantled the following year to – make room for construction of the [Large Hadron Collider](#) (LHC).
- 1980-1990 - Lab activity - TGC for the Hadron calorimeter
 - R&D – TGC taken from prototype level to mass production
 - Production of 500 units
 - Installation

OPAL




Hadron Calorimeter



Presample chambers

Hadron calorimeter



1990-2000 Activities

- Maintenance of OPAL detectors
- R&D of special pre chambers and installation in OPAL
- Spaghetti project muon TGC chambers
 - Planned and constructed at Weizmann
- Start of R&D of TGC's units for Atlas
- End of decade – start production of TGC's for the Atlas big wheels


2000-2008 Activities

- Construction of about 2100 TGC's
- Transport to CERN
- Mounting of TGC's on separated sectors
- Assembling of 6 big wheels and 2 small wheels
- Placing the wheels on Atlas pit (include services)

Big wheels




Small wheel



2008- 2014 Activities

- Maintenance of TGC's (big wheels)
- R&D and full design for New Small Wheels small-strip TGC (sTGC)



2014-2021 Activities

- Production of 64 sTGC's quadruplets for the new small wheels
- Support involved sites for production
- Transport to CERN
- Testing detectors at CERN including Beam test and GIF
- Expert team for electronics and units assembly at CERN

New small wheels

2 NSW are operating underground in the ATLAS pit



Current activities

Mexico lab

- Maintenance for the big wheels in ATLAS
 - DCS, Spare production and replacement
- R&D projects
 - Muon spectrometer NA60+
 - EIL4 TGC - to replace on 2026
- Production of the new EIL4 will start soon
- Design and planning the new lab

Spare TGC's units

- 22-23 – 7 units will be replaced next EYETS
 - Production is taking place these days
- LS3 – 23 units are needed to be replaced
 - Production (ongoing) and spares.

Laboratory team


- Part of the physics core facility unit at WIS
- Scientific Personnel
 - Overall scientific leadership – SB
 - Two permanent physicists – IR, LM
 - Physicist consultant – VS
 - Per project leadership – SB, SM, NT
- Technical team – 5 full time employees
 - Management - MS
 - Two project leaders – GC, FB
 - Two engineers – BY, ZF
- Temporary team – hired per project
 - Currently 2 and up to 20 in intense mass production periods

Laboratory expertise

- Multi wire proportional chambers
- Transition for MPGD structure is straight forward
- Transition to other technologies is doable

- Fully equipped with necessary instrumentations
 - Flat granite tables, PS, measurement equipment and raw material to produce detectors
- Procurement of new instrumentation supported by the institute
 - Provided decent scientific justification

Example equipment – Faro arm



**3D measurement to
the 20 μ m level**

Example equipment – Graphite spraying machine

- Capacity > 40 large area PCBs (TGC CB are 3 m²) per day
- Good accuracy



Example equipment – Adjustable winding machine

- Custom made based on in house design
- Adjustable table size – to cope with the different dimensions of the TGC types



Example equipment – XY X-ray machine

- Designed for the QA/QC of the sTGC
 - By the Russian team
- X-Y portable table synchronized with X-Ray tube and PS
- Used for gain uniformity test and identification of hotspots



Transition to the new DPPA building


- New building for the department of particle physics and Astrophysics
 - Construction start next year and will take ~3 years
- We are going to get a 850m² laboratory
 - Double than what we have today
- We will have all the facilities that we have today, but bigger and better

The new building



The new lab

Section | North- South



מכון ויצמן למדע
WEIZMANN INSTITUTE OF SCIENCE


MYS
ARCHITECTS


END

Thanks

Angle (Using the Faro arm)

	Quad no' 1	Quad no' 2	Quad no' 3	Quad no' 4	Quad no' 5	Quad no' 6	Quad no' 7	Quad no' 8	Quad no' 9	Quad no' 10	Quad no' 11	Quad no' 12	Quad no' 13
1st layer angle (°)	-0.003	0.012		-0.005	-0.006	-0.004	0.003	0.007	0.001	0.004	0.01	0.01	0.009
2nd layer angle (°)	-0.008	0.013		-0.005	0.005	0.006	0.009	0.01	0.004	0.001	0.006	0.004	-0.008
3rd layer angle (°)	0.006	0.016		0.004	0.007	0.008	0.004	0.001	0.007	0.01	0.004	-0.005	0.01
4th layer angle (°)	0.002	0.001		0.004	0.006	0.001	-0.011	0.005	0	-0.007	0.005	0.01	0.008






FARO ARM


- This arm can move 2.7m around the connection point and measure any object by either touching points or scan it with laser.
- Precision of the Faro is 27 Micron max.
- We use the Faro for measuring cathode boards and also for final alignment test of quads.



Isometric view actual measurement




The nominal distance between Vbrass to strip at 90°





NSW

Our major responsibility
was to produce 60 quads.
40 of type QL1
20 of type QS3




4 QS1 added in
the end of the project



IRRADIATION OF X-RAY MACHINE

- All the detectors and material pass x-ray irradiation to check long term stability and weak points

QL1 # 2, single gap # 4



LAB contribution at CERN

- Replacement and maintenance of TGC's on the big wheels
- Testing detectors at CERN including Beam test and GIF
- Experts technician with

