



# Status Report on D1 Magnets

**Tatsushi NAKAMOTO, KEK**

**On behalf of CERN-KEK Collaboration for  
D1 Construction for HL-LHC**

# Acknowledgement

- KEK (in particular)

M. Sugano, K. Suzuki, Y. Arimoto, R. Ueki, Y. Ikemoto, H. Kawamata, N. Okada, R. Okada, H. Ohhata, A. Terashima, K. Tanaka, N. Ohuchi, T. Ogitsu.

- Univ. of Tokyo

N. Kimura.

- CERN (in particular)

E. Todesco (WPL), H. Felice (exWPE), J. C. Perez (WPE), H. Prin, D. Duarte Ramos, C. Scheuerlein, H. G. Gavela, A. Devred.



- Hitachi

M. Yanagisawa, A. Yokogi, H. Togashi, T. Tahara, T. Chiba

- Fusac Technologies

T. Ichihara.

# Japanese Contribution to HL-LHC: D1 magnets




- Beam separation dipole (D1) by KEK
  - Design study of D1 for HL-LHC within the framework of the CERN-KEK collaboration since 2011.
  - 150 mm single aperture, 35 Tm (5.6 T x 6.3 m), Nb-Ti technology.
  - Development 2-m long model magnets (3 units) at KEK
- Deliverables for HL-LHC
  - *1 full-scale prototype cold mass (LMBXFP)*
  - *6 series cold masses (LMBXF1-6)*

**7 units x 7-m long cold masses**

Status Report on D1 Magnets, T. Nakamoto, KEK

# Design parameters

	prototype, series production (7m)
Coil aperture	<b>150 mm</b>
Field integral	<b>35 T m</b>
Field (3D)	<b>Nominal: 5.60 T, Ultimate: 6.04 T</b>
Peak field (3D)	<b>Nominal: 6.58 T, Ultimate: 7.14 T</b>
Current	<b>Nominal : 12.11 kA, Ultimate 13.23 kA</b>
Operating temperature	1.9 K
Field quality	$<10^{-4}$ w.r.t $B_1$ ( $R_{ref}=50$ mm)
Load line ratio (3D)	Nominal: 76.5%, Ultimate: 83.1% at 1.9 K
Differential inductance	Nominal: 4.0 mH/m
Conductor	Nb-Ti: LHC-MB outer cable
Stored energy	Nominal: 340 kJ/m
Magnetic length	6.26 m
Coil mech. length	6.58 m
Magnet mech. length	6.73 m <b>12 ton</b>
Heat load	<b>135 W (Magnet total)</b> <b>2 mW/cm<sup>3</sup> (Coil peak)</b>
Radiation dose	<b>&gt; 25 MGy</b>



**Large-aperture single layer coil →**  
**Mechanical support of a coil is challenging**


Three 2 m model magnets were developed at KEK.



# D1 Prototype Cold Mass: MBXFP1

# Full-scale D1 Prototype

- Magnet technology developed through 2m-long model magnet program (2011-2019) by KEK has been transferred to Hitachi.
- **Objective:** *Validation of design, manufacturing procedure and performance of a full-scale magnet constructed by Hitachi.*
- Cold test of the D1 prototype magnet at 1.9 K at the 9-m deep vertical cryostat at KEK was carried out in June to Sep. 2021.




D1 magnet for vertical cold test (Yoked magnet w/ shell, end-ring)



D1 cold mass to be delivered to CERN

# Recall Testing of D1 Prototype at KEK

- Lifting up the D1 magnet




- Insertion into vertical cryostat



Test Report of MBXFP1  
EDMS 2747573

# Vertical Cold Test Results Prototype



(units)

	Field Integral at 12.1 kA		
	Calculation		Meas.
	CERN H-Cryo.	KEK V-Cryo.	KEK V-Cryo.
$b_3$	-0.5	<b>-6.5</b>	<b>-12.7</b>
$b_5$	4.9	<b>4.8</b>	<b>6.5</b>
$b_7$	0.3	<b>0.3</b>	<b>0.5</b>
$b_9$	0.5	<b>0.5</b>	<b>0.8</b>
$b_{11}$	-0.2	<b>-0.2</b>	<b>-0.2</b>
$b_{13}$	-0.8	<b>-0.8</b>	<b>-1.0</b>
$b_{15}$	-1.3	<b>-1.3</b>	<b>-1.4</b>

## Training behavior

- The maximum current was 12.87 kA which was limited by allowable terminal voltage of DCCB.
- Good performance was confirmed while the ultimate was not demonstrated.

## Field quality

- Some discrepancies observed in  $b_3$  and  $b_5$ .
  - Larger discrepancy observed in  $b_3$  integral comes from the coil ends.
- **A fine tuning of the coil cross section for series production magnets.**



# Flow of D1 Cold Mass Production

PV: Pressure Vessel






HITACHI

KEK


HITACHI

KEK

CERN



# Welding Qualification for Manufacturing the D1 Pressure Vessel







Welding Book Part. 1 for Main body: **EDMS 2492330 Released.**

- Welding for the magnet (shell, end-ring).
  - **PQR 1, 2** for t=10mm: Completed.
- Welding Books Part. 2 for End dome & Part 3 for Extremities are completed.
  - Welding for End-cover, CBT, HX and the extremities.
  - **PQR 4, 5** for t=1 to 3 mm: Charpy V notch test required in EDMS 1891856 Rev. 4.31, but not-appropriate for shin plates. **Quite a long time for establishing qualification regulation...**
    - Charpy Test for PQR 4 (t=2 mm) was completed on Jan. 11.
    - Charpy Test for PQR 5 (t=1 mm) was finally **completed on Feb. 1, 2022.**
  - **PQR 6, 7, 8:** Lip weld joints, not specified in ASME or EN. Special agreement with CERN for welding qualification.
    - PQRs were completed including the burst-test.

DWC No. 310TC41-935			
<p>The Superconducting Beam Separation Dipole Magnet Cold Mass D1 For the High Luminosity LHC Project</p> <p>Prototype Part I (Main Body)</p> <p>Welding Book</p>			
SIGNATURES		DATE	TITLE Dipole Magnet D1
DWN	短越	2021.02.25	Prototype Welding BOOK
CHKD	高山	2021.02.25	
APPR	平美	2021.02.25	
Hitachi, Ltd. Tokyo Japan		DWG No. 310TC41-935	SH 1 / 25 REV 1
CAD SOFTWARE	WORD	SIZE DESIGNATION	A4





# Extremities Welding







Extremities Position Adjustment Tooling  
(Lines M, L, X, V for NIP and IP sides)

# SC Bus Leads and “Spider”


- SC bus leads and “Spider”: thanks to Herve and Rosario.
- Vtap installation and wire routing.



# SC Bus Leads and "Spider"






Spider for centering the bus-leads in Line M




# Insertion of CBT



- The allowed gap between CBT and inner surface of the coil structure is approximately ~1 mm.
- Insertion was very smooth and applied load was consistent with prediction (weight of CBT, friction of pinion): impedance induced in the bore was negligible.
- Hipot test at 2 kV was successfully passed.



# End-dome, End-cover




- Outer-rings to correct the formed and longitudinally-welded end-dome.
- Position of the end-cover was precisely aligned with respect to the mechanical fiducial of the magnet defined by the 32 alignment markers using the laser tracker.



- Hipot test at 3.1 kV between IFS tube and wires was passed.



# Saddle






- Position of the support saddles was precisely aligned with respect to the mechanical fiducial of the magnet defined by the 32 alignment markers using the laser tracker.

# Pressure Proof Test and Leak Test of the D1 Prototype

- A dedicated SS vacuum chamber (10 m long, ID 1000mm) was prepared for the pressure proof test (PPT) and leak test (LT) at Hitachi.
- “Guideline of Proof Test and Helium Leak Test for D1 Cold Masses”: EDMS 2681049.
- Test condition and criteria:

- PPT at 2.5 MPa<sub>Abs</sub> for cold mass,
- LT at 2.0 MPa<sub>Abs</sub>
  - ✓ Vacuum chamber: < 1 e-10 Pam<sup>3</sup>/sec
  - ✓ Cold bore tube: < 1 e-11 Pam<sup>3</sup>/sec
  - ✓ HX tubes : < 1 e-6 Pam<sup>3</sup>/sec

**All passed.**




# Series Production: MBXF1 and MBXF5

# Summary of results of coil size measurement

Magnet	Coil	Total average (MPa)	Max value (MPa)	Min value (MPa)	Standard deviation (MPa)	Cable thickness (44 stack) wrt S2-4 cable (mm)*
MBXFP1	LPT-1	112	116	106	2.0	0.262
	LPB-1	110	113	108	1.4	0.256
MBXF5	LT-1	122	125	119	1.5	0.418
	LB-1	122	125	118	1.8	0.422
MBXF1	LT-2	117	120	114	1.3	0.397
	LB-2	125	128	112	1.6	0.403

- Target range of the total average:  $115 \pm 10$  MPa.
- Thickness of the insulated SC cables from 19 spools was determined by the “10-stack measurement” before the coil winding.
- Dimension control of the wedge thickness:  $< 30 \mu\text{m}$
- All the prestresses are within the target range.
  - Check for the LB-2 coil with higher value is underway.



# MFM of MBXF5 after yoking

- Experimental check of **new coil cross section for the series magnets**.
  - Fine tuning of  $b_3$  and  $b_5$  with respect to the MBXFP1.
- Warm field measurement at Hitachi Rinkai-work.

$R_{ref}=50$  mm

Measurement


Calculation

n	Data						Roxie2D					
	MBXFP		MBXF5		MBXF5-MBXFP		MBXFP (v11.D)		MBXF5 (v13.A)		MBXF5-MBXFP	
	an	bn	an	bn	an	bn	an	bn	an	bn	an	bn
2	-1.4	0.8	-1.7	-0.3	-0.3	-1.0	0.0	0.0	0.0	0.0	0.0	0.0
3	0.0	-4.9	-0.6	-0.1	-0.6	4.8	0.0	-7.3	0.0	-2.7	0.0	4.6
4	0.1	0.4	0.0	0.0	-0.1	-0.4	0.0	0.0	0.0	0.0	0.0	0.0
5	-0.1	2.9	0.0	-2.8	0.1	-5.7	0.0	2.7	0.0	-2.8	0.0	-5.5
6	0.3	0.1	0.1	0.2	-0.2	0.1	0.0	0.0	0.0	0.0	0.0	0.0
7	0.0	1.0	0.1	0.0	0.1	-1.0	0.0	1.1	0.0	0.1	0.0	-1.0
8	0.4	0.1	0.1	0.0	-0.2	-0.1	0.0	0.0	0.0	0.0	0.0	0.0
9	0.0	0.6	0.1	0.1	0.1	-0.5	0.0	0.6	0.0	0.0	0.0	-0.6
10	0.1	0.0	0.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
11	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.1	0.0	0.1	0.0	0.0
12	-0.2	-0.1	0.0	0.1	0.2	0.2	0.0	0.0	0.0	0.0	0.0	0.0
13	0.0	-0.6	0.0	-0.5	0.0	0.0	0.0	-0.6	0.0	-0.6	0.0	0.0
14	-0.5	-0.3	0.1	0.0	0.5	0.3	0.0	0.0	0.0	0.0	0.0	0.0
15	0.0	-1.0	0.1	-1.0	0.2	0.0	0.0	-1.2	0.0	-1.0	0.0	0.1
16	-0.3	-0.2	-0.1	-0.1	0.2	0.2	0.0	0.0	0.0	0.0	0.0	0.0
17	0.1	-0.6	0.0	-0.5	-0.1	0.1	0.0	-0.7	0.0	-0.7	0.0	0.0
18	0.3	0.1	0.1	0.1	-0.2	0.0	0.0	0.0	0.0	0.0	0.0	0.0
19	0.0	0.3	-0.1	0.1	0.0	-0.2	0.0	0.4	0.0	0.4	0.0	0.0
20	0.0	0.0	-0.1	0.0	-0.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0


- ✓ Tuning of Multipoles: Consistent with the 2D model
- ✓ KEK proposes to give Hitachi a green-light to resume fabrication of the wedges of MBXF2.

# Status of Manufacturing

- MBXF5
  - NC: potential coil insulation damage was found after removal of the collaring-mandrel after yoking process. EDMS 2753776.
  - The yoked magnet was fully disassembled and the coil insulations were repaired.
  - The inspection tests to confirm the electrical insulation and the mechanical property of the coils are underway.
  - The magnet re-assembly is foreseen in January 2023 after review of the repair work.
- MBXF1
  - Shell welding was completed and RT is underway.
  - The vertical cold test is planned around April 2023.
- MBXF2
  - Coil winding will be started in February 2023.



Insulation repair of MBXF5 coil



MBXF1 in preparation for shell welding  
Status Report on D1 Magnets, T. Nakamoto, KEK


# Components delivered from CERN

	Item Code	0	1	2	3	4	5	6	7
		SC cables	QPH Laminate	Cold bore tube	End-cover	HX tube	Extremity parts	Cryo Heaters	Thermometers
Until Dec. 2019		19	14	0	0	0	0	0	0
March, 2020	ID 8294098, delivery on August 18	0	0	1	0	0	9 IFS pipes (obsoleted)	0	0
April, 2020	ID 8302253, delivery on July 3	0	0	0	3	0	3 (obsoleted)	4 (obsoleted)	8
Oct., 2020	ID 8455728, delivery on Nov. 4	0	0	0	11	0	3	10 (obsoleted)	20
Dec., 2020	ID 8477112, delivery on Jan. 12, 2021	0	0	3	0	4	6 IFS pipes	0	0
Aug., 2021	ID 8842597, delivery on Aug. 6, 2021	0	4	0	4	0	3	2	0
Oct. 2021	ID 8942303, delivery on Oct. 15, 2021	0	0	0	0	0	*	4	0
May. 2022	ID 9228712, delivery on May 9, 2022	0	1 Compensation	0	0	0	0	0	0
Nov, 2022	ID 9328931, delivery on Nov. 16, 2022	0	0	4	0	8	0	0	0
Jan., 2023	Production underway	0	6 QPH (2eq)	0	0	0	0	0	0
XXX, 2023		2	TBD	0	0	2	**	8	0
Total # (unit, set)		21	18+2eq	8	18	14	9	14	28

- EDMS 2326071 v.1.0, EDMS 2209761 v.1.0
- Issues of QPH laminate: defected insulation, delamination
  - CERN PCB group will produce 6 pieces of QPH for D1. Delivery is foreseen in January 2023.
- Nearly completed, but still a few deliveries from CERN will be required to cover a full series production of the D1.

# Production Schedule

Plan by Hitachi in Nov. 2022



To be scheduled after coil repair.

株式会社 日立製作所  
2022-11-07  
日立事業所  
担当: 加藤 崇





# Summary

- The D1 prototype cold mass was completed and delivered to KEK in September 2022.
  - To be delivered to CERN in March 2023.
  
- A series production of the D1 was started in 2021.
  - MBXF5
    - NC: potential coil insulation damage was found after removal of the collaring-mandrel after yoking process. EDMS 2753776.
    - The coil insulations were repaired. The magnet re-assembly is foreseen in January 2023 after review of the repair work.
  - MBXF1
    - Shell welding was completed and RT is underway. The vertical cold test around April 2023.
  - MBXF2
    - Coil winding will be started in February 2023.

# Additional Helium Gas Storage Bag

- Limitation of helium gas recovery at quenches of MBXFP1.
- Present capacity: **280 m<sup>3</sup>** (#2: 80 m<sup>3</sup>, #4: 200m<sup>3</sup>)
- Helium gas at 13.23 kA w/ **Varistors**: **294 m<sup>3</sup>** (prediction)
- Plan: new Helium gasbag (#4b, **40 m<sup>3</sup>**)
  - Total capacity: **320 m<sup>3</sup>** > 294 m<sup>3</sup>
  - #4b Gasbag to be installed next to #4 Gasbag in the same tent warehouse
  - The gasbag is already available. The drawings are being prepared in a rush.



In the event of MBXFP1 quench

