




Technology Department Vacuum, Surfaces and Coatings Group 2022's General Meeting




Paolo Chiggiato
Group Leader




Outstanding results in 2022




[Generated at: 2022-11-27 06:16:44]



[Generated at: 2022-11-24 23:30:22]




[Generated at: 2022-11-24 23:31:05]



Outstanding results in 2022

Approached 1.5×10^{11} ppb at start of stable beams. Reached record stored beam energy of almost 400 MJ



[Generated at: 2022-11-27 18:17:05]



Fast switching from proton to ions and ions to protons (two days).






LHC SCRUBBING RUN Baked Sectors Overview

Conditioning effect visible in all room temperature sectors


Pressure measurements scattered through 3 orders of magnitude:

- Vacuum sector history dependence
- Different systems, sector lengths, effective pumping speeds






Three TE-VSC sections involved (BVO, ICM, SCC) in the **upgrade of the VELO and SMOG-2**: now perfectly working with beams.




In-situ **carbon coated** beam screen in **Q5L8** standalone magnet:
no measurable heat load.



Run 2



Run 3



Plasma cleaning of radioactive vacuum equipment



Outstanding results in 2022


Aim: replace a wet degreasing with a plasma cleaning for **activated** parts; avoid liquid retention in complex shapes (avoid complex treatment of activated fluids).

-O₂ plasma to oxidise hydrocarbons to CO₂





ZS tank D=600mm L=3500mm


First real PSB tank cleaned successfully



Simulation: plasma species generation, surface and gas collisions, transport of active species



🏆 Outstanding results in 2022 🏆




A milestone:
HL-LHC beam-screen dummy inserted in a real magnet.

Installation of New Titanium LHC Dump Windows



Outstanding results in 2022



- Double windows design:
 - A Ti window in sandwich between 2 C/C disks. (vacuum side).
 - A second robust window downstream (vacuum/atm).
- **First use of SMA coupling in accelerators.** Implementation of a DN25 Steel-Titanium joint for LHC dump window

SCADA Performance Study




Outstanding results in 2022



Gather performance metrics of the system

Refactor problematic components



Analysis of the current environment

Identify sources of poor performance

Gather new performance metrics of the system







Performance Measuring Panel

- Several algorithms modified to increase the performance of the vacuum SCADA
- LHC's Main View loading time is expected to improve ± 10 seconds compared to the previous baseline after the LHC SCADA update
- Startup performance will further improve after the deployment of the new Unified Mobile System to about 50% of current time
- New metrics gathering system will allow to monitor the performance evolution on upcoming SCADA releases

Implementation of TSPP for Vacuum Framework (“UNICOS-style” Data Acquisition)

- **Time Stamped Push Protocol**: vast improvement in Time and Value resolution of acquired data
- No more lost data (pressure spikes, fast interlocks, momentary glitches, etc)
- Start of **deployment during 2023**



Polling at 1s

Pressure peaks every 5 seconds (**top**), ramp up/down every second (**bottom**)

With TSPP

Same signals, now properly acquired

Determination of the problem that caused the failure of four DQLPR001 power supplies: EDMS 2779930






Figure 15. DSC thermogram of the black oily liquid 30–500 °C at 10 °C/min

‘It seems highly probable that the PSU’s failure was caused by the **PowerStor® Aerogel capacitors** damaging their PCBs. It can also be assumed that the **release of the solvent and ammonium salts** was a factor that, together with slightly elevated operating temperature, caused the **decomposition of the PU cable.**’

MolFow+ extension



Outstanding results in 2022





Time dependent simulation of pipes

Vacuum chamber conditioning (VacuumCOST)

Python code for iterative Monte Carlo resolution.

Allow time-dependent simulation of conditioning and NEG saturation

<https://gitlab.cern.ch/phenril>



into NEG-coated tube.
density of adsorbed
d facets are saturated.




Outstanding results in 2022

TE-VSC Seminars

31 seminar talks in 24 group meeting, including Leybold's day and two **joint MME-VSC seminars**.

Good collaboration and support from the whole VSC group; excellent way to **share information**.

Number of Seminars during 2022



December 2022	
15 Dec	TE-VSC Plenary NEW
13 Dec	HL-LHC yearly update
06 Dec	Gas propagation in cryogenic tubes // New Sector Valve Control Unit
November 2022	
29 Nov	Leybold Users day at CERN
23 Nov	Joint TE-VSC and EN-MME Seminar on LISA - 23 November 2022
15 Nov	Production of a-C coatings for new HL-LHC beam screens // Advances on Nb3Sn HiPIMS coatings for SRF cavities
09 Nov	Joint Seminar TE-VSC and EN-MME on 9 November 2022
01 Nov	Laser surface treatment setup and development
October 2022	
25 Oct	Scrubbing run results
18 Oct	Degassing and Ultimate vacuum of gauges // Thin self-supported carbon films
04 Oct	New Profibus and 4G mobile equipment connectivity (HW & PLC) // New passivation recipes for copper
September 2022	
20 Sept	FCC-ee vacuum chamber development // Renovation of the HPWR control system
13 Sept	simulations for chemical/electrochemical surface treatments // FCC-ee and hh prototyping
July 2022	
19 Jul	NEG Embrittlement studies // Vacuum vs Polymers
June 2022	

TE-VSC and EN-MME main actors in beampipes for next-generation gravitational waves detectors. **Now approved!**



Outstanding results in 2022



ADDENDUM NO. 1
KR5427/TE
TO
FRAMEWORK COLLABORATION AGREEMENT
KN 4657/DG

BETWEEN: THE EUROPEAN ORGANIZATION FOR NUCLEAR RESEARCH (“CERN”), an Intergovernmental Organization having its seat at Geneva, Switzerland,

AND: THE ITALIAN NATIONAL INSTITUTE FOR NUCLEAR PHYSICS (“INFN”), established in Rome, Italy,

AND THE DUTCH NATIONAL INSTITUTE FOR SUBATOMIC PHYSICS (“Nikhef”), established in Amsterdam, The Netherlands,

Hereinafter each individually referred to as a “Party” and collectively as the “Parties”,

CONSIDERING THAT:

Framework Collaboration Agreement KN4657/DG (the “Agreement”) concluded between the Parties defines the framework applicable to collaboration between them in domains of mutual interest.

Article 2.1 of the Agreement provides that the scope, each Party’s contributions, and all other details of each specific project shall be set out in Addendum to the Agreement.

The Parties have identified the collaborative project set out below, which shall be covered by the provisions of this Addendum No. 1 (the “Addendum”),

AGREE AS FOLLOWS:

**Article 1
Purpose**

- 1.1 Under the terms of this Addendum, the Parties shall collaborate in the development of the vacuum systems of the arms of the Einstein Telescope (“ET”) (the “Project”). The Project is outlined in [Annex 1](#).
- 1.2 The Parties shall use the results and resources of their collaboration for non-military purposes only. INFN and Nikhef shall ensure compliance with this obligation by the ET Consortium members.
- 1.3 This Addendum shall be subject to the provisions of the Agreement, it being understood that in case of divergence the provisions of this Addendum shall prevail.

**Article 2
Duration of the Project**

Subject to the continued validity of the Agreement, the Project shall begin upon signature by the last Party to sign and shall be completed after 36 months.

Done in the English language and signed by the authorized representatives of the Parties.

The European Organization
for Nuclear Research (CERN)

The European Organization
for Nuclear Research (CERN)

Mike Lamont

Jose Miguel Jimenez

Mike Lamont
Director for Accelerators and Technology

Jose Miguel Jimenez
Head of Technology Department

Signed on 7/7/2022.....2022

Signed on 8/7/2022.....2022

Christopher Hartley

Cristina Lara

Christopher Hartley
Head of Industry, Procurement and
Knowledge Transfer Department

Cristina Lara
Deputy Head of Procurement Service

Signed on 11/7/2022.....2022

Signed on 9/7/2022.....2022

The Dutch National Institute for Subatomic
Physics (“Nikhef”)

The Italian National Institute for Nuclear
Physics (“INFN”)

Stan Bentvelsen

Dr. Antonio Zoccoli

Stan Bentvelsen
Nikhef Director

Antonio Zoccoli
INFN President

Signed on 19/7/2022.....2022

Signed on 26/7/2022.....2022

LHC operation in 2023

- **2023 Final draft schedule:**
 - *YETS'23-'24: 4 weeks extension and 6 weeks anticipation as a result of the energy crisis*
 - *5 weeks Pb ions run, includes p-p reference run - partial compensation for no Pb ions in 2022*
 - *217 days YETS to YETS:*
 - *Start beam commissioning 27 March 2024*
 - *End of run 30 October 2023*

2023 – Q1

	Jan			Feb				Mar			Apr		
Wk	1	2	3	4	5	6	7	8	9	10	11	12	13
Mo	2	9	16	23	30	6	13	20	27	6	13	20	27
Tu	Annual Closure	Control System admin. days											
We													
Th	Control System admin. days					YETS							
Fr										DSO test		Machine checkout	
Sa													
Su													

LHC hand-over to BE-OP (between Mar 9 and 10)
 LHC, T12, T18 and experiments closed (between Mar 11 and 12)
 Start Beam Commissioning (at the end of Mar 13)

Post-YETS'22-23 commissioning as initially foreseen – not impact by change of YETS

Control system administration days in wk1 and wk2

LHC hand-over to OP & DSO test 10 March

Hardware re-commissioning and machine cold check out wk11 and wk12

Beam commissioning starts 27 March

Rende Steerenberg LMC 30-11

2023 – Q2

	May							Jun					Jul
Wk	14	15	16	17	18	19	20	21	22	23	24	25	26
Mo	3	Easter 10	17	24	1st May 1	8	15	22	Whitsun 29	5	12	19	VdM 26 program
Tu					Scrubbing								
We	Re-commissioning with beam											TS1	
Th							Ascension						
Fr	G. Fri.				Interleaved commissioning & intensity ramp up						MD 1		
Sa													
Su													

First Stable beams: indicated by a vertical arrow pointing to the start of week 16.
 Collisions with 1200 bunches: indicated by a vertical arrow pointing to the start of week 20.
 SPS HiRadMat#1: indicated by vertical hatched bars between weeks 20-21 and 25-26.

Beam commissioning & intensity ramp-up wk14 – wk19

- First stable beams **22 April**
- 2 day e-cloud scrubbing run

Start of physics with 1200 bunches 15 May

SPS HiRadMat#1 added as indication in wk22

MD1 block (5 days) in wk24

Technical stop & technical stop recovery wk25

Van de Meer run week 26 followed by return to normal p+ physics

- This week is also a spare week for SPS HiRadMat

Rende Steerenberg LMC 30-11

2023 – Q3

	Aug							Sep			Oct		
Wk	27	28	29	30	31	32	33	34	35	36	37	38	39
Mo	3	10	17	24	31	7	14	21	28	4	11	18	25
Tu												TS2	p-p ref run
We				MD 2					High β run				
Th										Jeune G.		p-p ref setup	
Fr											MD 3		
Sa												p-p ref run	
Su													Ion setting up

End 25 ns run [08:00]

Good period of hopefully stable p+ running and lumi production

SPS HiRadMat runs added as indication in wk29 and wk34

MD2 block (5 days) in wk30

High beta run in wk35 is a place holder – the actual dates may change depending on the needs

MD3 block (5 days) in wk37

Wk 38 until end of the 2023 run Pb ion run period

- 3-day technical stop for experiment to move in ZDCs – no major activities expected in the LHC machine – quick restart
- p-p reference run and its setting-up
- Pb ion setting-up

Rende Steerenberg LMC 30-11

2023 – Q4

Wk	Nov				Dec								
	40	41	42	43	44	45	46	47	48	49	50	51	52
Mo	2	9	16	23	30	6	13	20	27	4	11	18	Xmas 25
Tu			MD 4										
We													
Th		LHC Pb- Pb ion run						YETS					Annual Closure
Fr													
Sa													
Su													

Wk40 – Wk43 Pb-Pb ion run

24 hours MD slot on 17 October


End of 2023 run on Monday 30 October @ 06:00

SAFETY



Safety (status on 1st Dec 2022)

11 incidents
reported in TE-VSC (info from **DSO**)



Loss of working days:
0 MPE, **0** for MPA+MPAt, **0** for ENTC




Accident (status on 6th Dec 2022)

Date	Incident de sécurité	Groupe	Statut	Catégorie	Bâtiment	Description	Type d'incident de sécurité	Siège des lésions	Elément matériel	Jours d'arrêt
17 janv. 22	Accident évité de justesse	VSC	Titulaire (STAF)	MPE	3126 (LHC Pt1 - UX15)	Légères décharges ressenties lors de l'installation du beam pipe depuis une petite nacelle une place	Sécurité électrique	Pas de lésions	Electricité	
7 févr. 22	Accident évité de justesse	VSC	Attaché(e) de projet (PJAS)	MPA	Hors CERN	Chute à vélo après avoir perdu l'équilibre lorsqu'une sangle de son sac à dos s'est prise dans les rayons	Sécurité routière	Pas de lésions	Véhicules	
8 févr. 22	Accident évité de justesse	VSC	Attaché(e) de projet (PJAS)	MPA	Hors CERN	Chute à vélo après avoir perdu l'équilibre en heurtant une bordure de trottoir	Sécurité routière	Pas de lésions	Véhicules	
14 févr. 22	Accident				548	Accrochage d'un rétroviseur avec un autre véhicule lors du passage dans le tunnel	Sécurité routière			
11 avr. 22	Accident évité de justesse				376	Morceaux saillants touchant les mains et les avant-bras de l'opérateur suite à la rupture en plusieurs parties de la protection en plastique sur un tour, en la manipulant après un usinage	Sécurité matériel	Pas de lésions	Machines / Machines-outil fixes	
2 mai 22	Situation dangereuse				814 (SPS, sous BA1)	Étincelles de fumée au niveau d'un câble électrique endommagé recouvert d'eau	Inondation			
16 mai 22	Accident professionnel	VSC	Employé(e) d'entreprise contractante du CERN (ENTC)	ENTREPRISE	3191 (hall SMI2)	Heurt de la tête contre une bride de cryostat en se relevant	Accident du travail	Tête	Heurt au poste de travail, faux-mouvement	0
11 août 22	Accident professionnel	VSC	Attaché(e) de projet (PJAS)	MPA	376	Coupeure index main droite avec une pièce métallique tranchante	Accident du travail	Mains	Objets en cours de manipulation/manutention manuelle	0
2 sept. 22	Accident professionnel	VSC	Titulaire (STAF)	MPE	Hors CERN	Douleur à l'épaule et égratignures sur la jambe en chutant au sol après avoir été percuté par un véhicule alors qu'il était arrêté à un feu rouge avec son scooter	Accident de trajet	Localisations multiples	Véhicules	0
27 sept. 22	Accident évité de justesse	VSC	Etudiant(e) en doctorat (DOCT)	MPA	CERN	Signalement d'un véhicule entrant dans un rond-point sans tenir compte de la présence d'un cycliste	Sécurité routière	Pas de lésions	Véhicules	


info from DSO

Evolution of the number of incidents since 2014

Incidents professionnels par année



Incidents professionnels par catégorie de personnel



Check your training courses

- [Ims.cern.ch](https://ims.cern.ch)

and access right :

- ADaMS (from CERN directory, Applications)

In case of doubts or problems, please contact GL or **Bernard Henrist, our Safety Link Person (SLP)**.



Departmental officers (2022)



Delphine
Letant-Delrieux

DSO
Deputy RSO

162473



Alexis Vidal

Radiation SO
Deputy DSO


164502



Olivier Pirotte

Cryogenic SO

164252



David Jaillet
(Dept. EN)

Flammable
Gas SO

167151



Bruce Marsh
(Dept. EN)

Laser SO

162552



Leonel M. A.
Ferreira

A&T sector
Chemical SO

163612

Staff members with safety roles

Radiation Safety Support Officer RSSO *GENERAL SAFETY INSTRUCTION GSI-SO-8*

RSSO are nominated by the group leader



Jan Hansen



Antonio
Mongelluzzo



Anthony Harrison



Jerome Chaure



Ludovic Mourier



Alexis Vidal



Paul Demarest



Julien Finelle












Staff members with safety roles

Territorial Safety Officer TSO
GENERAL SAFETY INSTRUCTION GSI-SO-2

TSO are nominated by the department head


Deputy Territorial Safety Officer DTSO
GENERAL SAFETY INSTRUCTION GSI-SO-2

DTSO are nominated by the department head

	SMA-18		118 676		10-1		10-1		142 SMA-18
Alexis Vidal		Serge Forel		Benoit Teissandier		Colette Charvet		Bernard Henrist	
	112 142		169		101				101
Jerome Gilles Chaure		Paul Richard Demarest		Wilhelmus Vollenberg				Benoit Tessandier	
	368				375-1 ISR Ring				
Jose De La Gama Serrano				Antoinio Mongelluzzo					

Waste-water treatment plant

Regular treatment and monitoring of the released effluent measured by ICP-OES at the Chemistry Lab.



TE-VSC group structure

Dec 2022

- Staff: 72
- Fellows: 27
- MPA: 25, including 3 COAS
- **→ Total: 124**

Associates for the purpose of international collaboration (MPAc);
Associates for the purpose of exchange of scientists (MPAx);
Associates for the purpose of training (MPAt).

Our director general and new president of CERN Council



Director-General of CERN, **Fabiola Gianotti**



President of the CERN Council, **Eliezer Rabinovici**


Our management

**Our A&T director
Mike Lamont**




**Our TE Department Head
José Miguel Jimenez**





Courtesy of Mike Lamont



SECRETARIAT



TE – VSC

Vacuum, Surfaces & Coatings group



GL OFFICE



Vacuum Studies and Measurements (VSM)



Beam Vacuum Operation (BVO)




Design, Logistics & Methods (DLM)



Interlocks, Controls & Monitoring (ICM)



Surface, Chemistry Coatings (SCC)



Staff Members



Left TE-VSC in 2022:


- Pablo Prieto (ICM)
- Patrick Lepeule (BVO)
- Claude Collomb Patton (BVO)

New staff members in TE-VSC:

- Benjamin BAYLISS (ICM)
- Valentine PETIT (SCC)

Structure of the TE-VSC group







Giorgione, Tre età dell'uomo
Galleria Palatina, Firenze



Age of staff members in Dec 2022

Average age: 45.5
was 42 in 2014




Giorgione, Tre età dell'uomo
Galleria Palatina, Firenze



Average age: **38.1**



Age of all MP in Dec 2022



Category of staff members in Dec 2022

Staff indefinite contract (IC): 57


Staff limited duration (LD): 15




Cat 2: Scientific work

Cat 3: Technical work


Category of staff members in Dec 2022



Staff indefinite contract (IC): 57
Staff limited duration (LD): 15




A 15-country group, with a significant French composition in Dec 2022




Staff distribution vs career path

2015



Staff indefinite contract (IC): 57
Staff limited duration (LD): 15

Grades of staff members in Dec 2022




Gender repartition in TE-VSC in Dec 2022




Maestro delle storie del pane, Portrait of a man and a woman, New York

In USA in the 2017-2018 academic year, women represented **about 21%** of the bachelor's degree holders in the fields of engineering and computer/information sciences.

Source: SWE, Society of Women Engineers






















































Average F / tot : **22%**




Student, fellows and collaborators in Nov 2022

Students & collaborators

Vacuum Studies and Measurements (VSM)	Beam Vacuum Operation (BVO)	Design, Logistics & Methods (DLM)	Interlocks, Controls & Monitoring (ICM)	Surface, Chemistry Coatings (SCC)
 C. Castro Squitiro FELL 31.01.2024  P. Hevričan FELL 31.01.2024  A. Hooper FELL 31.05.2024  F. Kivortz FELL 31.10.2023  J. Repolho Correia FELL 31.12.2023  A. Sibatani FELL 29.09.2023  E. Terazon TECH 30.08.2023  Q. Duong DOCT 31.03.23  C. Bevilacqua DOCT 31.10.23  A. Passarelli COAS 31.12.2022	 A. Bissolati FELL 31.01.2024  K. Hopponi FELL 31.10.23  R. Hill James FELL 31.05.2023  T. Raski FELL 31.03.2024  O. Ribeiro FELL 31.10.2023  X. Sax FELL 31.09.2024  P. Czapkiewicz TECH 31.07.2023  P. Nacidiou TECH 31.07.2023  C. Scaccia DOCT 31.03.2023  A. Gallero PJAS 30.04.2023  I. Lopez Cuevas PJAS 31.03.2023  Y. Mertins PJAS 31.12.2022  T. Silva PJAS 31.10.2023	 H. Hevričan FELL 31.08.2024  M. Knovich FELL 20.09.2024  B. Raviso FELL 31.05.2023  M. Sorenelli FELL 30.09.2024  V. Giovinco DOCT 28.02.2023  R. Perez Martinez PJAS 31.12.2022  F. Niccoli PJAS 31.09.2023	 J.D. Francisco Rebelo FELL 30.09.2023  J. Staniszewski FELL 30.09.2023  D. Terfinkiy FELL 31.03.2023  S. Goncalves Soares PJAS 31.12.2023  M. Khatib PJAS 31.12.2022	 T. Agulhon FELL 31.12.2022  M.C. Dienero FELL 20.02.2024  A. Gulland FELL 31.10.2024  S. Lenti FELL 30.11.2023  T. Munka FELL 30.09.2023  A. Rosasco FELL 31.03.2024  N. Nirodhi FELL 30.07.2023  S. Baraglia FELL 30.06.2024  M. Watkins FELL 30.06.2024  N. Souchet TRNE 31.12.22  G. Bellini TRNE 31.08.23  C. Amadio DOCT 31.12.2023  E. Bilo DOCT 31.07.2023  C. Perrone DOCT 28.02.2023  E. Stranella TECH 31.07.23  R. Cimbro COAS 29.09.2021

November 2022




- 12-2022: **49** (exc. COAS)
- 12-2021: **46** (exc. COAS)
- 11-2020: **51** (exc. COAS)
- 11-2019: **53** (exc. COAS)
- 11-2018: **53** (exc. COAS)
- 12-2017: **58** (exc. COAS)
- 12-2016: **55** (exc. COAS)
- 12-2015: **37** (exc. COAS)
- 12-2014: **38** (7 COAS)

Age of non-staff members

Total: 49 (exc. COAS)


Average age: 27.3




COAS excluded

Evolution in 9 years


Status	2013	2017	2018	2019	2020	2021	2022
STAFF	75	74	75	74	74	72	72
TECH-ADMIN	9	15	6	8	5	5	5
DOCT	2	5	5	5	6	7	7
FELL GET-DGP-EU	13 (6 GET)	17 (14 GET)	19 (13 GET)	17 (11 GET)	17 (9 GET)	13 (6 GET)	17 (11 GET)
FELL TTE-TTS	2	8	9	9	8	6	10
SASS	1	0	0	0	0	0	0
PJAS	8	9	9	9	7	8	8
VIA, ADI, Trainee	3	4	5	5	8	7	2
TOTAL	75+38 113	74+58 132	75+53 128	74+55 129	74+51 125	72+46 118	72+49 121



PJAS evolution



Fellows TTE evolution



PhD students

DOCT: 7 at CERN in Dec 2022

1. Valentina GIOVINCO: **Shape memory alloys** for UHV bi-material connections
2. Elena BEZ: **Laser surface treatments** for accelerator applications
3. Catarina SERAFIM: Materials for **RFQ of LINAC4**, hydrogen implantation and blistering
4. Carlo SCARCIA: Materials for vacuum systems of next-generation **gravitational wave telescopes**
5. Carolina AMOEDO: Discharge **plasma source** design and characterisation
6. Carlota CARLOS : Development of high performance thin film **coatings for SRF cavities**
7. Quentin DUONG : Electron cloud interaction with laser treated beam tube at the **vacuum pilot sector**

Changes in the TE-VSC group structure

New Section: Insulation and Injectors Vacuum Operation (IVO)

Name	First Name	Status Code	Supervisor Name
SAX	Xavier Michel	FELL	FERREIRA SOMOZA, Jose Antonio Dr.
BITAUD	Alexis	FELL	PASQUINO, Chiara Ms.
NAZLIDOU	Panagiota	TECH	FERREIRA SOMOZA, Jose Antonio Dr.
DEMAREST	Paul Richard	STAF	FERREIRA SOMOZA, Jose Antonio Dr.
KORTESMAA	Jarmo	STAF	PASQUINO, Chiara Ms.
THAUS	Nicolas Claude	STAF	FERREIRA SOMOZA, Jose Antonio Dr.
HARRISON	Anthony	STAF	PASQUINO, Chiara Ms.
FERREIRA SOMOZA	Jose Antonio	STAF	BREGLIOZZI, Giuseppe Dr. Paolo
SINTUREL	Alexandre Xavier	STAF	FERREIRA SOMOZA, Jose Antonio Dr.
PASQUINO	Chiara	STAF	BREGLIOZZI, Giuseppe Dr. Jose
MICHET	Alice Ingrid	STAF	FERREIRA SOMOZA, Jose Antonio Dr.
MERINO FERNANDEZ	Guillermo	STAF	FERREIRA SOMOZA, Jose Antonio Dr.

Changes in the TE-VSC group structure

Name	First Name	Organic Unit	Status Code	Professional Category	Supervisor Name	New Section
SCARCIA	Carlo	TE-VSC-BVO	DOCT	2	BREGLIOZZI, Giuseppe Dr.	no
CZAPKOWICZ	Paulina Gabriela	TE-VSC-BVO	TECH	2	WEVERS, Ivo Mr.	no
REIS E RIBEIRO SANTOS	Orlando Miguel	TE-VSC-BVO	FELL	2	BREGLIOZZI, Giuseppe Dr.	no
HENNELI	Kristoffer	TE-VSC-BVO	FELL	3	BREGLIOZZI, Giuseppe Dr.	no
RASKA	Tomas	TE-VSC-BVO	FELL	2	SESTAK, Josef Mr.	no
HILL-JAMES	Rowan Cape	TE-VSC-BVO	FELL	3	BREGLIOZZI, Giuseppe Dr.	no
LOPEZ CUEVAS	Isabel	TE-VSC-BVO	PJAS	2	BREGLIOZZI, Giuseppe Dr.	no
NASCIMENTO MARTINS	Vasco Miguel	TE-VSC-BVO	PJAS	2	SESTAK, Josef Mr.	no
GALLORO	Alessio	TE-VSC-BVO	PJAS	2	BREGLIOZZI, Giuseppe Dr.	no
PEREIRA NAVE HENRIQUES DA SILVA	Tomas	TE-VSC-BVO	PJAS	2	BREGLIOZZI, Giuseppe Dr.	no
HANSEN	Jan Helge	TE-VSC-BVO	STAF	2	BREGLIOZZI, Giuseppe Dr.	no
WEVERS	Ivo	TE-VSC-BVO	STAF	3	BREGLIOZZI, Giuseppe Dr.	no
ZELKO	Nicolas	TE-VSC-BVO	STAF	3	BREGLIOZZI, Giuseppe Dr.	no
PAGE	Eric	TE-VSC-BVO	STAF	3	BREGLIOZZI, Giuseppe Dr.	no
CALEGARI	Didier	TE-VSC-BVO	STAF	3	SESTAK, Josef Mr.	no
BREGLIOZZI	Giuseppe	TE-VSC-BVO	STAF	2	CHIGGIATO, Paolo Mr.	no
CHAURE	Jerome Gilles	TE-VSC-BVO	STAF	3	SESTAK, Josef Mr.	no
CATTENOZ	Gregory	TE-VSC-BVO	STAF	3	BREGLIOZZI, Giuseppe Dr.	no
FINELLE	Julien	TE-VSC-BVO	STAF	3	BREGLIOZZI, Giuseppe Dr.	no
SESTAK	Josef	TE-VSC-BVO	STAF	2	BREGLIOZZI, Giuseppe Dr.	no
VAZQUEZ PELAEZ	Cesar	TE-VSC-BVO	STAF	3	BREGLIOZZI, Giuseppe Dr.	no
OWENS	Karl John	TE-VSC-BVO	STAF	3	BREGLIOZZI, Giuseppe Dr.	no

Roles in TE-VSC

The roles and participation in CERN's official meetings are reported in:

<https://edms.cern.ch/document/2566636/2>



Memorandum



Date : December 8th, 2022
To : TE-VSC staff members
Copy to : José Miguel Jimenez
From : Paolo Chiggiato
Objective : Roles in TE-VSC and participation in official meetings from 01-2023

New post in 2023



Abel Grimmer, Spring

Posts	Planned contract start
Technical eng. in chemistry	Q3-Q4

CCRB slots in 2022



Posts	VSC candidates	Results
Mechanical technician	Christian Duclos	✓

Budget in 2022

Budget



OP budget and commitments (CET extraction 08-12):

Payment budget: **4.126 MCHF**

Charged to budget code on **recurrent** budget: **2.979 MCHF**

Commitment (incl. pipeline) on operation (**recurrent**) : **4.091 MCHF**

(Transitory code for IS and FSU, XPS and NEG pumps DR excluded)

PRJ+CONS budget and commitments (CET extraction 08-12):

Payment budget: **7.61 MCHF**

Charged to budget code on **non-recurrent** budget: **6.164 MCHF**

Most important lines of expenditure:

- Blanket contracts
- Industrial support
- EN-MME services
- CERN store








Jan Gossaert, Portrait of a Merchant, 1530
National Gallery of Art, Washington DC

2022 Budget

Operational budget evolution

Year	Payment budget [kCHF]	Commitments and Pipeline [kCHF]
2017	4888 to 4798 in Dec	5016
2018	4623 to 4453 in Dec	4808
2019	5506 to 4596 in Dec	4670
2020	4623 to 4621 in Dec	4972
2021	4451 to 4551 (DG funds)	4374
2022	4703 to 4126	4091







Update

Cost of MPA in 2021

Status on 12.12.2021 (reference CET using 'Account', incl. pipeline)



Total cost in OP: **382 kCHF**
 Ceiling: **400 kCHF**



update

Industrial support & FSU contracts

VSC coordinator of the IS contract: Jaime Perez Espinos

FSU and IS contract supervision and FSU coordinator: Nico Kos

Contracts close to retendering.

Status on 12.12.2022 (reference JMT+CET)

Contract	No. of jobs	Total (kCHF)
S175 (AL4030)*	364 (<i>CERN-wide: 900</i>)	455 (<i>CERN-wide: 1028</i>)
S144 – Cabling, bakeout and mechanical design	208	381
S145 – Machining, assembly, testing, logistics and mechanical design	144	422
Total	716	1258


*This includes the cost of jobs, as well as supervision, QA and logistics.

Industrial support: new contract in 2023

Vue générale des activités du consortium

■ Nombre total de lignes SP : 900

Moyenne H/ligne	12,7
Maintenance	6,8
Détection de fuite	10,5
Support indus	24,3
Intervention tunnel	35,3



Courtesy of AL-4030


12/12/2022

Réunion annuelle 2022

4

Répartition des activités sur le CERN


4 Principaux demandeurs



- 2022 : Toujours les mêmes principaux demandeurs,
- 2021 vs 2022 : Modification importante de la répartition des différents demandeurs.

Activités : Détection de fuites

Industrial support: new contract in 2023



- HL-LHC grand demandeur de test d'étanchéité
- Activités également sur l'ensemble des accélérateurs et projets.


12/12/2022

Réunion annuelle 2022

Courtesy of AL-4030 6


Maintenances réalisées en surface

Répartition par famille d'équipements



Part TE/VSC

VSC : 84%, Hors TE/VSC : 16%



TE/VSC : Travail important de maintenance préventive

12/12/2022

Réunion annuelle 2022


9

Courtesy of AL-4030

Industrial support: new contract in 2023

Maintenance : Dashboards détecteurs de fuites

Taux de réalisation : 98%
 2 Détecteurs non maintenus (non disponibles)




- Démarrage du plan de maintenance au mois d'avril,
- Démarrage de la maintenance des nouveaux détecteurs ASM340

12/12/2022

Réunion annuelle 2022

10


Maintenance des équipements Vide faisceau par année calendaire



- Modification des groupes HiPace 80 :
 - Toujours en stand by (pompes primaires pas encore livrées par le fournisseur),


Industrial support: new contract in 2023

Interventions tunnel



- Répartition des interventions tunnel :
 - Interventions spécifiques vide isolation
 - Consolidation des groupes de pompage vide isolation
 - Consolidation du SPS
 - Intervention Cps
 - Intervention secteur cavité RF

Courtesy of AL-4030



12/12/2022


Réunion annuelle 2022

25

Courtesy of AL-4030

Industrial support: new contract in 2023

Etat de la facturation



12/12/2022


Réunion annuelle 2022

27

Industrial support

For the IS contracts, we have two limits in 2022-23:

- Max in **OP** in the period 2022-2026: **737 kCHF.**
- Max **contract envelop** in 2022-2023: **1350 kCHF.**




Total annual commitment of S175 in 2022 (all groups) = 1028 kCHF


TE-VSC only annual commitment in 2022 in OP = **395 kCHF**

In VSC:


Contract	OP part
S175	87%
S144	43%
S145	31%



Forecast IS and FSU for TE-VSC



- Current IS support contract will end on 30 June 2023.
- Current FSU contract will end on 31 March 2024.



Direct request won't be considered by our contractors.

Blanket contracts



TE-VSC Blanket contracts


At present 8 blanket contracts running:

1. Supply of UHV all-metal valves with and without RF-contacts [3.758 MCHF]
2. Supply of Turbo-Molecular Vacuum Pump Packages [4.939 MCHF]
3. Supply of UHV right angle valves [1.153 MCHF]
4. Sputter ion pumps [3.5 MCHF]
5. Supply on non-evaporable getter pumps [2.184 MCHF]
6. Helium leak detectors [0.351 MCHF]
7. Overhaul of residual gas analysers [0.992 MCHF]
8. Dry pumps (High water vapour capacity) [0.75 MCHF]

2 New Blanket contracts being put in place:

- SMA rings [200 KCHF] → B1715 (not in CET yet)
- Dry primary pumps [550 KCHF] → Market Survey ongoing

Thanks Chiara for ensuring the contracts supervision



Status on 05.12.2022


B CONTRACTS OVERALL STATUS

	Description	Company	Start Date	End Date	Extension End Date
B1501	Metal gate valves	VAT	01.01.2017	31.12.2021	31.12.2024
B1502	UHV right angle valves	VAT	01.01.2017	31.12.2021	31.12.2024
B1510	Dry pumps	Swiss Vac Tech	01.03.2017	28.02.2022	28.02.2024
B1520	Turbo pumps	Pfeiffer	01.01.2018	31.12.2022	31.12.2024
B1457	Non Evaporable Getter Pumps	SAES	15.01.2016	14.01.2022	14.01.2023
B1646	Sputter Ion Pumps	Agilent	16.10.2020	15.10.2025	
B1589	Helium Leak Detectors	Pfeiffer	01.01.2019	31.12.2024	
B1392	Overhaul of Residual Gas Analysers	Pfeiffer	20.02.2014	31.12.2024	


→ Strategy under discussion with VAT

→ Extension asked, a new B contract will be needed to be put in place in the coming year


B1392 - Overhaul of residual gas analysers [kCHF] - Per year




B1392 - Overhaul of residual gas analysers [kCHF] - Cumulative




B1457 - Supply of Non-Evaporable Getter Pumps [kCHF] - Per Year




B1457 - Supply of Non-Evaporable Getter Pumps [kCHF] - Cumulative




B1646 - Supply of Sputter Ion Pumps [kCHF] - Per Year




B1646 - Supply of Sputter Ion Pumps [kCHF] - Cumulative











B1501 - Supply of UHV all-metal valves with and without RF-contacts [kCHF] - Per Year




B1501 - Supply of UHV all-metal valves with and without RF-contacts [kCHF] - Cumulative







Consolidation



Leonardo da Vinci, *Codex Atlanticus*, Biblioteca Ambrosiana, Milan, Italy

In addition to the operation budget, VSC submits funding requests for CONSOLIDATION of the existing accelerator complex.

CONS criteria = Safety conformance; Ensuring accelerator availability; End-of-life replacement; Spares; Equipment obsolescence; Achieving nominal performance.

LHC program - 1 consolidation packages

99712	VSC Prj: Acc Cons - LHC Turbo mobile pumping vacuum - P1
99716	VSC Prj: Acc Cons - LHC beam vacuum
99727	VSC Prj: Acc Cons - LHC Insulation Vacuum
99763	VSC Prj: Acc Cons - LHC bake out
99764	VSC Prj: Acc Cons - LHC Beam Vacuum instrumentation
99776	VSC Prj: Acc Cons - LHC Electron Cloud
99804	VSC Prj: Acc Cons - LHC MKB dilution kickers - Turbos
99810	VSC Prj: Acc Cons-Replacement BV mobile pumping groups-arcs
99829	VSC Prj: Cons X-ray Photoemission Spectroscope (XPS)
99893	VSC Prj: LS2 Consolidation of Vacuum Controls
99710	VSC Prj: Acc Cons - LHC Spares - Ins. vacuum turbos
99820	VSC Prj: Acc Cons - LHC spares - MBX chambers
99822	VSC Prj: Acc Cons - LHC spares - RT magnet chambers

Other programs - 10 consolidation packages (NA cons not included)

99741	VSC Prj: Acc Cons - PS
99824	VSC Prj: Isolde pumps & front-end consolidation
99827	VSC Prj: Acc Cons - consolidation of PS controls
99830	VSC Prj: Acc Cons - PS fixed pumping
99831	VSC Prj: Acc Cons - PS magnet consolidation
99828	VSC Prj: Acc Cons - consolidation of SPS controls
99840	VSC Prj: Acc Cons - SPS ion pumps
99841	VSC Prj: Acc Cons - SPS spares
99842	VSC Prj: SPS cons - Pumping Groups cons - inj & ext zone
62722	VSC Prj: Acc Cons - SPS & TD2


Approved in 2022:

Consolidation of LHC Turbo mobile pumping groups and pump out valves (insulation vacuum) (718 kCHF).

Two new consolidations programs proposed in 2022:


1. SPS Transfer Line Vacuum system consolidation : 862 kCHF
2. SPS Ring and Transfer Lines Valve consolidation : 560 kCHF

TE-VSC LHC consolidation budget (Status on 9.12.2022)



- **Total planned value: 630 kCHF**
- **Total commitment: 1367 kCHF**
- **Delays of big deliveries pushed the budget to 2023**
- Over several years, VSC has **consistently achieved** its CONS goals.
- As we compete with many Groups for limited CONS funds, **our continued efforts & results provide a solid basis** for further approval of essential VSC needs.
- In the future the focus should be put on matching the planned value with the charged budget → Advance your orders!!


TE-VSC **other consolidation** budgets (Status on 9.12.2022)



- **Total planned value: 677 kCHF**
- **Total commitment: 877 kCHF**

Status on 9.12.2022 (APT)

Evolution ACC CONS



Total amount of 8.9 MCHF


LHC – 4.6 MCHF

PS – 0.8 MCHF

SPS – 2.6 MCHF


PROJ: SPS-CONS, PS-CONS, ADCONS, LHC-SPARES, LHC-CONS, NA-CONS, EA-CONS, SPS-SPARES, PS-SPARES

New requests at Consolidation Day (October 2022) - summary

New request #	Short description	Material [kCHF]	M2P [KCHF]	Time frame	Priority
 VSC-1	SPS Transfer Line Vacuum systems consolidation Consolidation of ion pumps (reusing VPIAL from LEP), gauges, spare chambers and windows.	862	FSU: 0.6 Y's G/S: 0 Y's	2023-2027	1
VSC-2	SPS Ring and Transfer Lines Vacuum valve consolidation Consolidation of valve pneumatics (irradiation), old venting valves and VVRs in sectors 6001, 440 and 2002	560	FSU: 0.3 Y's G/S: 0 Y's	2023-2028	2

Proposed spending profile

0.9 MCHF already committed for 2023!
 2023: 2.1 MCHF available → 1.2 MCHF to charge during 2023 if all 2022 commitments are transformed in charged budget
 Advance 2024 commitments!





Purpose of HL-LHC

At present, **HL-LHC is the most important CERN's project**. Its objective is an **annual** LHC integrated luminosity of **250 fb⁻¹ in ATLAS and CMS** for 12 years of operation.


To achieve this ambitious goal:

- The LHC **injector chain** will be **upgraded**:
 - Bunch population from 1.15 to 2.2×10^{11} .
 - Emittance reduction from 3.4 to 2.0 μm at the SPS extraction.
- The beam optics in **IP1 and IP5** will be **improved**:
 - β^* reduction from 0.55 to 0.15 m.
 - Bunch rotation by crab cavities.

The new parameters coupled together imply, among other modifications, **larger aperture insertion magnets** (triplet magnets, D1, D2 and Q4, Q5 magnets) in P1 and P5.

The insertion magnets of P2 (ALICE) and P8 (LHCb) are not replaced nor modified.


Vincent Baglin & Giuseppe Bregliozzi: TE-VSC link and deputy link persons for the HL-LHC project



HL-LHC is divided into 19 Work Packages.

TE-VSC HL-LHC (all VSC)

2022 Budget



Crosstab Report


Report extracted on 08-Dec-2022 18:38

Rows: WBS from 0 to 1
Columns: Time from 0 to 0
Time: All
Category of Accounts: Materials (all) kCHF

Filters:
Org (Res) TE-VSC
Wbs CERN-PPA
Project (Res) HL
Workunit
Status PL, AC, CO
Show:
A
APT
Totals
Use Trend (All) for EVM projects

HL-LHC CONS Total amount of 10.9 MCHF

EVM Extraction in 08.12.2021



Main activities:

- LS2 : BS and LSS
- RUN3 and LS3: LSS

Crosstab Report

Report extracted on 08-Dec-2022 18:44

Rows: WBS from 0 to 1
Columns: Time from 0 to 0
Time: All
Category of Accounts: Materials (all) kCHF

Filters:
 Org (Res) TE-VSC
 Wbs CERN-PPA
 Project (Res) HL-C
 Workunit Status PL, AC, CO

Show:
 A APT
 Totals
 Use Trend (All) for EVM projects

What's the difference between ACC-CONS & HL-CONS ?

2022 Budget

TE-VSC submits funding requests for ACCelerator CONsolidation (ACC-CONS):

- Criteria: Safety conformance; availability; end-of-life replacement; spares; obsolescence; achieving nominal performance.
- Vision of the needs for all operational accelerators for at least the next 5 years.

To upgrade LHC to HL-LHC, some costs are taken outside of HL project and grouped as HL CONsolidation. So for TE-VSC we have 'HL-LHC WP12' & 'HL-LHC WP12 CONS', where the latter includes:



- Manpower to demount & remount existing vac equipment - eg due to civil engineering at IP1 & IP5 or equipment relocation,
- R2E infrastructure changes due to higher radiation doses – eg control rack displacements, cable routings,
- R2E infrastructure changes due to pressure measurement issues – eg VPI re-cabling at LSS3 collimators,
- Replacement of equipment that doesn't have the required capacity for HL needs – eg new PLC masters & slaves,
- Increase of beam vacuum instrumentation all around the ring for adequate monitoring during the HL era,
- Replacement of mobile equipment in readiness for heavy use during HL installation in LS3 – eg RGA & magic box,
- HL spares – eg vacuum chambers, interconnections, instrumentation.

Presently ACC-CONS and HL-CONS are separately managed within Accelerator & Technology Sector (ATS).

- On 7th Nov '18, TE-VSC were asked to review all the approved & pending activities,
- Goals: defend existing approved activities, identify possible cost savings, check which activities can be postponed & the impact, check & remove any double-counting, motivate the (financial) approval of pending items, submit new requests as required.
- Outcome: Some inconsistencies in the categorization of some ACC-CONS, HL-LHC & HL-LHC-CONS workunits. Several significant VSC cost savings were identified, allowing the approval of pending VSC requests.

Status on 12 Dec 2022 (EVM, baseline 6.1.0)

kCHF			
PV	EV	AC	BAC
23782	22612	23763	51304



Project: LRD-PRJ
 Workpackage: HLLHC 12
 Baseline: Baseline 6.1.0

12-Dec-2022 09:34


PV: Planned Value

EV: Earned Value (i.e. the value of completed work expressed in terms of budget assigned to that work)

AC: Actual Cost (i.e. the costs actually incurred and recorded in accomplishing the work performed)

BAC: Budget At Completion

HL-LHC WP12 personnel plan



HL-LHC: Cost and Schedule Review 2022



Space management and strategy

Meyrin site

SMA18

SMA18

B113

B30, 112, 376

B181

B252

B101

B153

B101

B169

B107

B118

B169

B107

B676

Vacuum & mechanics activities mostly in SMA18, 101, 113, 30, 112, 376
 Storage: 113, 169, 867 (RA components), SMA18
 Coating: 101, 252, 181
 Surface treatments, chemical analysis, large furnace: 107, 153, 118, 673, 10, (867)

Preveessin site

B867

B867

Restructuring of the welding workshop (b. 376)



TE-VSC's services


W. Kandinsky, *Farbstudie Quadrate*, 1913



TE-VSC services: 2022 summary updated on November 30th

Service	Number of jobs (all included)	Income [kCHF]
Surface treatment	1729	416
Surface treatment for ext. institutes	3	24
Chemical analysis	41	42
Thin film deposition	38	50
Large furnace	6	6
Total	1817	538


Surface treatments: 1639 jobs (status on 30.11.2022)




Invoiced jobs: **1227**
 Non-invoiced jobs: **412**

Last year the total number was 1710.


Surface treatments: 1639 jobs (status on 30.11.2022)



Surface treatments: 1639 jobs (status on 30.11.2022)





Surface treatments: 1639 jobs (status on 30.11.2022)




Total revenue expected at the end of the year: ≈ 440 kCHF

Last year: 410 kCHF

Surface treatments: 1639 jobs (status on 30.11.2022)




Surface treatments: 1639 jobs (status on 30.11.2022)




Acceptance tests: 121 tests (status 01.12.2022)

121 Tests completed in 2022: By machine/projects




Acceptance tests: 121 tests (status 01.12.2022)



121 Tests completed in 2022: By family of components



Acceptance tests: 121 tests (status 01.12.2022)




Non-conformities



Acceptance tests: 121 tests (status 01.12.2022)

Non-conformities



A selection of remarkable activities in 2022

Internal and CERN-wide services


Vacuum measurement service: Instrumentation laboratory

Repair & construction

- Complete set of insulating wire & connectors built by CERN



Insulating wires



Connectors

• Gauge design

- Study of the SVT 305 collector assembly






Fig. 3 – SVT gauge – connection between tungsten wire and anode.

- In collaboration with DLM and EN-MME

Vacuum measurement service: Instrumentation laboratory


Instrumentation manufacturing



Grid for coating : SMOG



Power supply gas analyzer




ESD BIG welding filament

Vacuum measurement service: Instrumentation laboratory


Vacuum and functional tests

- 9 repairs/maintenance
- 36 acceptance tests
- New RGAs evaluation



MKS Microvision 2 with degassed ion source

- MAST software evaluation
 - Dow corning grease recognition



- Next step: filling of database

Vacuum measurement service: Instrumentation laboratory

Mass spectrum analysis

Based on iterative deconvolution and machine learning

- Web interface developed in collaboration with IDAL, under test




Chemistry Laboratory

Corrosion issue of aluminium on MLI (LHCb SciFi cooling plant)

MLI corrosion after
Novec 649 leak



Courtesy : S. Jakobsen



**strong corrosion in contact with
Novec 649 + water (acid production)**

On going : Polymer and metal compatibility tests with different cooling fluids (Novec 649, NOVEC 7100 and C_6F_{14})

Chemistry Laboratory



Characterization of SnAg layer on Nb-Ti superconducting wires

HL-LHC production of SnAg coating:

- electroplating specifications:
 - ✓ Composition SnAg 5%wt.
 - ✓ Thickness: 0,5 mm



Rutherford cable coated with SnAg



Courtesy EN-MME

ICP-OES analysis of SnAg coating: Composition and thickness

- Since 2019: qualification of companies (IT4703) ~100 analysis
- Now: **quality control** of the production ~ 50 analysis planned for December 2022



Acidic solution etching of SnAg coating





ICP-OES (Agilent 5110)


Surface finishing

Wet surface treatments: copper plating of large components

- Finished the plating of a series of 5 RFQ tanks for SPES accelerator at INFN Legnaro
- Developing a new facility for plating by fluid circulation at bldg 107 for **long chambers** (up to 5m) to get more flexibility for CERN vacuum chambers production




Surface finishing



Cu plated tube for CRAB coupler




Copper plated flange before Nb coating



RF contacts inner CRAB line (copper plating on stainless steel)



Surface finishing



Gold and copper plating steps of LHC BPMs

Surface finishing




Gold plating of Kovar edge of the glass assembly for the FLOTUS experiment (CLOUD)





Surface finishing

Wet surface treatments: special copper plating...on polymers

- Application: Mock-up of HOM couplers for PERLE. For low power RF testing and design validation
- with EN-MME, TE-MSL polymer lab, EP-DT
- 3D printing in Accura polymer + 30 um copper (inside) plating on a pre-layer of chemical carbon based conductor (commercial)
- complex configuration of electrodes to get a good thickness distribution



Acceptance tests Lab 101



Acceptance tests: Material validation for prototype double beam collimator for HL-LHC

CuCD jaw blocks for TCTPXH





Hydroformed belows




Acceptance tests: sub-assemblies validation for prototype double beam collimator for HL-LHC

TCLPX jaws



Acceptance tests: Sub-assembly UHV validation for TCPC collimator at YETS 22-23


Crystal inside holder




Edge welded bellows for motorisation




Acceptance tests: Final vacuum acceptance test of TCPC collimators




Bakeout: Example of activities






ADT Transverse Kicker Bake-out Installation – B.113



BSRTMB Bake-out Installation – B.113




Outgassing measurements: Polymeric LCP for BGI





Mechanical design: QCF CHAIN CLAMP


3D models



DN300




DN250




DN200

Mechanical design: Trolley for operation


3D models and manufacturing



JOB 1012





JOB 983




JOB 1020





Mechanical design Examples




Consolidation of vacuum chambers BHZ378 and BHZ377 in TT2 (F16) beam line





Design of autoregulated bake-out jacket for UHV test collimation at LS3 (HL)





New Plasma support system



Dismountable QPR sample + flange drawing




Vacuum chambers for ion gun setup





PSBooster



Mechanical design Examples




Chamber cut + flanges for PS magnet leak




Cadre machining of the stiffener 2M



HRM SMAUG experiment



Design of 2 vacuum transitions (VCT) and one vacuum chamber (VCD)



New VCPMC for Magic boxes

Accelerator operation


Injectors and experimental areas

LHC injectors 2022 performance

Excellent availability, but still some faults:

- ❑ LINAC4: Valves closed due to RF spark (child of another fault)
- ❑ PSB: Leak due to faulty RF bypass (spark)
- ❑ PS: One solenoid valve burnt in TT2 sector valve
- ❑ SPS: TBIU beam strike and BA5 collar mechanical failure

No systematic failure. Most of the failures linked to non VSC origin




LHC injectors 2022 performance

Excellent availability, but still some faults:


- ❑ AD/ELENA: Failure PLC communication module
- ❑ ISOLDE: Failure TPG controller. Target leak (no VSC origin)

No systematic failure. Most of the failures linked to non VSC origin

PUMA received beam for first time!




Injectors and EA: Some issues




YETS: water leak brazing BSW in PSB

Solidified oil of REX primary pump




C:\Bruker\DATA\2022\Pump oil\pump oil hexane.0	DTGS	11.03.2022
C:\Bruker\DATA\2022\Pump oil\pump oil CHCl3.0	DTGS	11.03.2022
C:\Bruker\DATA\2022\Pump oil\mineral oil new.0	DTGS	11.03.2022





ELENA: Leakage current of penning gauges due to humidity



Spark PSB seal (faulty RF bypass)



Interventions in PS complex



Linac4 Controls upgrade

New pumping groups control

- Test, Installation and commissioning of 14 VPG controls
- Power network modification
- VacBD and SCADA update



Homogenization of Interlock system

- Replacement the LHC logic interlock by cPS logic
- New cabling for interlocks sources



VPI control upgrade

- Replacement of old VPI controllers for new Agilent
- New Profibus network
- Test and commissioning



De-cabling and cabling

BA1

Cables identification

HV lock-out




VPI controllers in local during de-cabling campaign

LINAC3 and LEIR

Unscheduled campaign

New 3 Phase distribution

VPI controllers in local during de-cabling campaign



Linac3 de-cabling and 3Phase


Grand Four

New cabling due to gauge measurement issues

Test and commissioning

Electro beam test stand

Cabling for a VPS and a Valve, test and commissioning





Grand Four

ELENA

- 8 working experiments
- New WIC interlocks installed and tested
- LNE51 (**PUMA**) line commissioned
 - Local controls rack and cabling provided to operate the vacuum line of the PUMA experiment




Local vacuum controls rack



AD area

AD/ELENA


- Racks cabling re-routing
- UPS powered racks
- IP3/2 compliant racks/crates



Rack cabling re-routing, door can be closed now





UPS powered racks



IP2/3 compliant racks – Plexiglass covers to see the PLCs




ISOLDE complex



- New **temperature measurement** for faraday cage and turbo-pumps in front-ends **HRS & GPS**
- New **fans and control system** to cool down the turbo-pumps in front-ends HRS & GPS

ISOLDE complex



- Replacement of **3x cryo-pumps** by **3x turbo-molecular pumps** in RFQ and 7-9GAP sector of REX-ISOLDE

Climatic Chamber Tests


EXCAL machine tests for temperature and humidity effect on Penning gauge measurement



EXCAL climatic machine



Penning setup








Temperature and humidity effects on VGP readout

SPS Operation

Excellent availability all along the year!

Main vacuum faults


- ❑ T2 TBIU beam strike: **140h** of downtime (high radiation area no direct access). No impact to the SPS and LHC operation
- ❑ BA5: Collar failure with 5 sectors vented. Just **19 h** to restart physic.
- ❑ BA2 Failure of 2 interlock cards (**2 h** of downtime).





SPS High Intensity vacuum limitations

8b4e & batch spacing: sparks upstream the **800MHz cavity** depending on batch spacing → **limiting beam delivery to LHC next year**. Endoscopy foreseen in YETS.

Dumping Kickers: MKDV/H **spurious sparks at LHC-25ns high intensities**. No action during YETS on VSC side.




SPS CRAB Cavities 2022 Operations





- ❑ For the first time the crab cavities have been scrubbed at 2K with high intensity beam (LHC-25nd at 450GeV, $1,6 \cdot 10^{11}$ ppb);
- ❑ Minor heat load deposited on the cavities;
- ❑ Slower conditioning than expected wrt SEY and ESD experimental data.

SPS: issues during 2022 run

TBIU beam strike



Collar failure in BA5 → 5 sectors vented




15.12.2022

Paolo Chiggato | TE-VSC 2022 plenary presentation

153

SPS YETS 22/23 Activities





YETS schedule for the SPS, with the following main activities:

- MKE4 sectorization;
- MPKIV exchange (current intensity limitation in the SPS);
- 800MHZ endoscopy, 300MHz Cavity 5 leak detection;
- T4 reconfiguration in TDC2;
- Ion pumps consolidation, magnet campaign, aperture restrictions investigations, wire scanner exchange.

LHC operation

LHC Operation




LHC Operation

Short-term analysis

- Works with **time windows** and a **range of fills**
- **Large choice of variable types:**
 - Pressure
 - Temperature
 - Heat Load
 - Beam Parameters
 - More are added on a regular basis!
- **Plot fully customisable**
 - X axis
 - Y axis
 - Logarithmic scale
 - Beam intensity and Energy filters
 - Gauges organisation
 - Legends, colours, etc...

Fill 8293: 2022-10-19 13:26:00 - 2022-10-19 16:32:00


Filling scheme not available for this fill



LHC OPERATION

Long-term analysis

- Works with a **time window**, a **range of fills**
- **Possibility to choose the instant we are interested in:**
 - Maximum intensity, stable beam, static pressure, etc...
 - Any other requirement is also possible
- **As before, large choice of variable types**
 - Allows beam vacuum performance analysis with beam parameters, heat loads, temperature, etc...
- **Plot fully customisable**
 - The same as before + trend lines



Pressure values at stable beam


LHC SCRUBBING RUN Baked Sectors Overview

Pressure at Maximum
Beam Intensity (VGI)

Conditioning effect visible in all
room temperature sectors


Pressure measurements scattered
through 3 orders of magnitude:

- Vacuum sector history dependence
- Different systems, sector lengths, effective pumping speeds





LHC SCRUBBING RUN

History Dependence in Baked Sectors




- Pressure
- Never Vented
 - LS1 - Vented with N2
 - LS2 - Vented with Air
 - LS2 - Vented with N2
 - NEG Only




Vacuum performance analysis must consider sector history:

- Pressure measurements spanning 2 orders of magnitude.
- Differences between LS1 and sectors that were never vented are still seen.
- In some locations we are at the multipacting threshold for this intensity/energy.

LHC SCRUBBING RUN TCLD Collimators




First room temperature sector in LHC ARCs




Factor 20 decrease of pressure at maximum intensity, down to low 10^{-8} mbar.


- Completely un-scrubbed surface: known initial surface state
- Possible to estimate ESD and SEY from:
 - Experimental conditioning curves.
 - TCLD pressure evolution




LHC SCRUBBING RUN Experimental Areas



- **Conditioning observed in ATLAS and LHCb**
- **In CMS and ALICE:**
 - No visible multipacting if the solenoid is ON
 - Pressure readings affected by magnetic fields



LHC YETS 22-23: Overview of Activities






Where	Sector	Activity	NEG activation
LSS6	MKB	Upgrade with NEG cartridges	N
LSS4	E5R4.B	BWS Maintenance	Y
	E5R4.R	BSRTM mirror exchange	Y
	E5L4.R	Pressure spikes (tbc)	Y
	C5L4.B	BGC installation	N
LSS7	A4L7.B	TCPCH.A4L7.B1 Exchange	Y
	A5R7.R	TCPCH.A5R7.B2 Exchange	Y
	A4R7.R	Sector valve exchange	Y
LSS8	E5R8.R-B	MKI Cool Installation	Y
	G5R8.R-B	MKI Cool Installation	Y
	A4L8.C	Leak on a TCTPV	Y
-	-	Sector valve consolidation in high radiation area	N


Resistive Magnets consolidation

10 over 15 MSD spare magnets (LSS6 Ejection dump septum) equipped

with racetrack and circular chambers





Installation of New Titanium LHC Dump Windows



- Double windows design:
 - A Ti window in sandwich between 2 C/C disks. (vacuum side).
 - A second robust window downstream (vacuum/atm).
- First use of SMA coupling in accelerators. Implementation of a DN25 Steel-Titanium joint for LHC dump window

Installation of New Titanium LHC Dump Windows


Implementation of a DN25 Steel-Titanium joint for LHC dump window





SMA joint (Ti-St transition)

Conflat St flange (to connect pump/gages)

Ti window



TCPC Crystal Goniometer installation in LSS7



LHC YETS 21/22 - Vacuum Pilot Sector NEG consolidation

- **Controls:**



- Procurement & production
- Cables & interconnection boxes production

- **SCADA integration:**

- Vacuum Database
- Manual modification of SCADA

- **Installation:**

- Rack installation
- Tunnel installation
- Hardware tests & commissioning



LHC YETS 21/22 - LHC Machine Checkout

Automatic test script of Vacuum Sector Valves & interlocks

- Reduces significantly the time to verify interlocks integrity
- Detection of interlock cabling and setting issues
- Number of equipment tested
 - Interlock Valves: ~300
 - Vacuum Gauges: ~680
 - Vacuum Pumps: ~820

ValveTestExecution

Valve	Step
VVGST.367.5L6.B	FINISHED
VVGSH.367.5L6.R	FINISHED
VVGST.291.5L6.B	FINISHED
VVGSH.291.5L6.R	FINISHED
VVGST.197.5L6.B	FINISHED
VVGST.104.5L6.B	FINISHED
VVGST.3.5L6.B	FINISHED
VVGSH.3.5L6.R	FINISHED
VVGST.1677.4L6.B	FINISHED
VVGSH.1677.4L6.R	FINISHED
VVGSV.526.4L6.B	FINISHED
VVGSW.1029.4L6.R	FINISHED
VVGSW.1029.4R6.B	FINISHED
VVGSW.682981.B	FINISHED
VVGSV.526.4R6.R	FINISHED
VVGSW.622981.R	FINISHED
VVGST.1683.4R6.B	FINISHED
VVGSH.1683.4R6.R	FINISHED
VVGSH.3.5R6.B	FINISHED
VVGST.3.5R6.R	FINISHED
VVGSH.291.5R6.B	FINISHED
VVGST.98.5R6.R	FINISHED
VVGST.291.5R6.R	FINISHED
VVGST.367.5R6.B	FINISHED
VVGSH.367.5R6.R	FINISHED

Check:
 Step by step
 Stop on error
 Beam Permit
 Vacuum Permit
 Laser Alarms

Start #1 Start #2 Log 1 LASER
Pause Continue Cancel Skip Wait For Valve Log All Close

MPP Vacuum tests and LHC checkout tracking with OP




LHC YETS 22/23 – P6 Controls Consolidation

Consolidation of Ion Pump Controllers



- Racks and PLC/SCADA documentation
- Cabling and material preparation
- Consolidation during YETS 22/23

MKB fast interlocks acquisition PLC

- Electrical schematic design
- Production of crates and cabling
- Installation during YETS 22/23




UA63 MKB racks distribution



MKB fast acquisition interlocks reading PLC crates


LHC beam-screen surface evolution (Heat Load Task Force)

Measure XPS and irradiation at 15K of sample exposed to humidity ($\text{Cu}(\text{OH})_2$)




Plausible path to **explain CuO presence**

Working to get rid of CuO... various principles work



Integration in-situ with limits of treatment time, temperature, gas safety reliability etc....going **towards plasma based system** progress.

LHC Experiments



ATLAS experimental beam vacuum IP1.X

New Small Wheel – side C (nSW-C) installed by end of 2021

- TE-VSC removed the vacuum layout for the LHC special run (2021) in ≈ 3 days.
- Installation of the operational layout by January 2022.



Installation of the VT and VJ aluminum chambers

ATLAS experimental beam vacuum IP1.X

Bake-out & NEG activation of the IP1.X performed by February 2022.

ATLAS tracker stays in place (including pixel detector).

- Complex DSS protection matrix put in place by ATLAS.
- **8 days process** (ATLAS running non-stop shifts).

18 m of IP1.X under active cooling


We are basically baking a fridge without melting the ice-cream inside 😊



Overheating may cause permanent damage of the tracker.

CHAN	PV	SP	St	A	Prog	M/A	CTRL	PV	Target
01	-13.4°C	Error	6	Y	1	M	25	999.9°C	
02	-12.3°C	Error	6	Y	1	M	26	999.9°C	
03	-12.1°C	Error	6	Y	1	M	27	999.9°C	
04	27.8°C	Error	6	Y	1	M	28	999.9°C	
05	27.2°C	Error	6	Y	7	M	29	999.9°C	
06	28.7°C	Error	6	Y	10	M	30	999.9°C	
07	25.9°C	Error	6	Y	10	M	31	999.9°C	
08	23.4°C	Error	6	Y	10	M	32	999.9°C	
09	22.1°C	Error	6	Y	7	M			
10	21.0°C	Error	6	N	0	M			
11	22.0°C	Error	6	Y	10	M			
12	29.7°C	Error	6	Y	10	M			



ATLAS experimental beam vacuum IP1.X






CMS experimental beam vacuum IP5.X

IP5.X vacuum sector recommissioned (installation, bake-out & NEG activation) by May 2021.

CMS required special opening to investigate post-SR2021 observations by beginning 2022.



Opening of the YB+2 central segment during LS2

CMS experimental beam vacuum IP5.X

Experiment reclosed for Run 2022 by March 2022.


Standard heavy involvement of TE-VSC team on site.



Final alignments prior the Run 3




ALICE



ALICE experimental beam vacuum IP2.X

Mechanical support for additional activities with central region (new tracker tested during the special run 2022).




Central chamber upstream of the IP2 – carbon “trampoline” zone

ALICE experimental beam vacuum IP2.X


- New central beryllium chamber, new FoCal (Forward calorimeter) chamber.
- Main changes in vacuum layout of IP2.X (merge with upstream sector).

The most complex beryllium chamber we ever build



Length 5658mm (5000 in Beryllium), ID_{min} 32mm
Double aluminum bellow assembly
500 μm beryllium thick central segment



Forward Calorimeter (FoCal-E; FoCal-H)



LHCb VELO & SMOG2 Control System



Implementation and deployment of SMOG2 Control System (integrated into VELO)

Extensively validated and calibrated during 2022
Several modification requests after one year of tests
Injection control to be transferred to LHCb during 2023

LHCb experimental beam vacuum IP8.X

VELO detector (C – side) installed 02-2022.

VELO detector (A – side) installed 05-2022 (from Ne venting to pump-down <24h).



Installation of the VELO A-side



LHCb experimental beam vacuum IP8.X

SMOG & GFS system installed in March 2022.

- *SMOG – System for measuring overlap with gas; GFS – Gas Feeding System (SMOG injection platform)*

System allows injection of 4 different gases (He, Ne, Ar, H₂).

Two injection modes (VELO vessel – SMOG 1, Storage cell – SMOG 2).




SMOG2 storage cell,
Gas Feeding
System (UX85 table)

LHCb experimental beam vacuum IP8.X

Intensive testing performed during 2022 (SMOG 1-2, different gases).

Injection without beam; with beam – VELO open; with beam VELO closed.




Molflow simulation of SMOG2 injection

LHCb experimental beam vacuum IP8.X



Hydrogen injection simulations for SMOG2

- Iterative simulations made using the Molflow+ CLI interface.
- Calculation of the progressive degradation of the sticking factor of the NEG coating during hydrogen injection.

Variations in the IP8 gas target profile



Evolution of H2 sticking factor in IP8






LHCb experimental beam vacuum IP8.X

NEG embrittlement studies for SMOG II

High pressure experiment


Low pressure experiment



LHCb experimental beam vacuum IP8.X


TE-VSC Support to the LHCb during 2022

Injections in both SMOG 1 & 2 regimes for VdM Scans (for all experiments)



LHCb is the world first experiment taking data simultaneously in beam/beam & beam/gas regime

The second interaction point provided by TE-VSC ☺



SMOG2 Argon injection as seen by VELO and Machine


HL-LHC: some remarkable results

Layout DB and 3D layout

Finalize data changes after LS2 and for YETS 2021-22

Finalize the HL-LHC v1.6 layout and continue studies in v1.7 for LSS 5R

Work in progress for LS3 de-installation and re-installation for LHC-LSS 1 and 5



> VCBQQDDA.D4R5.X	VCBQQDDA.252.4R...	13425.2456 13431.1456	5.9	S	22.207	U	0	V	0
IP 95.804				B	0	A	0	C	0
▼ VAMCAGAI.4R5.X	VAMCAGAI.283.4R...	13431.1456 13431.5456	0.4	S	28.107	U	0	V	0
IP 101.704				B	0	A	0	C	0
▼ VMBQQDDG.C4R5.X	VMBQQDDG.283.4...	13431.1456 13431.5456	0.4	S	0	U	0	V	0
IP 101.704				B	0	A	0	C	0
▼ VPIB.C4R5.X	VPIB.282.4R5.X	13431.2706 13431.2706	0	S	0.125	U	0	V	0
IP 101.829				B	0	A	0	C	0
▼ VAZAE.4R5.X	VAZAE.282.4R5.X	13431.2706 13431.2706	0	S	0.125	U	0	V	0
IP 101.829				B	0	A	0	C	0
▼ VGIA.C4R5.X	VGIA.282.4R5.X	13431.2706 13431.2706	0	S	0	U	0	V	0
IP 101.829				B	0	A	0	C	0
> VCBQQDDA.E4R5.X	VCBQQDDA.315.4R...	13431.5456 13437.4456	5.9	S	28.507	U	0	V	0
IP 102.104				B	0	A	0	C	0

VAMCAGAI.4R5.X ID 56775021

Vacuum - Assembly - Module - Circular - Circular - VMBQQDDG400
with -,VGI,-,VPI
H > S56 > LSSR5 > 4R5

Type

HCVAMCAGAI001 ID 56772096 Vacuum Assembly Module

Description

Vacuum - Assembly - Module - Circular - Circular - VMBQQDDG400 with -,VGI,-,VPI

Dimensions

width: 0.4


Warm Module

VMBQQDDG.C4R5.X

Circular - NEG coated - 212.7 - 212.7 - CF250 - CF250 - Port b and d
H > S56 > LSSR5 > 4R5 > VAMCAGAI.4R5.X


Layout DB and 3D layout

Layout DB data are used by the optics to check the aperture for the future: LSS 5R for LS3





Pressure profile of LSS1 and LSS5 of HL-LHC

- Simulation of the pressure in the LSS1 and LSS5 with the new HL-LHC layout
- Different scenarios simulated, from the machine startup to the end of the Run 4
- Similar profiles in both LSS, with small differences at the IP due to the different apertures





Other vacuum simulations for LSS1 and LSS5

- LSS1 and LSS5 SR simulations
 - Include actual PSD gas load in vacuum simulations









- Support to the routing of the pumping lines of the VAX
 - Guarantee adequate pumping speed of the IP sector



Other vacuum simulations for LSS1 and LSS5


- Optimization of the VAX-TAXS area
 - Improve reliability, performance and access to the area

- Support to the ATLAS vacuum system upgrade
 - Assess the effects of the experimental vacuum upgrade







ANSYS simulations and metrology of QCF chain clamps



Stress/Strain analysis of different QCF chain clamp designs using FEM




Design proposal for manual chain assembly for ISO standard chain.





3D scan of chain parts to verify tolerances





DRF assembly tooling



Deformable RF Fingers DN150 Assembly Test




Module Length




- Spring Compression 1st set
- Spring Extension 1st set
- Spring Compression 2nd set
- Spring Extension 2nd set

Tooling and QCF chain clamp validation



Torque Multiplier Test



Tightening tool





Ingersoll Rand QXX programmable tool

CERNBot - Robot






Programmable torque, angle, speed etc. through cable or Wi-Fi


Seal and chain installation test



Design and testing of new vacuum support for HL-LHC



HL-LHC criteria: All vacuum supports shall be designed to have atmospheric pressure on one side and vacuum on the other.





ANSYS simulation: total deformation of support




Deformation testing of vacuum supports in B113


HL-LHC cold vacuum system development




3D update of the interconnections



Drawings for fabrication of the interconnection components




3D update of the triplet pumping line




Update of thermal simulations


HL-LHC cold vacuum system development




Integration of the cold/warm transition







Integration of the beam vacuum line in the cryomagnet



Integration of the mobile point support




Inlet/outlet of the helium beam screen cooling circuit



Supports of the beam screen mobile point



HL-LHC cold vacuum system development



Cooling tube bending machine for D2






Model of the D2 exit tubes



Cooling tube bending machine for Q1

HL-LHC cold vacuum system development



Fixed point pre-assembly mock-up and BPM assembly test




Model of the beam screen for cold leak/pressure test

HL-LHC cold vacuum system development




Digital
Image
Correlation



Orbital
welding head


Stochastic
painting

Preliminary tests of welding induced deformation





Preliminary results of deformation after welding

Surface: Displacement magnitude (mm) Surface: gpeval(4,shell.disp) (mm)




Deformation due to gravity



HL-LHC cold vacuum system development




Update of the metrology bench



Model and fabrication of the supports




Model and fabrication of the adjustable movable supports





Model and fabrication of the insertion bench

HL-LHC cold vacuum system procurement




Reception of machined parts for the interconnections

Bellows supplier qualification



Completion of pumping slot shields



Analysis of as-built Ti springs

Rework of Ti compression rings

Reception of tungsten absorbers


Leak test tooling for series bellows

HL-LHC cold vacuum system procurement


Thermal link production: change from ultrasound welding to brazing



Ultrasound welding



Thermal link brazing on the tungsten absorbers



Assessment of brazing quality for different process configurations

HL-LHC cold vacuum system manufacturing



Production of thermal links for the beam screen absorbers

Production of thermal links for the interconnection absorbers

HL-LHC cold vacuum system manufacturing

Beam Screen Tube Manufacturing

Series production of the beam screen tubes:





Levelling of the sheets in industry, completed



Machining to width and length, completed




Copper removal at the edges, completed




Punching of the strips in industry, completed



Forming of the half shells, completed



Micro-TIG tack welding, completed




Micro-TIG tack welding


HL-LHC cold vacuum system manufacturing

Beam Screen Tube Manufacturing

Series production of the beam screen tubes:




Longitudinal welding, ongoing



Metallography for butt weld qualification



Longitudinal welding tooling




Longitudinal weld brushing



Calibration of the beam screen segments



Cutting to length of the beam screen segments




Butt welding of the beam screen segments



HL-LHC cold vacuum system manufacturing

Beam Screen Pre-Assembly Manufacturing


Preseries production of the beam screen pre-assemblies:



Laser welding bench for the cooling tube welding, completed



Metallography for the cooling tube weld qualification



Welding of the contact rings, cooling tube supports and fixed points, completed



Pre-series completed



HL-LHC cold vacuum system manufacturing

Beam Screen Pre-Assembly Manufacturing




Completion of the dedicated bench for the stud welding of the absorber pin supports

Stud welding on Q2 pre-series




Tooling for stud welding quality check




Metallography for stud weld qualification

HL-LHC cold vacuum system manufacturing

Dummy Beam Screen Assembly



Preparation of the bench and tooling for the beam screen assembly



Dummy beam screen assembly

HL-LHC cold vacuum system integration


Dummy Beam Screen Insertion



Preparation of the springs with ceramic balls



Transfer from the assembly to the insertion bench




Insertion of the dummy beam screen in the interconnection mock-up


HL-LHC cold vacuum system integration

Beam Screen Assembly


Bench for the thermal link welding on the cooling tubes:




Commissioning of the laser welding robot




Clamp manufacturing





Beam screen assembly before laser weld



Commissioning of the laser bench with welding robot



Welds between the cooling tube and the interface plate





Metallography for the thermal link weld qualification


HL-LHC cold vacuum system integration

Beam Screen Assembly

Assessment of a potential non-conformity for the thermal link welding on the cooling tubes:



Tomography of interface plate weld with defects done on purpose



Sample and pressure cycling test set-up



Pressure cycling at room temperature and 77K
(3000 + 3000 cycles without sign of leak)

HL-LHC cold vacuum system integration

Beam Screen Facility



Stud welding



Tack welding of beam screen tube segments



Storage of segments and beam screen tubes




Metrology/calibration



Class 4 laser facility with laser machine and bench



aC coating



Cold leak/pressure test



Assembly



Insertion



Movable adjustable support



Lifting beam



Pressure test of cooling tubes



Cleaning facility by circulation

HL-LHC cold vacuum system quality assurance

WP12-WP4 UHV Bellows MTF Structure

EDMS Home Favourites Inbox Caddie

Navigator

No active tags.

- Vacuum (WP12)
 - Management
 - Links for the Collaborations WP12
 - Minutes and Reports
 - Presentations
 - Scientific Documents via CDS
 - ECRs - Engineering Change Request WP12
 - Hardware Baseline Nodes
 - Engineering
 - V - Vacuum Components
 - VSM - Shielded Beam Screen
 - VSC - Non-shielded Beam Screen
 - Beam Screen
 - CWTs & ICs
 - Other Vacuum Components
 - Production HL-LHC Formed vacuum bellows
 - Design File
 - Bellows for WP12
 - Bellows for WP4
 - 2753845 (v.0.1) BOM UHV Bellows
 - Manufacturing Records
 - Bellows for WP12 - Manufacturing Records
 - Bellows for WP4 - Manufacturing Records
 - Retraction tooling for WP5

Production HL-LHC Formed vacuum bellows

- Design File
 - Bellows for WP12
 - HCVBU__223 (v.0) PUMPING LINE BELLOWS ASSEMBLY ID56.3/OD84
 - HCVBUTPA001 (v.0) HL-LHC PLUG IN MODULE BELLOWS
 - HCVBUTIA001 (v.0) BEAM SCREEN BELLOWS ASSEMBLY FOR IT
 - HCVBUTCA004 (v.0) OUTER BELLOWS SET CWT Q1
 - HCVBUTCA007 (v.0) INNER BELLOWS SET CWT Q1
 - HCVBUTCB001 (v.0) D1 COLD WARM TRANSITION BELLOWS
 - HCVBUTCC001 (v.0) D2 COLD WARM TRANSITION BELLOWS
 - HCVBUTIB001 (v.0) BEAM SCREEN BELLOWS ASSEMBLY D2
 - Bellows for WP4
 - HCVBUCIA010 (v.0) INTER BEAM SCREEN BELLOWS
 - HCVBUCCA010 (v.0) COLD/WARM TRANSITION BELLOWS
 - HCVBUCIB006 (v.0) INTERCAVITIES BELLOWS
 - HCVBUCBA013 (v.0) BEAM SCREEN BELLOWS
 - 2753845 (v.0.1) BOM UHV Bellows
- Manufacturing Records
 - Bellows for WP12 - Manufacturing Records
 - HCVBU__223 PUMPING LINE BELLOWS ASSEMBLY ID56.3/OD84
 - HCVBUTPA001 HL-LHC PLUG IN MODULE BELLOWS
 - HCVBUTIA001 BEAM SCREEN BELLOWS ASSEMBLY FOR IT
 - HCVBUTCA004 OUTER BELLOWS SET CWT Q1
 - HCVBUTCA007 INNER BELLOWS SET CWT Q1
 - HCVBUTCB001 D1 COLD WARM TRANSITION BELLOWS
 - HCVBUTCC001 D2 COLD WARM TRANSITION BELLOWS
 - HCVBUTIB001 BEAM SCREEN BELLOWS ASSEMBLY D2
 - Bellows for WP4 - Manufacturing Records
 - HCVBUCIA010 INTER BEAM SCREEN BELLOWS
 - HCVBUCCA010 COLD/WARM TRANSITION BELLOWS
 - HCVBUCIB006 INTERCAVITIES BELLOWS
 - HCVBUCBA013 BEAM SCREEN BELLOWS

Items

Assets

Bellows for WP12 - Manufacturing Records

- HCVBU__223 PUMPING LINE BELLOWS ASSEMBLY ID56.3/OD84
- HCVBUTPA001 HL-LHC PLUG IN MODULE BELLOWS
 - HCVBUTPA001-OD000001 - HL-LHC PLUG IN MODULE BELLOWS PRESERIES
 - HCVBUTPA001-OD000002 - HL-LHC PLUG IN MODULE BELLOWS PRESERIES
 - HCVBUTPA001-OD000003 - HL-LHC PLUG IN MODULE BELLOWS PRESERIES
 - HCVBUTPA001-OD000004 - HL-LHC PLUG IN MODULE BELLOWS
 - HCVBUTPA001-OD000005 - HL-LHC PLUG IN MODULE BELLOWS
 - HCVBUTPA001-OD000006 - HL-LHC PLUG IN MODULE BELLOWS
 - HCVBUTPA001-OD000007 - HL-LHC PLUG IN MODULE BELLOWS
 - HCVBUTPA001-OD000008 - HL-LHC PLUG IN MODULE BELLOWS

HL-LHC cold vacuum system quality assurance

Beam Screens EDMS-MTF Structure

- Management
 - Links for the Collaborations WP12
 - Minutes and Reports
 - Presentations
 - Scientific Documents via CDS
 - ECRs - Engineering Change Request WP12
 - Hardware Baseline Nodes
 - Engineering
 - Fabrication, Assembly and Verification
 - V - Vacuum Components
 - VSM - Shielded Beam Screen
 - Manufacturing procedures
 - Inspection & test procedures
 - Qualifications
 - Manufacturing records
 - Beam Screens
 - Beam Screen Assembly Before Insertion
 - Beam Screen Tubes
 - Beam Screen segments
 - Beam Screen segments w/o slots
 - Tungsten Shielding and Extremities/Interconnections
 - Beam Screens Cooling Tubes
 - Co-laminated Strips for BS
 - Pumping Slot Shield
 - HCVS__002-X1000001 - HL-LHC Beam Screen cooling tube Ø10
 - HCVS__002-X1000002 - HL-LHC Beam Screen cooling tube Ø10
 - HCVSMSC001-F2000001 - HL-LHC Cold Bore Type Q1/Q3
 - HCVSMSC001-F2000002 - HL-LHC Cold Bore Type Q1/Q3
 - HCVSMSC001-F2000003 - HL-LHC Cold Bore Type Q1/Q3
 - HCVSMSC001-F2000004 - HL-LHC Cold Bore Type Q1/Q3
 - HCVSMSC001-F2000005 - HL-LHC Cold Bore Type Q1/Q3
 - HCVSMSC001-F2000006 - HL-LHC Cold Bore Type Q1/Q3
 - HCVSMSC001-F2000007 - HL-LHC Cold Bore Type Q1/Q3
 - HCVSMSC001-F2000008 - HL-LHC Cold Bore Type Q1/Q3

Tungsten Absorbers

- MTF

Equipment Identifier: HCVSMLS002-MZ000455
Other Identifier: None
Description: TUNGSTEN SHIELDING [6mm]

Main Made of Equipment data **Manufacturing** Operation Documents History Map

Actions: **Add extra step**


Workflow Diagram
No workflow diagram is defined for this equipment

Workflow Steps

Step ID	R/E	Other name	Description	Status	Result	NC	Last Repeated
<u>10</u>		()	Certificate of Conformity	Done	Ok		
<u>20</u>		()	Cleaning at CERN (*)	Done	Ok		
<u>30</u>		()	Vacuum testing	Done	Ok		

- Delivery


Quantity delivered by 12/2022: 1383 parts



In work: Interconnections EDMS/MTF Structure BOM -> Done

HL-LHC VAX area design


ATLAS and CMS layouts




HL-LHC VAX area design

Module design


Module 1



Module 2




Module 3




HL-LHC VAX area design

Simplification and update of technical design




HL-LHC VAX area design

Simplification and update of technical design



HL-LHC VAX area design




Simplification and update of technical design



Q1 – TAXS module: evolutions 2022. Use of NEG SAES wafers. Integration details under discussion

HL-LHC VAX area design




Compensation system study



FEM analysis UEJ bellow and Q1-TAXS double bellow system.

HL-LHC VAX area design


Integration study




Integration of new Q1-TAXS model

HL-LHC VAX area design


Module prototyping



Reception and assembly of vacuum parts for final proto M1 and M3




Assembly of M1 proto – final version. New valve supporting system.



HL-LHC VAX area design

Module prototyping



Cabling of female staublis (VAX support), installation of support tooling and measuring the force needed for connection of the pneumatic lines

HL-LHC VAX area design

Integration tests




Temporary integration of pumping lines in mock-up. Adjustable system.

Tests mock-up in Preveessin site


HL-LHC VAX area design

Integration tests


First tests of cables routing on support, for VAX modules 2 & 3, CMS




Cables from M3



Pneumatic lines





Position indicator cables



VEJ cables

VGIA cables. Not radiation resistant cables due to lack of stock




- Studies ongoing.
- New position for Penning cable.
- Symmetric solution for VGIA may be necessary.

Simplified design to test on proto


HL-LHC warm vacuum system

3D models of the vacuum layouts


D1 / TAXN




TAXN / D2




D2 / CRAB



CRAB / Q4



Q4 / Q6




HL-LHC warm vacuum system

Design of the warm modules

<p>Ø150</p> <p><u>Ø150 VMBNNCL</u></p>  <p><u>Ø150 VMDNNCL</u></p> 	<p>Ø250</p> <p><u>Ø250 VMBRREEA</u></p>  <p><u>Ø250 VMERREEA</u></p> 	<p>Ø90</p> <p><u>Ø90 VMBLKAAI</u></p>  <p><u>Ø90 VMBLKAAK</u></p> 	<p>Ø90</p> <p><u>Ø90 VMBKAAI</u></p>  <p><u>Ø90 VMBKAAK</u></p> 	<p>Ø63 DRF</p> <p><u>Ø63 VMDFFAAI DRF</u></p>  <p><u>Ø63 VMDFFAAK DRF</u></p> 	<p>Ø63 RF</p> <p>LHCVMABC002</p>  <p>LHCVMABD0001</p> 
<p>Ø90/80 RF</p> <p><u>Ø90/80 VMBKIAAA200</u></p> 	<p>Ø80 LRM</p> <p><u>Ø80 VMVIIAAA</u></p> 	<p>Ø80/63 LRM</p> <p><u>Ø80/63 VMVIFAAA</u></p> 	<p>DOUBLE MODULE Ø80/63</p> <p><u>Ø80/63 double VMQIFFAN</u></p> 	<p>Ø63 LRM</p> <p><u>Ø63 VMVFFAAI LRM</u></p>  <p><u>Ø63 VMVFFAAK LRM</u></p> 	



HL-LHC warm vacuum system

Design of the warm module supports for storage




HL-LHC warm vacuum system



Design of the supports



Vacuum chamber supports




Valve module supports for D2




Valve module supports for the crab cavities

HL-LHC warm vacuum system

Recombination chamber




Production plan
definition + welding
plan




HL-LHC warm vacuum system


Recombination chamber



Supporting beam for NEG coating, cleaning, handling and storing.




Heating jacket



Processing steps for the recombination chamber


11 T magnet

Shimming schemes tested in the 11 T model



Collaring phase



-outer layer-



11 T magnet

Shimming schemes tested in the 11 T model



pole shimming
(baseline mitigation solution)



Collaring phase

-inner layer-



pole shimming
(FUJI_1)




11 T magnet

Instrumentation impact on the magnet

Determination of an equivalent pole to accommodate the instrumentation for the testing campaign



Slit for instrumentation: 2 mm (baseline)




-75 MPa



Azimuthal stress
(Collaring phase)



Pole with groove_v2




-75 MPa




-25 MPa

-90 MPa



-75 MPa

-60 MPa





-75 MPa

-60 MPa

MQXF magnet


Fracture mechanics

Fracture mechanics analysis on the fixed point of MQXF. Crack phase field based on damage model.



HL-LHC jacks


Mechanical design and procurement of pre-series




Cross-section of HL-LHC jack 3D model for FEA




Pre-series of HL-LHC jacks for IT String



Deflection of HL-LHC jack base plate wrt ground (concrete)



Von-Mises stress of HL-LHC jack frame at 1.5 rated load



Acceptance test tool for HL-LHC jacks (prepared to apply >26 Tn of vertical load and >4 Tn of lateral load)



HL-LHC WP12 Vacuum Controls – LSS1 and LSS5 documentation

- Work units with deliverables and spending profiles
- Racks and machine layout updated for optics v1.6
- Cable requests for P1 & P5
- Integration of power and mini-racks for P5R

VY11
VACSEC.B4L5.R


SA

Fixed group	Pumping port	Pumping port	Gauges & Fixed group	Gauges	start pos		
787.4L5	784.4L5	-150	-146.5	659.4L5	644.4L5	637.4L5	635.4L5
-152.383	-152	-139.5	-137.34	-138	-137.34	-137.18	-137.18
13177.06	13177.44	13179.44	13182.94	13189.94	13191.44	13192.10	13192.26




HL-LHC WP12 Vacuum Controls – Integration of equipment in EDA



TPG crate



Master PLC




Agilent crate



HL-LHC WP12 Vacuum Controls – R2E

- 3 designs qualified at CHARM
- Starting production of x400 power supplies for LS3
- Penning design partially accepted (LOG stage requires further analysis)
- Good results from the STS Piezo gauge up to 60 kGy (gamma)



HL-LHC WP12 Vacuum Controls - production


- **Number of equipment produced:**
 - 120 Agilent crates & 35 controllers
 - 80 VPI local boxes
 - 60 TPG crates
 - 100 Profibus cards
 - 32 VPGF local crates (DS)
 - 140 R2E crates
 - Master PLC crates
- **Equipment prepared and stored ready for LS3 deployment**



HL-LHC WP12 - New electronics for Sector Valve Control


New Profibus DP Interface Card

- Based on Microcontroller and ASIC
- New SPI differential lines communication
- Improved surge and overvoltage protection
- C code Firmware update



New Sector Valve Control Card

- Based on FPGA
- New SPI differential lines communication
- Improved surge and overvoltage protection
- New VHDL Gateware and logic description
- Long life components




HL-LHC WP16 Vacuum Controls - IT STRING

- **Procurement & production**

- Designed at CERN
- Manufactured at CERN & external companies
- All controllers are ready & tested

- **Requests**

- Rack requests
- Cabling requests
- Powering requests
- Ethernet sockets requests
- Installations completed





IT STRING Layout


HL-LHC WP16 Vacuum Controls - IT STRING

- **Developments**

- New PCB for the VPGF local crate
- Pumping group safety feature: HW pressure switch
- Vacuum data base & SCADA synoptic



New SCADA Application for IT string




HL-LHC WP5.3 Vacuum Controls - Beam Gas Curtain (BGC)

- **Developments**
 - Study of control system
 - Design BGC PLC controller
 - Controllers procurement & production
 - Vacuum data base & SCADA synoptic
- **Requests**
 - Cabling & power requests
 - Ethernet sockets
- **Documentation**
 - Technical specifications document




BGC PLC controller



New Synoptic integrated in LHC SCADA

Results from the a-C in-situ coated standalone of LHC



Coated only Q5L8 during LS2, to suppress e-cloud related heat load (the other standalones are equipped with cryosorbers: gas release during coating spoils the SEY performance)



etching train








coating train






The result:

Thin film coating: a-C on HL-LHC beam screens in IP 1 and 5



Laser Surface Structuring to reduce SEY in HL-LHC vacuum components



Higher power and slower scanning speed :




- More material removal
- Deeper trenches
- Lower SEY....but more particles

Laser Surface Structuring to reduce SEY in HL-LHC vacuum components

Beam screen type 74


Beam screen type 50L
& 50A

-possible application in LS3 for beamscreens of Q5 of IP1 and IP5,
to be treated on surface, to mitigate e-cloud -collaboration UK2 HL-
LHC, IOM Leipzig, Uni Naples
-integration and particle mitigation in progress



Other projects and studies

Future acceleration techniques: 10 m plasma source for AWAKE tunnel



Extension to 10 m

To be inserted in AWAKE tunnel in spring 2023

Test scalability: 2 plasma sources in series


Gasket-like aluminium vacuum window (200 μm thick)

FCC-hh vacuum system

FCC-hh prototyping



Carbon coating of prototypes sent to KARA




Sample design for impedance tests

FCC-hh BESTEX studies at KARA

3 FCC-hh beam screen prototypes ready to be measured (Cu, Cu sawtooth, a-C coated).

Measurements to be started in 2023. First (preparatory) visit to KIT in January.


Also work ongoing for measuring FCC-ee beam pipe in BESTEX.




FCC-ee vacuum system

FCC-ee design

Interconnection design:




DRF Contact Bridge type



Comb-type

Two designs presented for the interconnection undergoing impedance modelling.

Synchrotron radiation absorber design:




3D model with twisted tape to increase heat transfer coefficient


FCC-ee vacuum system

FCC-ee design


Thermal analysis on the absorber




Assessment of the heat transfer coefficient




Temperature fields in the chamber and in the absorber



Integrated power is ~ 3 kW over 109.2 mm.



Model of the heat deposition




Temperature on the cooling tube wall


FCC-ee vacuum system

FCC-ee design: SMA applications

BPM Design Updated




BPM position behaviour: horizontal




BPM position behaviour: vertical


Current analysis from BPM R&D team on optimal locations for BPM pick-ups



Copper additive manufacturing using cold-spray: Blue area are machined to support SMA couplers and pick-up devices




Design update of the FCC-ee BPM block on the vacuum chamber, incorporating the proposed equipment (BPM design given CERN/SY/BI for illustration)





FCC vacuum system

FCC-ee design: SMA applications


Oval-shaped connectors for FCC-ee chamber




Replacement of bolted flanges by SMA connectors



Elliptic profile for SMA connector compatibility



Simulations of contact pressure










Preliminary analytical calculations and FE simulations

FCC-ee vacuum system

FCC-ee design: SMA applications

Training setup for oval-shaped connectors





Training parameters optimization based on simulations

Training set-up


FCC-ee vacuum system

FCC-ee design: SMA applications

Training setup for oval-shaped connectors



Ring 1- Compression




Ring 2- Tension

Future tests: Recovery stress test (contact pressure measurements) and leak-tightness tests

FCC-ee vacuum system

FCC-ee prototyping

FCC-ee Vacuum Chamber Prototypes




Prototype vacuum chambers delivered.





Cold extruded chamber in C10200, 2 mm uniform thickness

First plans for use are:

- Metallography
- Metrology analysis (create 3D image of 5m length to compare against baseline design)
- NEG Coating
- **Integration to magnet system**




Stress field in the prototype chamber under vacuum



Preliminary study for integration in KARA

FCC-ee SC-RF cavities: electropolishing optimisation



$$\Delta E = U - IR(\text{bath, cables...})$$



$$j = f(U,$$

- j , Current density
- **U**, Overall applied tension
- T_b , Bath temperature
- τ , fluid dynamics
- S_c/S_a , Cathode geometry & Cathodic/Anodic surface rati
- σ_l , Bath conductivity
- $[b]$, Bath composition

1.3GHz
 Mass flow rate: 30 L/min
 T_b : 15 °C
 0.5 rotations per minute
 U: 7.4 V

$$j = f(\eta_a)$$


$$j = f(\eta_a, \tau)$$



1.3 GHz

■ Electropolished area

FCC-ee SC-RF cavities: coating optimisation



From DC magnetron sputtering to **HIPIMS***:

- first LHC-like cavity (400MHz)

- more compact coatings, improve the quality factor Q for the cavity ($R_{res} \sim 18$ nOhms, Target: <10 nOhms)


NB: on small 1.3GHz the electropolishing+ HIPIMS proved a surface resistance below 5nOhms!

*HIPIMS: High Power Impulse Magnetron Sputtering

FCC-ee SC-RF cavities: coating optimisation (Nb₃Sn)

Reacted **During** Coating


coating temperatures 500 - 750°C
further annealing (in-situ) 24 - 72 h



- Majority of coatings completed this way
- Large parametrical space investigated
- Cu diffusion issue

Reacted **After** Coating (Post-coating annealed)

annealing temperatures 450 - 750°C (1 - 24 hrs)
annealing vacuum much better than in situ




- Reduced Cu diffusion
- Ramp rate dependency
- Improved T_c consistency with Sn enriched target

FCC-ee SC-RF cavities: coating optimisation

1. Understand relationship between microstructure and RF properties

J_c = metric of crystalline quality
Low J_c = low RF dissipation
Increase maximum gradient






2. Relax requirements on surface treatments

“erase” the substrate by planarization effect

3. Reduce costs

Improve target utilization by shaping the plasma source







Deceleration of antiprotons from 100 to 4 keV

Design of ISOLDE beam line ongoing

Objectives 2023:


- First trapping of antiprotons
- First attempt to transport antiprotons






PUMA: H₂ and He isosteres in the 5-20 K range on Cu

Helium




Hydrogen



PUMA: Pressure wave propagation on Cu at cryogenic temperature


He propagation at 6 K

Simulation in agreement with experimental data



At 5-10 K


- New cryostat in construction
- a-C surface to slow down the pressure wave




Muon collider

Muons are elementary particles, over **200 times heavier than the electrons**, that therefore emit much **less synchrotron radiation** than the electrons and positrons.

Muon Colliders are the **ideal accelerators to reach multi-TeV center-of-mass energies**, otherwise forbidden in conventional $e^+ e^-$ linear colliders because of the cost



- Operating a Muon Collider at high energy is convenient with respect to other accelerators.
- No sub-constituents: the full energy can be exploited in the interaction. 14 TeV center of mass muon collisions are equivalent to 100 TeV p-p collisions.



Muon collider

Building muon colliders is **very challenging**.

Muons decay with a **lifetime of $2.2 \cdot 10^{-6}$ s if at rest**, while in a machine with a centre-of-mass energy of 3 TeV each beam has an energy of 1.5 TeV and the muons have a longer lifetime, **$3.1 \cdot 10^{-2}$ s**. In this very short time, the produced muons have to be accelerated and transferred in the collider to make them interact, possibly several times.

Three stages are needed: muons have to be **produced, accelerated** and finally **brought to collision**.

Muons are produced as tertiary particles by decay of pions created with an intense, **typically several MW, proton beam interacting with a heavy material target**.

The muon beam is **produced with low energy** and hence a limited lifetime.



It has **very large transverse and longitudinal emittances**.

It needs **to be cooled** by approximately five orders of magnitude in the six-dimensional (6D) transverse and longitudinal phase space.

The beam has to be **accelerated rapidly** to avoid excessive muon decay.

Muon collider

A **solenoidal cooling** channel was proposed and cooling of muons was demonstrated by using both **liquid hydrogen and lithium hydride absorbers**




Ionization cooling is achieved by reducing the beam momentum through ionization energy loss in absorbers and **replenishing the momentum loss only in the longitudinal direction** through radio frequency (RF) cavities.

Muon collider

An impressive list of problem to solve, including **radiological hazard**.

The muon decay






and its charge conjugate are the major source of background in a Muon Collider. The decay neutrinos coming from muon decays do not affect the detector design due to the low interaction cross section, but the secondary radiation, hadrons, muons and electrons **produced by the neutrino** interaction with the earth could constitute a problem.

TE-VSC participate in the study. Our task is to contribute to the feasibility study of ionisation cooling investigating very thin beam window separating vacuum from liquid hydrogen.

Muon collider



H ₂ Absorber	Length	Max P (bar)	Max T (K)	P assuming power deposited in 3 \times σ_{RMS} (bar)	K assuming power deposited in 3 \times σ_{RMS} (K)
RT@1bar	124 m	1.3	373	1.04	303
RT@4bar	31 m	5.2	373	4.18	303
20.3K@1bar vapor	8 m	7.5	140	1.8	34
26.1K@4bar vapor	2.1 m	29.2	143	7	40
20.3K@1bar liquid	15 cm	833	128	125	35

Maximum differential pressure v membrane size (membrane thickness 30 nm to 1000 nm)



1 μ m 6x6mm Si₂N₃ window \rightarrow \approx 5 bar pressure


DEFT: Deep Electron FLASH Therapy




Design of the FLASH therapy vacuum chamber placed in a bending magnet.

DEFT: Deep Electron FLASH Therapy



Time dependent pressure profile in the photo-cathode area



Design of the FLASH therapy vacuum chamber placed in a bending magnet.




Surface: Total displacement (mm)
Bending magnet where the chamber is placed. ▲ 0.37



Displacement map of the vacuum chamber due to external pressure. Load factor : 38.

HiRadMat – SMAUG vacuum window experiment



# spot	Beam size	Intensity	# shots at 288 bunches
1	0.5	$1.6 \cdot 10^{11}$	5
2	0.5	$1.6 \cdot 10^{11}$	50
3	0.35	$1.2 \cdot 10^{11}$	5
4	0.35	$1.2 \cdot 10^{11}$	50
5	0.35	$1.6 \cdot 10^{11}$	5
6	0.35	$1.6 \cdot 10^{11}$	50



Assembly in BA7




Transport to TNC




CCC – SMAUG run!

HiRadMat – SMAUG vacuum window experiment




- All windows are leak tight!
- Optical microscopy: clear marks of point 2-4-6 on G-carbon and Be alloyed sample; clear marks of point 4 and 6 on PF-60.
- The Facility limit in terms of brightness is moved from $0.5 \cdot 10^{13}$ p+/mm² to $1.8 \cdot 10^{14}$ p+/mm² (beyond LIU);
- A new layout is under study within the HRM upgrade working group.

Other projects: ELISA, CNAO gantry, gamma factory,...



ELISA – SCIENCE GATEWAY



GAMMA FACTORY – BA6


CONSOLIDATION WORK PACKAGE DESCRIPTION

North Area target stations T2, T4, T6, T10 consolidation SY-STI, SY-BI, TE-VSC, BE-CEM

ABSTRACT|

To improve the reliability of the North Area target stations those equipment's are proposed for consolidation. This document describes the scope, impact and resource estimate of the proposed consolidation action and contains a related risk analysis. This document is used to request funding in the framework of the North Area Consolidation program, and it serves for analysis and prioritization of all consolidation requests.

DOCUMENT PREPARED BY:	DOCUMENT CHECKED BY:	DOCUMENT TO BE RELEASED BY:
Jean-Louis Grenard Damien Grenier Françoise Ximenes SY-STI-TCO Giulia Romagnoli	Marco Calviani SY-STI-TCO Ramon Folch BE-EA	Yacine Kadi BE-EA - NA-CONS Project leader Consolidation Project Management Simone Gilardoni SY-STI
Jocelyn TAN SY-BI Jerome LANDARO BE-CEM Patrick BESTMANN	TBIU/D @ NA-CONS	
		SY-BI Helene Mainaud Durand BE-GM Paolo Chiggiano TE-VSC



CNAO - 360° GANTRY

Next generation of GWD: Einstein Telescope

ADDENDUM NO. 1
KR5427/TE
TO
FRAMEWORK COLLABORATION AGREEMENT
KN 4657/DG

BETWEEN: THE EUROPEAN ORGANIZATION FOR NUCLEAR RESEARCH ("CERN"), an Intergovernmental Organization having its seat at Geneva, Switzerland,

AND: THE ITALIAN NATIONAL INSTITUTE FOR NUCLEAR PHYSICS ("INFN"), established in Rome, Italy,

AND THE DUTCH NATIONAL INSTITUTE FOR SUBATOMIC PHYSICS ("Nikhef"), established in Amsterdam, The Netherlands,

Hereinafter each individually referred to as a "Party" and collectively as the "Parties",

CONSIDERING THAT:

Framework Collaboration Agreement KN4657/DG (the "Agreement") concluded between the Parties defines the framework applicable to collaboration between them in domains of mutual interest.

Article 2.1 of the Agreement provides that the scope, each Party's contributions, and all other details of each specific project shall be set out in Addendum to the Agreement.

The Parties have identified the collaborative project set out below, which shall be covered by the provisions of this Addendum No. 1 (the "Addendum"),

AGREE AS FOLLOWS:

Article 1
Purpose

- 1.1 Under the terms of this Addendum, the Parties shall collaborate in the development of the vacuum systems of the arms of the Einstein Telescope ("ET") (the "Project"). The Project is outlined in [Annex 1](#).
- 1.2 The Parties shall use the results and resources of their collaboration for non-military purposes only. INFN and Nikhef shall ensure compliance with this obligation by the ET Consortium members.
- 1.3 This Addendum shall be subject to the provisions of the Agreement, it being understood that in case of divergence the provisions of this Addendum shall prevail.

Article 2
Duration of the Project

Subject to the continued validity of the Agreement, the Project shall begin upon signature by the last Party to sign and shall be completed after 36 months.

Done in the English language and signed by the authorized representatives of the Parties.

The European Organization
for Nuclear Research (CERN)

The European Organization
for Nuclear Research (CERN)

Mike Lamont

Jose Miguel Jimenez

.....
Mike Lamont
Director for Accelerators and Technology

.....
Jose Miguel Jimenez
Head of Technology Department

Signed on 7/7/2022.....2022

Signed on 8/7/2022.....2022

Christopher Hartley

Cristina Lara

.....
Christopher Hartley
Head of Industry, Procurement and
Knowledge Transfer Department

.....
Cristina Lara
Deputy Head of Procurement Service

Signed on 11/7/2022.....2022

Signed on 9/7/2022.....2022

The Dutch National Institute for Subatomic
Physics ("Nikhef")

The Italian National Institute for Nuclear
Physics ("INFN")

Stan Bentvelsen

Dr. Antonio Zoccoli



.....
Stan Bentvelsen
Nikhef Director

.....
Antonio Zoccoli
INFN President


Signed on 19/7/2022.....2022

Signed on 26/7/2022.....2022

Next generation of GWD: Einstein Telescope



Items	Requirements
Pipe diameter	1.2 m (tbd)
Total length	≈120 km
Hydrogen partial pressure	order of 10^{-10} mbar
Water vapour partial pressure	$< 5 \times 10^{-11}$ mbar
Hydrocarbon partial pressures	$< 10^{-14}$ mbar
Lifetime	50 years



**WP1:
engineering**

Design and
engineering of
the vacuum
chamber

**WP2:
production**

Choice of
materials and
manufacturing
technology

**WP3:
treatments**

Choice of
post-
manufacturing
treatments

**WP4:
transport**

Handling and
logistics

**WP5:
installation**

Installation
procedure and
interface with
other systems

**WP6:
vacuum**

Choice of
vacuum
pumps and
valves

**WP7:
prototyping**

Installation
and test of a
pilot sector

**WP8:
coordination**

Coordination
of the different
work
packages and
contribution of
collaborators

Work-Breakdown Structure

27–29 Mar 2023
CERN
Europe/Zurich timezone

Enter your search term

Overview

Timetable

Registration

Getting to CERN

Register your laptop for Cern Wifi access

Accommodation

Cern Access Cards

Contribution List

My Conference

My Contributions

Useful information

Contact

carita.hervet@cern.ch

0227672373

Timetable



Contributions are in draft mode

While in draft mode, regular users cannot see the contributions and timetable.

Publish contributions

Mon 27/03 | Tue 28/03 | Wed 29/03 | All days

Print

PDF

Full screen

Detailed view

Filter

Session legend

- Monday Afternoon Plenary Session
- Monday afternoon Session
- Monday morning Plenary Session
- Visit to Mechanical Workshop and

09:00	Welcome and motivation 30/7-018 - Kjell Johnsen Auditorium, CERN	Jose Miguel Jimenez 09:00 - 09:10
	Next generation Gravitational Wave Observatories and vacuum S&T as a key for their success 30/7-018 - Kjell Johnsen Auditorium, CERN	M. Zucker et al. 09:10 - 09:30
	Cosmic Explorer: status of the project, planning and requirements for beampipes vacuum systems 30/7-018 - Kjell Johnsen Auditorium, CERN	Mike Zucker 09:30 - 09:50
10:00	Einstein Telescope: status of the project, planning and requirements for beampipes vacuum systems 30/7-018 - Kjell Johnsen Auditorium, CERN	09:50 - 10:30

Next generation GWD: Einstein Telescope

- **TT1 tunnel:**

- Advantages: almost constant environmental conditions, synergy with alignment team.
- Disadvantage: difficult access and transport (feasibility to be done), no ventilation in the tunnel.





Next generation GWD: Einstein Telescope



Next generation GWD: Einstein Telescope

Mild Steel as possible alternative to stainless steel

Extended study of the outgassing properties of mild steel to replace austenitic stainless steels



Next generation GWD: Einstein Telescope



Interferometer vacuum chamber for Einstein Telescope

Pre-prototype chamber:

Reduced 2.1-m long, 400-mm diameter corrugated vacuum chamber, thickness 1.0mm

3 different types of material:

- 304L -> production launched December/January
- Ferritic stainless steel
- Mild steel




Vacuum chamber design and prototype

2D drawings

Next generation GWD: Einstein Telescope

Study of low temperature bakeout efficiency




3 x DN400 – 2m long corrugated chambers

Structural mild steel

304L + VF

AISI430




- 1 turbo pump every 2 km (the curves shown are at 1 km, so L/2)
- $D = 1.2$ m
- Isotherm parameter from mild steel binding energy measurement.
- Distribution of NEG pumps every 100 m (CapaciTorr HV2100).
- $Q_{H_2} = 1 \times 10^{-13}$ [mbar \cdot l \cdot s $^{-1}$ \cdot cm $^{-2}$]
- The cycle was thought as follow:
 - Pump-down for 7 day
 - Bake-out for 7 days


Next generation GWD: Einstein Telescope

Interferometer vacuum chamber for Einstein Telescope

Mechanical concept: **thin-walled corrugated tube in stainless steel**



- Withstand external pressure:
For steels, a thickness of around 1.3 mm is enough to ensure the mechanical stability of the $\sim \phi 1.1$ m vacuum chamber.
- No need of compensation bellows.
- Light structure: ~ 50 kg/m (without thermal insulation).
The chamber can be supported either from the roof or the floor.
- “Easy” bake out of the structure.
- Reduced material amount and therefore cost.





Buckling mode under external pressure




Next generation GWD: Einstein Telescope

Interferometer vacuum chamber for Einstein Telescope

Vacuum system layout proposal:



Soft supporting system: stability analysis under compressive force




Linear and non-linear global buckling analysis

Plasma cleaning of radioactive vacuum equipment


Aim: replace a wet degreasing with a plasma degreasing for **activated** parts; avoid liquid retention in complex shapes (avoid complex treatment of activated fluids)

-**O₂ plasma** to oxidise hydrocarbons to CO₂




ZS tank D=600mm L=3500mm


First real PSB tank cleaned successfully



Simulation: plasma species generation, surface and gas collisions, transport of active species



● active species ● neutral gas



Developments

Shape Memory Alloy Rings for Tight connections

FE modelling of SMA: implementation of a new constitutive model in ANSYS

Thermo-mechanical pre-strain $\epsilon_{tot}=15\%$ ($T=-65^\circ\text{C}$)

Additional features: **plasticity** and **Two-Way SME**


Ability to simulate **coupling/uncoupling** process

Suitable for **complex system** geometries


Possible results: **transformation/plasticity** strain components

High solution **accuracy**

Subroutine (**USERMAT**) code: **FORTRAN77**




no usermat




usermat

Pre-strain ($\epsilon_{tot}=28.8\%$) + free thermal cycles



Experimental measurements



Predicted numerical results




Shape Memory Alloy Rings for Tight connections

FE modelling of SMA: implementation of a new constitutive model in ANSYS


OVAL COUPLERS

Radial stress at $T_{max}=200^{\circ}\text{C}$




- Pipe-pipe and pipe-coupler contact: **FRictional**
- Max pre-strain: $\epsilon_{tot}=15\%$
- Initial pipe-coupler gap: 0.15mm

Average contact pressure




BI-MATERIAL CONNECTION



Radial stress at $T_{max}=120^{\circ}\text{C}$




Average contact pressure



Norm of transformation and plastic strain tensors at $T_{max}=200^{\circ}\text{C}$




Pipes-SMA contact pressure at $T_{max}=120^{\circ}\text{C}$




Shape Memory Alloy Rings for Tight connections

C-Shaped connectors for conical CF flanges



Simulations and experiments




C-Shaped connector principle





DN100 3D simulations



- Elastic-plastic copper gasket
- Elastic flange




Instrumented C-shaped connector




Measured and simulated recovery force

ESD characterization of materials for UHV




Sample temperature measurement


ESD and SEY of LHC Cu BS characterisation at 15 K



ESD vs primary energy



ESD conditioning at 300 eV







SEY conditioning at 0.3 and 1 keV

ESD of a-C at 4.2 K in a closed geometry

a-C surface irradiated at 500 eV

- Room temperature: $\eta = 0.15$ molecule/electron
- H_2 dominated





- 4.2 K: $\eta < 0.05$


TDS

Thermal and diffusion analysis


Thermal simulation on TDS samples (radiation + conduction) to better estimate the outgassing rate.



Outgassing rate (normalised) vs temperature between uniform temperature and the simulated one considering the thermocouple wires.




Temperature comparison





Temperature uniformity

Surface analysis: surface characterization of photocathodes






- ✓ Vacuum transfer systems for sensitive and reactive photocathodes to avoid surface oxidation and adsorption of ambient species (with SY-STI-LP)
- ✓ CsKSb film-like cathodes and Cu nanostructured cathodes for
→ **Surface composition analysis, aging effects**



H. Panuganti et al., Nucl. Inst. Meth. Phys. Res. A 986 (2021) 164724

MolFlow+ extension

Extending MolFlow+ with microscopic force and torque calculations



LISA Pathfinder




Image: Lorenzo Sala, ESA

MolFow+ extension

Time dependent simulations of pressure in NEG pipes


Vacuum chamber conditioning and saturation simulation tool (VacuumCOST)

Python code for iterative Molflow simulations of high temporal resolution.

Allow time-dependent simulation of vacuum chamber conditioning and NEG saturation.

<https://gitlab.cern.ch/phenriks/vacuumcost>


Result after 1/3000 seconds



Ex.: Injection of gas into NEG-coated tube. Colors indicate density of adsorbed molecules. Red-edged facets are saturated.


BGC phase II for LHC and phase III for Hollow e⁻ lens

BGC ph.II Vacuum studies



Vacuum tests of BGC at B8 laboratory


- BGC ph. III Simulations




Pressure in vessel & particle density due to gas jet

Hollow Electron Lens collector vacuum simulations

Pressure at the HEL collector due to ESD and thermal outgassing produced by the flux of electrons impacting on the surface of this chamber



Section view of the original CAD model






Pressure along the collector

Beam impedance of deformable RF bridge

3 types of warm modules in HL-LHC




- $\varnothing 63$, $\varnothing 150$, $\varnothing 250$

Determination of the longitudinal and transverse beam impedance



Surface impedance as a function of temperature

Coatings and treatments characterisation





HTS applications for future accelerators

Beam screens


- Factor 10 reduction in surface impedance

RF cavities

- High power test facility at SLAC





YBCO deposition on Copper




RFQ-Linac 4 irradiation campaign

The blistering effect does not affect the conditioning field but is a function of the grain orientation.



Cu OFE

Material	E _{max} (MV/m)	Irrad.	Blistering
Cu OFE	80	Yes	Yes
	83	Yes	Yes
	80	No	x
TiAl6V4	110	No	No
	95	Yes	x





Cu-OFE and TiAl6V4 are so far best materials in reaching a stable field.

Radiation hard O'rings

New O'ring formulation:

- Development by LRCCP of a new formulations for high irradiation environment
- Characterisation tests, in particular after irradiation, with LRCCP of two new formulations and comparison with LHC O'rings.



Influence of radiation doses on tensile/relaxation curves for selected and LHC formulations

Summary of leak tests for EPDM-F14 for 25% compression:



- Irradiation up to ≤ 1 MGy (at γ): leak tight assembly at any condition
- Irradiation up to 2 and 3 MGy (at γ): leak tight assembly as received; leak tight assembly when O-ring is irradiated without compression and mounted for vacuum sealing; leaky assembly when O-ring is irradiated at compressed status and re-assembled at the same compression ratio
- Irradiation up to 5 MGy (at γ): leaky assembly as received; leak tight assembly when O-ring is irradiated without compression and mounted for vacuum sealing; leaky assembly when O-ring is irradiated at compressed status and re-assembled at the same compression ratio



Irradiation campaign of elastomer seals

Clamshell for leak detection

CLAMSHELL	Line	ST	ST	PARAMETERS	Manufacturing & testing				
					CLAMSHELL	MOULD	INLET	SEAL	VALVE/PIECE
D0709	Medium Sluice	ST1350037	ST1350038	5 20 1 2	✓	✓	✓	✓	ST264383
D8410	Intermediate Medium Sluice	ST1344286	ST1344287	4 40 1 1	✓	✓	✓	✓	ST200044
D2104	IPS	ST1350086	ST1350087	4 40 2 2	✓	✓	✓	✓	Transition tube
D18	Safety Line By-Pass	ST1323966	ST1324028	4 44 10 2	✓	✓	✓	✓	Tube
D67-Plug	Shutter	ST1342979	O-RING		✓	✗	✗	✓	O-ring Plug




Clamshell and fabrication tooling design

Clamshell redesign



Clamshell prototype





Clamping methods



Different seals and sealing manufacturing method



Clamshell tests




Aluminum clamshell with glued vacuum connection

Radiation hard bakeout system


Heating track deposited by cold-Spray

Thermal simulations:







From 2021, design of prototype


Bake-Out prototype successfully tested:



Bake-out setup in workshop




Thermal camera examination




Heat Transfer simulations of the lattice track.

Temperature homogeneity within tolerance. Materials can achieve bake-out of 250°C.



Testing ideal track parameters to update above design.



Further work required to perfect bake-out track and cold-spray parameters. New 'lattice' track proposed


Additive manufacturing by cold spray

Cold-Spray UHV Validation



Helium leak testing. Tool developed to test:



- Deposit + Substrate
- Deposit only
- Interface



Pure Cu and Cu + Al₂O₃ combinations successfully tested
Decreasing thickness of Deposit to find limit of leak tightness capability. Pure Cu is better




All samples subjected to thermal shock testing




Metallography examinations

- Alumina particles are homogeneously distributed
- Interfaces are free from imperfections (cavities, cracks, lack of adhesion)



Outgassing campaign on-going in Bld.101




Additive manufacturing by SLM

Leak tightness tests of copper samples made with green laser.



Friction stir welding of copper flange


Phase 1: 6 Flanges + short chamber profiles for destructive testing to determine optimal weld parameters and refine any design issues with flange and/or chamber.



Oval Flange designed to fit vacuum chamber with FSW manufacturing process in mind.



Short chamber profile made by wire-cutting (Erosion Discharge Machining)




Short chamber profile inserted into flange for Phase 1 welding tests

Results from Phase 1 of Friction Stir Weld (FSW) Tests:


- Good shoulder print on part surface.
- Small internal porosities (maximum size = 0,9 mm) into some (likely coming from the clearance between tube and flange)
- No residual bond between flange and tube
- On cross section 3, we see copper pushed away on the internal side of the flange

Phase 2:

Longer chambers, 150mm inserted into flanges.
15 assemblies will be welded using newly-determined weld parameters for UHV validation and other testing at CERN.




Cross-section 1



Cross-section 2



Cross-section 3



Possible flange modification for future iterations

Macroscopic inspection

- Good shoulder print on part surface
- No visible porosity in surface
- Excessive penetration in the end of the weld (tool collapse, too hot)




SCADA development

vacCC Synchronizer – Tool for Layout and vacDB synchronization

vacCC Synchronizer – Validated and used to perform the final LHC synchronization before RUN3

- Human-assisted tool to aid the update of vacDB with new LayoutDB data (equipment, sectors, mainparts)
- New version allows:
 - Partial synchronizations (per sector/mainpart) as opposed to the entire machine
 - Synchronization with different LayoutDB versions – allowing us to work in advance for HI-LUMI



- New LayoutDB error detection mechanisms implemented – errors are now detected in the layoutDB before they are imported into vacDB:
 - Missing attributes (Sector, Sector Before, Sector After)
 - Position Mismatch (DCUM and Sector don't match)
 - Overlapped sectors
 - Sector loss of continuity
 - Control type mismatch (types in LayoutDB and vacDB don't match)



Validation:

- ~ 100 page test document
- Synchronizer fully validated in production environment
- vacDB LHC production database synchronized

Vacuum Controls Configurator Machine




vacCC Machine upgraded to use the new versions:


- Backend updated to Spring 2.7
- User Interface upgraded to React 17 and AntD 5

Updating software:

- Avoiding software obsolescence
- Keeping up to date with security patches



SCADA Performance Study





Performance Measuring Panel


- Several algorithms modified to increase the performance of the vacuum SCADA
- LHC's Main View loading time is expected to improve ± 10 seconds compared to the previous baseline after the LHC SCADA update
- Startup performance will further improve after the deployment of the new Unified Mobile System to about 50% of current time
- New metrics gathering system will allow to monitor the performance evolution on upcoming SCADA releases

Vacmon

- New version under development
- Web pages with resume information from vacuum SCADA applications
- Fully configurable – new **templating mechanism** allows pages to be created online
- Data containers developed:
 - Real-time streaming the current state of Valves
 - Real-time Elogbook events
 - Vistar Images
 - SCADA Screenshots
 - Images
- **To be released Q1 2023**



Templating a Page







Rendered templated Page

PLC and ELECTRONICS DEVELOPMENT

TSPP for Vacuum Framework

Implementation of TSPP for Vacuum Framework (“UNICOS-style” Data Acquisition)

- Time Stamped Push Protocol: vast improvement in Time and Value resolution of acquired data
- No more lost data (pressure spikes, fast interlocks, momentary glitches, etc)
- Start of deployment during 2023



Polling at 1s

Pressure peaks every 5 seconds (**top**), ramp up/down every second (**bottom**)

With TSPP

Same signals, now properly acquired

Consolidation of Mobile Systems

New router for 4G renovation of Mobile Systems selected and validated

Connectivity tests on the surface and tunnels

Vibration tests in QART Lab


Large-volume orders in late 2022 / early 2023

Consolidation planned for 2023 (VPGs + Bakeout)




Merging of Wireless and Profibus

- Works continues to merge the 4G and Profibus systems for Profibus Mobile Integration
- PLC implementation of new Profibus Protocol is **complete**
- SCADA / exporter implementation is **ongoing** (planned 2023)



Renovation of High-Pressure Water Rinsing Facility




Intuitive Touch Panel

New, reliable and flexible Control System

- Uses up-to-date technology that we can maintain for the expected lifetime of the machine
- A lot of added functionality
- New safety features
- Properly documented



Rinsing Quality Control



Modern Control Architecture

Safety interlocks integrated into the Control System

TPG500 & Profibus diagnostic

TPG500


- Validation of new Profibus firmware v2.11
- Sixteen units installed in production (13x SPS, 2x MEDICIS, 1x LEIR)

PROFIBUS

- Combricks diagnostic tool evaluation
- One unit installed in BA2
- One unit installed in Lab
- Company visit



TPG500s installed in BA6




ComBricks in BA2 Profibus network

MEMS low-cost Helium detector electronics


- **MEMS thermal conductivity sensor**

- First demonstration prototype fully functional
- Very small size: 37mm x 29mm x 25mm



- **Foreseen upgrades for second prototype**

- Further size reduction
- Battery powered
- Wireless (LoRa)
- Radiation tolerant



In period with **limited visibility**, we have to **reinforce and acquire new competences**.

Technological competences are key aspects of our flexibility and ability to join new studies and projects

However, **our credibility comes from our services and operational daily work**. Only if we ensure excellent services/operation, we can see **optimistically into the future**.



25 x 25 Diversity & Inclusion Programme

[TE Focal Points : Caroline Fabre, Holger Neupert, Paulo Gomes]

Analysed and summarised the answers from a sample of ~45 TE members. Examples of comments:

colleagues are strongly against positive discrimination at recruitment and advancement

there are not enough interesting candidates applying (already before looking into nationality or gender)

action is needed upstream of HR long list, e.g. the advertisements for open positions

Dept. should provide more visible, accessible and digested data analytics; and more communication on dept. vision

Analysed the TE personnel statistics on nationality and gender

Elaborated a set of actions for the “Department Fitness Plan”

Presented to & approved by HD and TEMB (22/09/2022) [[EDMS 2775176](#)]



Moved from 3 Dep. Focal Points to 1 D&I Officer [Paulo Gomes]

Current Discussion on DIO mandate modification:

monthly meetings instead of 3 / year ?

extend duration of the mandate up to 2 or 5 years ?


include policy recommendations ?





Merci à vous tous!

Publications 2022



CERN COURIER.COM

FEATURE VACUUM SYSTEMS

TRACING MOLECULES AT THE VACUUM FRONTIER

CERN's Molflow software has become the de-facto industry standard for ultra-high-vacuum simulations. Roberto Kersevan and Marton Ady describe how it is now enabling space research and other branches of science to develop their own applications.

Fusion flow
Thermal-radiation calculation for a huge (1 m diameter) cryopump at ITER, based on a modified version of Molflow called McCryot, which exploits similarities between heat and molecular transfer.

In particle accelerators, large vacuum systems guarantee that the beams travel as freely as possible. Despite being one 25-trillionth the density of Earth's atmosphere, however, a tiny concentration of gas molecules remain. These pose a problem: their collisions with accelerated particles reduce the beam lifetime and induce instabilities. It is therefore vital, from the early design stage, to plan efficient vacuum systems and predict residual pressure profiles.

Surprisingly, it is almost impossible to find commercial software that can carry out the underlying vacuum calculations. Since the background pressure in accelerators (of the order 10^{-10} - 10^{-11} mbar) is so low, molecules rarely collide with one other and thus the results of codes based on computational fluid dynamics aren't valid. Although workarounds exist (solving vacuum equations analytically, modelling a vacuum system as an electrical circuit, or taking advantage of similarities between ultra-high-vacuum and thermal radiation), a CERN-developed simulator "Molflow", for molecular flow, has become the de-facto industry standard for ultra-high-vacuum simulations.

Instead of trying to analytically solve the surprisingly difficult gas behaviour over a large system in one step, Molflow is based on the so-called test-particle Monte Carlo method. In a nutshell: if the geometry is known, a single test particle is created at a gas source and "bounced" through the system until it reaches a pump. Then, repeating this millions of times, with each bounce happening in a random direction, just like in the real world, the program can calculate the hit-density anywhere, from which the pressure is obtained.

The idea for Molflow emerged in 1988 when the author (RK) visited CERN to discuss the design of the Elettra light source with CERN vacuum experts (see "From CERN to Elettra, ESRF, ITER and back" panel). Back then, few people could have foreseen the numerous applications outside particle physics that it would have. Today, Molflow is used in applications ranging from chip manufacturing to the exploration of the Martian surface, with more than 1000 users worldwide and many more downloads from the dedicated website.

THE AUTHORS
Roberto Kersevan
and Marton Ady
CERN.

CERN COURIER SEPTEMBER/OCTOBER 2022 25

Publications 2022

PUMA, antiProton unstable matter annihilation, Eur. Phys. J. A 58 (2022) 88

An instrumented baffle for the Advanced Virgo Input Mode Cleaner End Mirror submitted for publication <https://arxiv.org/abs/2210.16313>

J. Tagg, E. Bez, M. Himmerlich, A. K. Reascos Portilla,
A reliable monitoring and control system for vacuum surface treatments
Proceedings 18th Int. Conf. on Acc. and Large Exp. Physics Control Systems ICALEPCS2021, Shanghai, China p492-96 (2022)

P. Lorenz, M. Himmerlich, M. Ehrhart, E. Bez, K. Bodganowicz, M. Taborelli, K. Zimmer
Secondary electron yield reduction of copper after 355 nm ultrashort pulse laser ablation
Lasers Manuf. Mater. Process. 9 (2022) 135-150, DOI: [10.1007/s40516-022-00167-5](https://doi.org/10.1007/s40516-022-00167-5)

P. Lorenz, E. Bez, M. Himmerlich, M. Ehrhardt, M. Taborelli, K. Zimmer
Secondary electron yield engineering of copper surfaces by 532 nm ultrashort laser pulses
Proc. CIRP 111 (2022) 662-666, DOI: [10.1016/j.procir.2022.08.017](https://doi.org/10.1016/j.procir.2022.08.017)

P. Lorenz, M. Himmerlich, M. Ehrhardt, E. Bez, K. Bogdanowicz, M. Taborelli, K. Zimmer
Secondary electron yield engineering of copper surfaces using ultra short infrared laser pulses
Proc. SPIE 11989, Laser-based Micro- and Nanoprocessing XVI (2022) 119890A, DOI: [10.1117/12.2609463](https://doi.org/10.1117/12.2609463)

M. Himmerlich, D. Zanin, M. Taborelli, A. Granadeiro Costa, P. Costa Pinto, L. Lain Amador, W. Vollenberg, A. Baris, E. Garcia-Tabares Valdivieso, A. T. Perez Fontenla, S. Wackerow and A. Abdolvand
Efficient Combination of Surface Texturing and Functional Coating for Very Low Secondary Electron Yield Surfaces and Rough Nonevaporable Getter Films
Adv. Mater. Interfaces 2022, 2201671

T.Kövener, D. Kuchler, E. Mahner, R. Scrivens, A. Baris, S. Pfeiffer, L. Mourier, W. Vollenberg,
Experiments to improve the performance of the GTS-LHC ECR ion source
J. Phys. : Conf. Ser. 2244 (2022) 012020
19th International Conference on Ion Sources (ICIS 2021), Vancouver, BC, Canada, 20 - 24 Sep 2021, pp.012020

D Fonnesu, A Baris , S Calatroni, L Lain Amador, S Pfeiffer, G Rosaz, M Bonura and C Senatore
Reverse coating technique for the production of Nb thin films on copper for superconducting radio-frequency applications
2022 Supercond. Sci. Technol. 35 125003

J. Golm; S. Arguedas Cuendis; S. Calatroni; C. Cogollos; B. Döbrich; J.D. Gallego; J.M. García Barceló; X. Granados; J. Gutierrez; I.G. Irastorza; T. Koettig; N. Lamas; J. Liberadzka-Porret; C. Malbrunot; W.L. Millar; P. Navarro; C.P.A. Carlos; T. Puig; G.J. Rosaz; M. Siodlaczek; G. Telles; W. Wuensch
Thin Film (High Temperature) Superconducting Radiofrequency Cavities for the Search of Axion Dark Matter
IEEE Transactions on Applied Superconductivity 2022 Volume: 32, Issue: 4, 1050605

G. Rosaz, A. Bartkowska, C.P.A. Carlos, T. Richard, M. Taborelli,
Niobium thin film thickness profile tailoring on complex shape substrates using unbalanced biased High Power Impulse Magnetron Sputtering,
Surface and Coatings Technology, Volume 436, 25 April 2022, 128306,

M Arzeo, F Avino, S Pfeiffer, G Rosaz, M Taborelli , L Vega-Cid and W Venturini-Delsolaro
Enhanced radio-frequency performance of niobium films on copper substrates deposited by high power impulse magnetron sputtering
Supercond. Sci. Technol. 35 (2022) 054008

A.- M. Valente-Feliciano, C. Antoine, S. Anlage, G. Ciovati, J. Delayen, F. Gerigk, A. Gurevich, T. Junginger, S. Keckert, G. Keppel, J. Knobloch, T. Kubo, O. Kugeler , D. Manos, C. Pira, T. Proslie, U. Pudasaini, C.E. Reece , R.A. Rimmer , G.J. Rosaz , T. Saeki , R. Vaglio, R. Valizadeh, H. Vennekate, W. Venturini Delsolaro , M. Vogel, P. B. Welander, M. Wenskat,
Next-Generation Superconducting RF Technology based on Advanced Thin Film Technologies and Innovative Materials for Accelerator Enhanced Performance & Energy Reach ,
Submitted to the Proceedings of the US Community Study on the Future of Particle Physics (Snowmass 2021), <https://arxiv.org/pdf/2204.02536.pdf>

G. Rosaz, Associate member for the section High-gradient RF structures and systems, in European Strategy for Particle Physics - Accelerator R&D Roadmap, N. Mounet (ed.), CERN Yellow Reports: Monographs, CERN-2022-001 (CERN, Geneva, 2022), <https://doi.org/10.23731/CYRM-2022-001>.

M. Ghaemi, A. Lopez-Cazalilla, F. Djurabekova, K. Sarakinos , G. J. Rosaz and S. Calatroni
Growth of Nb films on Cu substrates by direct current and high-power impulse magnetron sputtering: a molecular dynamics study
Submitted to NIMB Proceedings (2022)

E. Bez, M. Himmerlich, P. Lorenz, M. Ehrhardt, A. Graham Gunn, S. Pfeiffer, M. Rimoldi, M. Taborelli, K. Zimmer, P. Chiggiato and A. Anders
Influence of wavelength and accumulated fluence at picosecond laser-induced surface roughening of copper on secondary electron yield
Submitted to J. Appl. Phys.

J. JJ Nivas, M. Hu, M. Valadan, M. Salvatore, R. Fittipaldi, M. Himmerlich, E. Bez, M. Rimoldi, A. Passarelli, S.L. Oscurato, A. Vecchione, C. Altucci, S. Amoroso, A. Andreone, S. Calatroni, M. R. Masullo
Laser-induced periodic surface structuring for secondary electron yield reduction of copper: dependence on ambient gas and wavelength
Submitted to Appl. Surf. Sci.

L.A.J. Soomary, C.P. Welsch, L.B. Jones, T.C.Q. Noakes, H.M. Churn, C. Benjamin, H. Panuganti, E. Chevally, M. Himmerlich, V. Fedosseev, E. Granados, Performance characterisation at Daresbury laboratory of Cs-Te photocathodes grown at CERN, Proc. 13th Int. Particle Acc. Conf. (IPAC2022), 12.-17.06.2022, Bangkok, Thailand
doi:10.18429/JACoW-IPAC2022-THPOPT033

V. Petit, P. Chiggiato, M. Himmerlich, S. Marinoni, H. Neupert, M. Taborelli, L. Tavian, Origin and mitigation of the beam-induced surface modifications of the LHC beam screens, Proc. 13th Int. Particle Acc. Conf. (IPAC2022), 12.-17.06.2022, Bangkok, Thailand,
doi:10.18429/JACoW-IPAC2022-TUOXSP1

J. Harray, V. Petit, C. Garion, Thermo-mechanical modelling and thermal performance analysis of beam vacuum line interconnections and cold warm transitions in HL-LHC long straight section magnets, IPAC 2022.

S. Weiller, F. Delloro, F. Willot, A. Thorel, M. Jeandin, C. Garion, Influence of Porosity on Ultra-High Vacuum Gas-Tightness in Cold-Sprayed Aluminum Coatings, Transport in Porous Media, 2022.

F. Niccoli , G. Scalet, V. Giovinco , C. Garion , C. Maletta, P. Chiggiato. Novel C-shaped SMA connectors for vacuum flanges: modelling and tests. Submitted to Shape Memory and Superelasticity.

F. Niccoli , C. Garion , C. Maletta, P. Chiggiato. NiTi Shape memory alloys pipe couplers: development and implementation. Smart Materials and Structures, Volume 31, Number 6, 2022.