

# WP 11.2

## “High-Efficiency Klystron Industrial Prototype”


I.FAST P1 review

09/02/2023

O Brunner / N. Catalan-Lasheras





# Objective

- Design and build an industrial prototype of the LHC klystron reaching 70% efficiency, in collaboration with THALES.
- In order to control the costs, the choice was made to retrofit the existing LHC klystrons, TH2167, with the aim of reusing some components (e.g. solenoid).
- Expected gain in DC to RF conversion efficiency: + 10 - 15 %





# Simulation and RF design

- RF design fully completed (bunching RF circuit, collector)
- Power transfer, bandwidth fined tuned and magnetic profile optimized



# Towards construction

- All interfaces reviewed and defined -> 'quick' plug and play replacement of the LHC klystrons
- Mechanical design of klystron parts is well underway
- **THALES' activities are impacted due to material shortages -> delays ..**
- The design review is foreseen end of March '23



3  
SRP - R&D THE LHC HEP CD - www.cern.ch - Rev 001 - 0019-06-18  
Modèle de l'imagerie 3D système / Template: 001/02-000-000-B-000

THALES



# Milestones, deliverables and schedule

- The project has accumulated important delays (9 months) -- missing resources & THALES
- Preliminary Design Review only took place early October
  - Design report (CDR) -- March/April '23
  - Factory acceptance test -- Q4 '23 -> delivery to CERN end '24 ..
- Additional delays are to be expected

