

# KEK PF-AR Test Beamline

17-21.Apr.2023

11th Beam Telescopes and Test Beams Workshop @ DESY

中村勇 (Isamu Nakamura) / 高工研 (KEK)

on behalf of ARTBL group

(KEK: Acc. Div., IMSS, IPNS and Universities: Nagoya, Kobe, Kyoto, Kyushu..)





12.Jan.2018 from the way to Fudo-Toge

- KEK (高工研)
  - 60km North-East of Tokyo (1.5 hour by train and bus)
  - IPNS, IMSS, Accelerator, ARL, J-PARC, QUP....
  - Many Accelerators, SuperKEKB, Linac, PF, PF-AR, ATF, J-PARC etc.
  - No Testbeam Facility after shutdown of Proton Synchrotron

# PF-AR



- PF-AR (Photon Factory Advanced Ring)
  - Photon Source Facility (High Energy X-ray)
  - former booster (8 GeV) of TRISTAN  $e^+e^-$  collider
- Maximum 6.5 GeV, 60 mA, Single Bunch (Run at 6.5 or 5 GeV, 50 mA, Top-up)
- 377m Circumference (1.26  $\mu$ s or 795 kHz)
- Four Experimental Halls North/East/West/South

# PF-AR South Exp. Hall (1)






Photo around PF-AR South Exp. Hall

## PF-AR South Exp. Hall (2)



Inside the Hall

# Beamline Overview




- Insert Carbon Target to Beam Halo
- Convert photon to  $e^+e^-$  with Copper converter
- Select Energy with Dipole(Bending) Magnet in the tunnel
- Transport beam through hole in the Concrete Wall

# Photos inside the Tunnel





# Carbon Target



- Graphene Target Foil ( $40\mu\text{m}$  Thick)
- Can see Target during machine operation




# Converter



- Water cooled Copper Converter (14mm Thick, adjustable)

# Beam Property (1)


from Beamline Simulation



- Assume  $I = 60$  mA,  $\tau_{\text{beam}} = 20$  hours
- Peak of Rate  $O(\text{kHz})$  around 2 GeV
- Beam Revolution  $\sim 800\text{kHz} \Rightarrow$  once per hundreds of turns
- Beam Rate depend on Lifetime (i.e., Target Position)

# Beam Property (2)

from Beamline Simulation



15


- roughly 8cm x 2cm beamsize
- Strong Correlation between Energy and Horizontal position

# History (1)



- Apr. 2020 Kick-off (total ~1 Oku Yen in 2 years Assigned)
- Mar. 2021 Floor Construction Completed
- Oct. 2021 Beamline Construction Completed (Authorization given)

## History (2)



- Oct. 2021 1st Run Target Insertion Test (No instability, No HOM, No evil)
- Mar. 2022 2nd Run First beam extraction (Rate Measurement)
- Jun. 2022 3rd Run Profile Measurement
- Nov. 2022 4th Run 6.5 GeV Top-up with established. (First “beamline user” invited)

# Some Preliminary Measurement Result (1) – Beam Rate

Rate Measurement by Kyushu Univ. Jun.2022

## Beam Rate


- 上流と下流の"シンチ+PMT"を各1組ずつ使用してビームレート測定。(Up1×Dn1)
- Up2, Dn2 は検出効率が低かったため、使用していない
- Up1 detection efficiency : 89.3%
- Dn1 detection efficiency : 89.2%
- Up1\*Dn1 detection efficiency : 79.7%

- **2.5~3.0GeVあたりがrate最大**



2022/07/18

PF-AR-TBL



- Very stable beam
- Beam Rate strongly depend on Target Positon
- seems Peak of rate slightly shifted to higher energy

# Some Preliminary Measurement Result (2) – Beam Profile

Profile Measurement by Kyushu Univ. Jun.2022

## Beam Position Scan

運動量は、2.0 GeV/c

想定

ビーム中心 X=0


鷺見さん想定座標 : Z + 500 mm

注意点

各2D Histは描画が被っている箇所がある。

解析結果

- ・高さ方向(Y)は想定通り見えている
- ・中心が想定よりずれている様に見える
- ・下流に行くほど高エネルギー側(左)にビームがよっている



Z = 1500

Z = 2500

Z = 3500


2022/07/15

PF-AR-TBL-Q

13

- Broader than expected both Horizontal and Vertical
- Beam center shifted by ~1 cm to High energy side

# Invited "User" during Commissioning Run



- Test Beamline is stable but not Yet "Officially" open to user
- Invited users with limited Support from Acc. for beamline staff to gain experience
- So far we accepted 7 Groups during Two Run Periods Nov.2022 – Mar.2023
- convinced beamline can co-exist with Photon Source (5 GeV needs extra study)



# Summery and Plan

- Construction of KEK PF-AR Test Beamline is completed
- Stable  $\sim 1$  kHz  $e^-$  beam obtained
- No bad effect to Photon Source seen so far
- Measured Rate and Profile different from expectaion
  - need More Precise Profile Measuremnet
  - need to adjust Magnet setting
- Performance already good enough for Test Beam Facility
- Need extra study (Top-up) at 5 GeV (2 days allocated in the next Run)
- Open to public from the Next Run for 6.5 GeV (Jun. 2023)

終

り