

# **ACCOR: What will change for operation and equipment groups?**

A. Radeva, on behalf of the ACCOR team, BE/CO  
IEFC, Controls session, 21.03.2011

- **ACCOR project state**
- **Impact of the new LHC schedule and LIU**
  - ACCOR's and equipment groups' concerns
  - ACCOR's proposal
- **ACCOR renovation process and its impact**
  - Formal approval process
  - Objectives
- **Impact of ACCOR on Operation**
  - Involvement in the renovation process
  - Post renovation impact, front-end diagnostic
- **Conclusions**



O  
B  
S  
O  
L  
E  
S  
C  
E  
N  
C  
E  
  
F  
U  
L  
L  
  
V  
E  
R  
T  
I  
C  
A  
L

**XMotif applications**

**GM front-end**

**Lynx OS**

**Obsolete hardware**

**VME RIO, CAMAC**

**Long-distance cables**

**ACCOR has very high priority for CO**

Injectors control system end of life (20 years old): impossible to add any new functionality

**Limiting:** for all applications (20 years) (e.g. InCA), no upgrade possible

**Critical:** blocking performance  
**Limiting:** no support, no evolution

**Critical:** procurement impossible  
no more single hybrid transceiver (30-years) **TE/EPC:** not blocking for PSB

**Critical:** procurement impossible 60 RIO spares (640 FECs)  
**Critical:** CPU blocking performance (7-13 years)

**Critical:** inventory required (EN/EL) (very old cables: 30 years)

## BE/CO components



## Some Equipment Groups

Specific applications

Specific FESA classes

no front-end renovation without low-level one


Low-level control

1. not planned yet for 2012 (no P+M)
2. busy with LHC for the last 2 years
3. 30-40-years old
4. ACCOR is not a priority

 **ACCOR cannot finish as planned in 2012**


# ACCOR Impact of New LHC Schedule

- Chamonix 2011 Outcome - LHC schedule




- Consequences

- Limited renovation can be done in 2012 (only non-critical)
- Gives 1 more year to some EQGs to advance with the low-level control and front-end renovation



- **ACCOR and equipment groups concerns**
  - decoupling of ACCOR, Consolidation and LIU projects
  - differing priorities of CO and EQGs
  - no visibility of ACCOR's P+M in the EQGs
  - LS1 might not be enough for some EQGs to finish renovating
- **ACCOR proposal**



### Actions:


1. **Combined coordination of priorities and planning (above the level of CO)**
2. **Visibility of P+M for ACCOR in EQGs**

*LHC proton chain  
Systems critical to maintain or  
blocking performance for operation*

- ACCOR project state
- Impact of the new LHC schedule and LIU
  - ACCOR's and equipment groups' concerns
  - ACCOR's proposal
- **ACCOR renovation process and its impact**
  - Formal approval process
  - Objectives
- Impact of ACCOR on Operation
  - Involvement in the renovation process
  - Post renovation impact, front-end diagnostic
- Conclusions




# ACCOR Strategy



- **LIU is a new major factor for ACCOR**
  - ACCOR adapting to LIU and EQGs priorities
  - MCC: from global renovation mode to one adapted to the EQGs

- **Necessity of formal approval by experience**
  - e.g. Linac 2 Software Interlock System Watchdog
  - e.g. CTF BPM (performance blocking operation)


R. Steerenberg's talk



- **Providing clear renovation planning per machine**
  - matching priorities of all active parties
  - allowing resource allocation
- **Improving the collaboration among the active parties**
- **Documenting the Injectors controls while renovating**
  - System Engineering Specification persisting beyond ACCOR
- **Giving clear picture what might be the impact of the delayed renovation on the delivery of beam to LHC**
- **Redefining the timeline of the project ACCOR**

- ACCOR project state
- Impact of the new LHC schedule and LIU
  - ACCOR's and equipment groups' concerns
  - ACCOR's proposal
- **ACCOR renovation process and its impact**
  - Formal approval process
  - Objectives
- **Impact of ACCOR on Operation**
  - Involvement in the renovation process
  - Post renovation impact, front-end diagnostic
- **Conclusions**

- **OP experts involvement during renovation**




- **Post renovation impact**

- validating the new solutions in operation
- getting used to the new instruments (hardware, front-end and application software)
- adapting to the new cooperative front-end responsibility model in place (SPS & LHC-like)


# ACCOR Front-end Responsibility Model

- Cooperative front-end responsibility model: strategy approved by CO3 in 2008




# ACCOR Front-end Responsibility Model

- **Cooperative front-end responsibility model: strategy approved by CO3 in 2008**



# ACCOR Front-end Responsibility Model

- Cooperative front-end responsibility model: strategy approved by CO3 in 2008



- OP concerns about the shared support - understandable




CCDB Extensions  
under discussion:

1. Group responsible
2. Expert list
3. Exploitation info
3. Renovation flag



Discussion involving  
all parties



e.g. DIAMON  
LASER

cfv-2013-a12gts1 (12GHZ TEST STAND FRONT-END)

General Details Host CMW

Ping Reboot SSH Menu

Responsible: **GROUP, TEAM, EXPERT?** Last update: 16:52:31 21/03/11

Exploitation info: BE/RF (first-line), CO Piquet (front-end), OASIS support (expert)

Missing jobs from transfer.ref: At least [TriggerSignal\_M] from server.init is missing

ACCOR's Goal



CCDB up-to-date as a  
source of exploitation info

- **New Exploitation Project is being launched in CO**

- **Reassessing the criticality of the Injectors controls in EQGs**
  - Controls renovation work (P+M) should be planned and be visible in APT by EQGs
- **ACCOR Adaptation to the LHC schedule and LIU**
  - Combined coordination of priorities and planning between LIU, EQGs and CO
- **Involvement of EQGs and OP in the approval process**
  - Every system renovation will be documented and approved by all parties using EDMS approval procedure
- **New cooperative front-end responsibility model**
  - EQGs become the first line of support for their front-ends
  - CO will be called by the EQG's first line support if the problem is CO related