# **Plans for the PS Injector**


K. Hanke for the LIU-PSB team and RCS task force



Plans for the upgrade of the PS injector are presented. The baseline scenario consists in a consolidation and upgrade of the existing PS Booster. The PSB upgrade can be broken up in the upgrade of the injection (H- injection from Linac4) and a possible energy upgrade of the machine from 1.4 to 2.0 GeV. As an alternative, a feasibility study for the replacement of the Booster by a Rapid Cycling Synchrotron (RCS) has recently started. Both scenarios are presented along with time lines and resource requests, notably for the first long LHC shutdown.

### 2 GeV Booster vs RCS






alternative locations outside the PS ring also being studied

IEFC Workshop 2011

### **PS Booster Upgrade**





2.1	Management			Klaus Hanke
	2.1.1	Overall coordination -	management activities (EVM, APT, EDMS, planning, resources)	Klaus Hanke, Deputy: Bettina Mikulec
	2.1.2	Safety		Nicolas Gilbert
	2.1.3	LARP collaboration		Eric Prebys
	2.1.4	Design Office		Ramon Folch
	2.1.5	Integration		Yvon Muttoni
	2.1.6	Optics Database		
	2.1.7	Layout Database		
		2.1.7.1	Equipment data	Sonia Bartolome
			Layout database model	Pascal Le Roux
	2.1.8	Consolidation and Shu		Nicolas Gilbert
	2.1.9	LIU-PSBU meetings		Thomas Hermanns
	2	2.1.9.1	2010	Thomas Hermanns
			2011	Thomas Hermanns
2.2	PSB Beam dynamic		2011	Christian Carli
2.2	2.2.1	Ring beam dynamics		Christian Carli
	2.2.2		Deinting	Christian Carli
<b>•</b> • •		Exploitation of Energy	raining	
2.3	Magnets			Antony Newborough
2.4	RF systems			Alan Findlay
	2.4.1	RF cavities & Power		Mauro Paoluzzi
	2.4.2	LLRF		Maria-Elena Angoletta
	2.4.3	PSB Transverse Dam	per	Alfred Blas
	2.4.4	RF Controls		Andy Butterworth
2.5	Power Convertors			
	2.5.1	Booster injection		David Nisbet
	2.5.2	2 GeV upgrade		Serge Pittet
	2.5.3	RCS studies		Serge Pittet
2.6	Beam instrumentati	ion		Jocelyn Tan
2.7	Beam Intercepting D	Devices		Oliver Aberle - Alternate Alessandro Massi
2.8	Vacuum System			Edgar Mahner
2.9	LINAC4 to PSB tran	sfer line and PSB injection	on systems	
	2.9.1	Beam dynamics studie	es	Christian Carli
	2.9.2	Injection system equip		Wim Weterings
2.10	PSB Extraction syst	em and PSB-PS transfer	line	
	2.10.1	Beam dynamics studie	es	Christian Carli
	2.10.2	Extraction and transfe	r line equipment	Jan Borburgh
2.11	Controls			Steen Jensen
2.12	Electrical Systems			Davide Bozzini, Slawomir Olek
2.13	Cooling and Ventilat	tion		Mauro Nonis
2.14	Installation, Transpo			Ingo Rühl
	2.14.1	Transport and handling	a equipment	Ingo Rühl
	2.14.2		g services (incl. feasibility studies)	Caterina Bertone
2.15	Civil Engineering		5 · · · · · · · · · · · · · · · · · · ·	Luz Anastasia Lopez-Hernandez
2.16	Radiation Protection	h		Markus Widorski
	2.16.1	General RP		Markus Widorski
	2.16.2	RP studies		Markus Widorski
2.17	Interlock systems			Bruno Puccio
2.17	2.17.1	WIC		Pierre Dahlen
	2.17.2	BIC		Benjamin Todd
2.18	Alarms			
2.10		loore		
	Access Systems - D	0015		Tabiaa Dabara
2.20	Survey	Oneration		Tobias Dobers
2.21	Commissioning and	Operation		Bettina Mikulec
2.22	Dismantling			

**CERN** CH-1211 Geneva 23 Switzerland



PSB Up	grade Working Group Document No.
	1082646-0003
CERN Div./G	roup or Supplier/Contractor Document No.
	BE-OP
	EDMS Document No.
	1082646 v.3

The **PSB Upgrade** Working Group

DATE: 2010-09-23

**Feasibility Study** 

#### PS BOOSTER ENERGY UPGRADE FEASIBILITY STUDY FIRST REPORT

#### Abstract

This document summarises a survey of the CERN PS Booster systems with regard to a possible energy upgrade to 2 GeV. Technical solutions are proposed along with a preliminary estimate of the required resources and the time lines.

Prepared by:	Checked by:	Approved by:
Klaus Hanke BE-OP Klaus.Hanke@cern.ch Oliver Aberle Alfred Blas Jan Borburgh Davide Bozzini Marco Buzio Christian Carli Tobias Dobers Alan Findlay Leandro Fernandez Simone Gilardoni Thomas Hermanns Edgar Mahner Bettina Mikulec Antony Newborough Mauro Nonis Slawomir Olek Thomas Otto Mauro Paoluzzi Serge Pittet Rende Steerenberg Ingo Ruhl Giovanni Rumolo Jocelyn Tan Davide Tommasini	Simon Baird Oliver Bruning Jean-Paul Burnet Edmond Ciapala Francois Duval Doris Forkel-Wirth Eugenia Hatziangeli Erk Jensen Jose Miguel Jimenez Rhodri Jones Mike Lamont Roberto Losito Volker Mertens Mauro Nonis Thomas Otto John Pedersen Lucio Rossi Ingo Ruhl Marc Tavlet	Steve Myers Roland Garoby Frederick Bordry Paul Collier Roberto Saban

• double checked the arguments presented at the 2010 Chamonix workshop - confirm that an increase in beam energy will facilitate injection of high-brilliance and high intensity beams into the PS

• survey of all PSB equipment and systems with regard to an energy increase - did not find any showstopper

- identified PSB equipment and systems that need to be modified or exchanged in order to operate at 2 GeV beam energy
- propose technical solutions for these items, along with a cost estimate and schedule
- identified items, which were already accounted for in the consolidation program disentangled these items from the budget estimate for the energy upgrade

• we propose a project schedule, which is in line with the long-term LHC planning

Distribution List: R. Heuer


#### KH IEFC Workshop 2011

### Expected Performance Gain with 2 GeV [G. Rumolo, LIU Day, Dec 2010]



- injection at 2GeV lowers space charge effect by a factor (βγ<sup>2</sup>)<sub>2GeV</sub>/(βγ<sup>2</sup>)<sub>1.4GeV</sub>≈1.63
  → can inject beams ~65% more intense keeping the same space charge tune spread as now
- if we assume to conserve the longitudinal emittance (e.g., 1.3 eVs, LHC beam h=1), the bunch at 2GeV will be 33% shorter at the exit of the PSB, which would in principle limit the above gain to less than 40%; however, the PS bucket acceptance at injection also increases by 50%, which allows for injection of larger longitudinal emittances, recovering the desired gain (50% larger longitudinal emittance required)
- larger transverse emittances acceptable at the PS injection, if the final transverse emittances to the LHC are the same? Unlikely, as the previously PSB specified transverse emittances have meanwhile become the "nominal" LHC emittances!

ightarrow at least 65% intensity increase (within constant emittance) expected



### LHC Beams from the PSB with L4 and 2 GeV [B.Mikulec]



User	Description	Harmonic at extr.	PSB rings used	Intensity per ring	rms emittance at extr. [mm mrad]	Bunch length at extraction [ns]	Extr. energy [GeV]
LHC25A/B	25 ns LHC beam (double batch PS transfer)	1	1-4 and 3+4 (2 extractions)	2.43E12 (ultimate) and smaller	hor.: ≤2.5 vert.: ≤2.5	180	2
LHC25	25 ns LHC beam (single batch PS transfer)	2+1	2-4	3.25E12 (nominal) and smaller by factor 20	hor.: ≤2.5 vert.: ≤2.5	140	2
LHC50	50 ns LHC beam (single batch PS transfer)	2+1	2-4	for ultimate expect also 2.43E12 (2 bunches/ring)	hor.: ≤2.5 vert.: ≤2.5	140	2
LHC75	75 ns LHC beam (single batch PS transfer)	2+1	2-4	variable, but smaller than 25 and 50 ns	hor.: ≤2.5 vert.: ≤2.5	140	2
LHCPILOT	early LHC pilot beam	1	3	0.005E12	hor.: 2.5 vert.: 2.5	85	2
LHCPROBE	early LHC probe beam	1	3	0.005-0.023E12	hor.: ≤1 vert.: ≤1	70	2
LHCINDIV	individual bunch LHC physics beam	1	1-4	0.023-0.135E12	hor.: ≤2.5 vert.: ≤2.5	80-85	2

B. Mikulec / Commissioning

emittance values as specified today - can be reduced with Linac4

### FT Beams from the PSB with L4 and 2 GeV [B.Mikulec]

User	Description	Harmonic at extr.	PSB rings used	Intensity per ring	rms emittance at extr. [mm mrad]	Bunch length at extraction [ns]	Extr. energy [GeV]
CNGS	beam for CNGS target (until end of 201 <i>5</i> ?)	2	1-4	$0.6-8E12 + \sim 45\%$ increase to reach target limit	hor.: ~10 vert.: ~8 ~12/7 with MTE	180	2
SFTPRO	SPS fixed target beam	2	1-4	< <mark>6E12</mark> – would an increase be desirable?	crease be vert.: ~5-6		2
AD	beam for AD target	1	1-4	4E12 (currently)	hor.: ∼8 vert.: ~6	190	2
TOF	nTOF beam	1	1-4	<9E12 (currently)	hor.: ~10 vert.: ~10	230	2
EASTA/B/C	beam for the PS EAST area targets	1	3 (+2)	~0.1-0.45E12	hor.: ~3 vert.: ~1	150	2
NORMGPS NORMHRS	ISOLDE GPS/HRS target beams	1	1-4	up to 10E12 (currently – increase with HIE- ISOLDE?)	hor.: ≤15 vert.: ≤9	250	1 or 1.4
STAGISO	ISOLDE staggered beam for special targets	1	2-4	<3.5E12	hor.: <8 vert.: <4	230	1 or 1.4

B. Mikulec / Commissioning

maximum intensity fixed to 1.4E13 p/ring (5.6E13 total) due to magnet cooling and RF limitations in principle Linac4 could deliver up to 1.6E14 ppp with 65 mA current and 400  $\mu$ s pulse no user known to us for such intensities

### 2 GeV Booster: Schedule



ID		Task Name	Duration	Start	Finish											,				IMP
	0	Task Name	Duration	Start		2008	2009		03 04 0	2011	2012	2013 Q4 Q1 Q2 Q3	201		2015	2016		017	2018	///
1	-	Operation and Shutdowns	2025 days	01.02.10			** 81 82 80								102 00 04	1 82 85	11		1 02 00 0	////
2		PSB Proton Operation	1764 days	01.02.10	31.10.16			<b>~</b>	<u> </u>		<u> </u>					-	7			
3		Proton Operation 2010	211 days	01.02.10	22.11.10															
4		Proton Operation 2011	214 days	29.01.11	21.11.11				9		h									
5		Proton Operation 2012	196 days	01.02.12	31.10.12							<b>D</b>								
6		Proton Operation 2014	89 days	01.07.14	31.10.14						T									
7		Proton Operation 2015	195 days	02.02.15	30.10.15									<u> </u>						
8		Proton Operation 2016	196 days	01.02.16	31.10.16												<b>)</b>			
9		PSB Shutdown	1814 days	23.11.10	31.10.17							-								
10		Xmas Break 2010/11	49 days	23.11.10	28.01.11				<u> </u>											
11		Xmas Break 2011/12			31.01.12						<u>ل</u>									
		Shutdown 2013/14 (LS1)			31.03.14															
		Xmas Break 2014/15			30.01.15									<b>P</b>						
		Xmas Break 2015/16	· · ·		29.01.16											2				
15		Shutdown 2017 (LS2)			31.10.17															
16		LHC Ion Operation	1586 days						- <b>P</b>					•	•					
17		lon Run 2010			06.12.10				0											
18		Ion Run 2011			12.12.11						2	. <b></b>								
19		Ion Run 2012			30.11.12							0 <sup>4</sup>		4						
20		lon Run 2014			30.11.14									Ø	<b>↓</b>					
21		lon Run 2015			30.11.15										0		<b>.</b>			
22		lon Run 2016	22 days	01.11.16	30.11.16												0'			
23	-																_			
24	11	WP 1 Beam Dynamics	1348 days	01.09.11	27.10.16			<u> </u>									-			
28	_																			
29	-	WP 2 Magnets	1923 days?	19.07.10	24.11.17				-											
60		MD2 DE Contene	4500	04 00 44	20.00.47															
61		WP3 RF System	1523 days?	01.09.11	29.06.17													<b>Y</b>		
73		WP 4 Beam Intercepting Devices	664 days	01 00 11	14.02.14															
81		WP 4 beam intercepting bevices	004 days	01.09.11	14.05.14								- T							
82		WP 5 Power Converters	1565 days	01 09 11	28 88 17					_										
118		WE SPOWER COnverters	1505 Gays	01.05.11	20.00.17															
119		WP 6 Vacuum System	1551 days	22 11 11	31 10 17															
125		in o vacuum system	1551 days	22.11.11	51.10.17													<b>X</b>		
126		WP 7 Beam Instrumentation	1437 days	01.09.11	01.03.17															
129																	Ť			
130	-	WP 8 Commissioning and Operation	1917 days	01.10.10	31.01.18														,	
134	-																	İ		
135	-	WP 9 PSB Injection	1652 days?	01.01.08	25.04.14	<del>, — –</del>														
227																				
228		WP 10 Extraction and Transfer	1652 days	01.09.11	27.12.17					<b>—</b>										
274																				
275	11	WP 11 Controls	506 days	17.03.14	22.02.16								<b>—</b>							
282																				
283		WP 12 Electrical Systems	1447 days	01.09.11	15.03.17					<b>—</b>										
288																				
289	11	WP 13 Cooling & Ventilation	681 days	01.10.14	10.05.17															
306																				
307	11	WP 14 Radio Protection, Safety	1332 days	27.10.11	30.11.16															
314																				
315	11	WP 15 Transport and Handling	1305 days	02.01.12	30.12.16															
329																				
330	11	WP 16 Survey	1602 days	13.12.11	31.01.18									_					,	
	-			1						1 I I			1 1 1 1	1 1	1 I I	1 1 1		1 1 1		

### IEFC Workshop 2011

### 2 GeV Booster: Schedule

### LS1:

- beam dump/beam stopper
- PSB injection
- transport/handling facilities

### LS2:

- magnet upgrade
- MPS installation and commissioning
- upgrade kicker/septa transfer line
- upgrade electrical system
- upgrade cooling/ventilation



### 2 GeV Booster: Budget

PSB
2.0

		S	pending	Profile (	subtract	ed conso	lidation	items a	nd Linac	4 expen	ses)	
	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	total
Total Beam Dynamics	0	0	10	10	10	10	10	0	0	0	0	50
Total Magnets	20	0	162.5	62.5	65	655	1080	90	0	0	0	2135
Total Magnetic Measurements	0	20	40	60	60	60	60	60	0	0	0	360
Total RF	0	0	0	0	0	0	0	0	0	0	0	0
Total Beam Intercepting Devices	0	25	41	50	50	25	25	25	0	0	0	241
Total Power Converters (PSB)	0	0	765	545	5670	6300	1560	1160	0	0	-2000	14000
Total Power Converters (Injection)	0	330	1045	105	0	0	45	45	0	0	0	1570
Total Vacuum System	0	0	387	281	0	0	0	0	0	0	0	668
Total Beam Instrumentation	0	0	0	57	0	0	0	0	0	0	0	57
Total Commissioning	0	0	0	0	0	0	0	75	75	0	0	150
Total Injection	0	1000	1000	1500	2125	1500	1000	154	0	0	0	8279
Total Extraction, Transfer	0	0	0	360	996	748	444	0	0	0	0	2548
Total Controls	0	0	0	0	0	0	0	500	0	0	0	500
Total Electrical Systems	0	0	1100	500	0	0	0	100	0	0	0	1700
Total Cooling & Ventilation	0	0	0	0	0	0	100	900	0	0	0	1000
Total RP and Safety	0	0	0	0	0	0	0	0	0	0	0	0
Total Transport and Handling	0	0	0	25	25	0	30	200	0	0	0	280
Total Survey	0	5	0	25	5	5	0	10	0	0	0	50
Total per Year	20	1380	4550.5	3580.5	9006	9303	4354	3319	75	0	-2000	33588
Integrated Budget	20	1400	5950.5	9531	18537	27840	32194	35513	35588	35588	33588	

33588 = 54776,5 (total) – 20348,5 (cons.) – 840 (already paid by L4)

<u>consolidation</u>: items that are required for the 2 GeV to work (e.g. Booster RF, dump, ...) <u>Linac4 injection</u>: transferred from Linac4 project to LIU-PSB, added to budget, partly paid → entered into MTP

### since Chamonix 2011:

- RCS option to replace the Booster
- would make both consolidation and upgrade obsolete
- work on 2 GeV Booster suspended
- RCS feasibility study and rough cost estimate launched (conclusions by summer 2011)
- if found competitive, more detailed study

RCS task force set up to reinforce the Booster Upgrade WG investigate general parameters (parameters, lattice, size, apertures, location) look only at potential cost drivers: magnets, power, civil engineering.

## **RCS: Suggested Parameter Table**

Energy range	160 MeV to 2 GeV					
Circumference	(200/7) π m ≈ 89.76 m		assume shortest option			
Repetition rate	~10 Hz					
RF voltage	60 kV	h =	3 to fill 18 out of 21 PS bucke			
Harmonics	h = 2 or 3	h =	2 to fill 12 out of 14 PS bucke			
Frequency range	3.48 MHz (h=2 at injection) to 9.5 MHz (h=3 at ejection)					
Beam parameters for LHC (for lower emittances scale down intensity accordingly)	Intensity: up to 12×2.7 10 <sup>11</sup> protons/cycle Transv. emittance: $\epsilon_{rms}^* \approx 2.5 \ \mu m$ Long. emittance: $\epsilon_l < 12 \times 0.27 \ eVs$ (determined by acceptance for most cases)					
Lattice	FODO with 15 cells and 3 periods, 4 cells in arc, straight with one cell					
Tunes	4 < Q <sub>H,V</sub> < 5					
Relativistic gamma at transition	~4					
Bending magnet filling factor	56 %					
Maximum magnetic field	1.16 T					

C. Carli, Chamonix 2011

### **RCS: Beams & Parameters**

#### LHC beams:

2.7E11 protons/LHC bunch (estimate for 2 GeV Booster with L4, M.Giovannozzi Chx. 2010)  $\rightarrow$  have to deliver intensity for 12 LHC bunches per cycle  $\rightarrow$  12 x 2.7E11 ppp

#### high intensity beams:

assume maximum 1E13 ppp

to be iterated with the high-intensity users ISOLDE, CNGS, ...


#### machine parameters:

starting point Chamonix 2011 table, lattice and magnetic cycle have been iterated since (C. Carli)

lattice  $\rightarrow$  beam size  $\rightarrow$  aperture  $\rightarrow$  magnet model  $\rightarrow$  main power supply


should allow to get a rough estimate for feasibility and cost drivers; no details. must not forget modifications to Linac4 in order to run at 10 Hz

### **RCS: Location inside PS (Chamonix Suggestion)**



A. Kosmicki, L.A. Lopez-Hernandez

### **RCS: Location inside PS**




- beam Lines cross twice the PS
- stray fields expected to be an issue


- A. Kosmicki, L.A. Lopez-Hernandez
- passing under the PS would have to be very deep, estimated minimum 10 m (involving pits ~25 m below ground level)

IEFC Workshop 2011

### **RCS: Location Parking Bldg 513**



### **RCS: Suggested Location closer to L4 (Roundabout Scenario)**



• PS injection from outside

KH


- beam lines do not cross the PS
- re-use L4-PSB transfer line, must re-assess
- from an RP point of view, but looks feasible

B.Goddard, A.Kosmicki

IEFC Workshop 2011

DEATI

### **RCS: Comparison of all Locations**



### Summary

### Booster Energy Upgrade well advanced

- transformed from a task force into a project
- Linac4 injection has been added (from L4 project), PS injection has been transferred (to LIU-PS project)
- presented at Chamonix 2011, ready to go
- budget entered in MTP
- since Chamonix 2011 on hold, apart from the H- injection where work continues (in particular in view of a possible connection during LS1)

### RCS option being looked into

- looking only into key issues, parameter space, civil engineering, magnets, power, RP
- Booster Upgrade Working Group reinforced
- feasibility and rough (!) cost estimate by early summer