


SAFETY MANAGEMENT OF SHUTDOWNS

David Mcfarlane
Superintendent for SPS
EN/MEF/ABA

SPS Statistics



- ▣ 6.9km of accelerator tunnel.
- ▣ 2.5km of transfer tunnels.
- ▣ 7 main access points.
- ▣ Over 20 surface buildings.
- ▣ 10 pits and 15 lifts.
- ▣ Access to the underground areas is only possible for very short periods of time.

2010/11 SPS Shutdown Statistics

- ▣ Although the technical stop lasted 11 weeks (from the 6th December 2010 until 21st February,) general access for works was only possible for 4 weeks
- ▣ 334 separate jobs requested.
 - 17 required *VICs* (*Visite d'Inspection Commune - Joint Inspection*)
- ▣ Works coordinated between multiple groups and departments:
 - EN (EL/CV/HE/STI/MEF)
 - BE (APB/BI/RF/OP)
 - TE (MSC/EPC/VSC)
 - GS (SEM/ASE/SEE)
 - DGS (RP)

Safety related works

- ▣ Electrical Safety checks
- ▣ Area safety visits
- ▣ Lighting inspections and maintenance
- ▣ Lift maintenance
- ▣ RP surveys
- ▣ Visits by the fire brigade to improve familiarisation with areas
- ▣ Fire and smoke detection maintenance
- ▣ Fire extinguisher maintenance
- ▣ Access control tests
- ▣ Toilet cleaning and maintenance.

Safety Documents

- ▣ PPSPS (Plan Particulier de Sécurité et de Protection de la Santé)
 - ([EDMS 801899](#))
- ▣ SPS general coordination plan
 - ([EDMS 1099003 - rev. 2010](#))
- ▣ Visitors in the controlled zone of the SPS
 - ([EDMS 346813](#))

Safety Courses

- ▣ Biocell training
- ▣ Electrical safety awareness
 - *Access into the SPS can only be granted to persons who have followed this web-based course.*
- ▣ General CERN safety courses (level 1,2 & 3)
- ▣ RP course.
 - (NO dosimeter without this course)
- ▣ EDH access request and authorisation


Personal Safety Equipment

- ▣ Hard hat
- ▣ Lamp/torch
- ▣ Passive dosimeter
- ▣ Electronic dosimeter
- ▣ Biocell
- ▣ Safety shoes

And your Buddy. *(Do not work alone !)*

SPS Safety Equipement

- ▣ Fire extinguishers
- ▣ Smoke detection systems
- ▣ Fire detection systems
- ▣ Sprinkler systems
- ▣ Evacuation alarms
- ▣ Emergency **RED** telephones
- ▣ Intercom system
- ▣ Controlled access systems
- ▣ Clearly marked evacuation routes





Safety Help and Tools

- ▣ People
 - TSO - (*Territorial Safety Officer*)
 - Safety Coordinator
 - Superintendent / Technical coordinator
 - CCC operators
 - DSO - (*Departmental Safety officer*)
 - GLIMOS (*Group Leader In Matters of Safety*)
- ▣ Visits
 - VICs - (*Visite d'Inspection Commune - Joint Inspection*)
 - Regular on site visits
- ▣ Permits
 - Authorisation to work
 - Consignation (Isolating of electrical equipment)
 - Fire permit
 - IS37 (*Disabling all or part of the system generating a level 3 alarm.*)
- ▣ Weekly planning meetings
 - Vital that key personnel attend
- ▣ Website (*up to date planning*)
 - <http://sps.web.cern.ch/SPS/>

Communication is key!


- ▣ Notice boards
- ▣ E-mails
- ▣ Meetings
- ▣ Telephone calls
- ▣ Face to face conversations
- ▣ RP surveys
- ▣ SPS coordination website
- ▣ De-Briefing meeting
 - Lessons learned and how can we improve for next time

When it comes to safety, you can never have too much information.

Example of how this works in Practice


Changing of 1 magnet in the SPS

☐ Magnet change campaign (ACCESS VIA BA3)	2.88 days	Jeremie Bauche	TE/MSC
☐ Cooling water circuit 5- & 5+ (main magnet) PURGED	2.88 days	Bill Bannister	EN/CV
☐ Magnet 51510 (QD)	2.88 days	Jeremie Bauche	TE/MSC
Vent vacuum circuit 520	2 hrs	Paolo Chiggiano	TE/VSC
Cut bus bars	10 mins	Jeremie Bauche	TE/MSC
Disconnect magnet from Vacuum system	30 mins	Paolo Chiggiano	TE/VSC
Magnet exchange (Transport)	4 hrs	Caterina Bertone	EN/HE/HH
Magnet alignment (Survey)	0.5 days	Patrick Bestmann	BE/ABP
Reconnect magnet to vacuum system (Vide)	30 mins	Paolo Chiggiano	TE/VSC
Pump vacuum sector 520	12 hrs	Paolo Chiggiano	TE/VSC
Re-braze magnet to bus bars	2 hrs	Jeremie Bauche	TE/MSC
Refill water system	0 days	Bill Bannister	EN/CV





- Coordination of work between 5 separate groups
- Breaking of the vacuum
- Cutting of cooling water systems
- Isolating of main power supplies
- Transportation of a large magnet around the SPS
 - For the main dipoles (MBA's and MBB's): w- 80cm x h- 65cm x l- 6.5m ; weight 18 tons
 - For the main quadrupoles (QD's and QF's): w- 80cm x h- 80cm x l- 3.5m ; weight 8.5 tons

SPS Safety Chains



Changing a magnet in the SPS

- ▣ Preliminary meeting
 - Ensure that all groups are aware of what they need to do and when.
 - Coordinate with planning to find the best time in the schedule to do the work.
 - Identify any radiation issues. (*How hot is the area being worked in?*)
 - Identify any safety issues. (*Arrange a VIC if necessary*)
 - Ensure that all equipment to be used has been fully tested and certified. (*lifting equipment etc*)
- ▣ Inform all parties working in the affected areas of the planned work
 - E-mail
 - Weekly planning meeting
 - Notice boards in the affected areas
- ▣ Ensure that the planning is respected!!



Completion of work

- ▣ Once work has been finished, it is imperative:-
 - That the area is clean and has been made safe.
 - That the coordination team and everyone involved is informed.
 - That all permits and consignations are signed off.
 - That the planning is updated.

Handing the SPS back to Operations

EDMS N° : 1052987

BEAM PERMIT SPS / 2011 Beam is permitted once all sections have been completed correctly and signed

ZONE : Main ring and transfer lines TT10, TT20, TT40 and TT60

<p>1 - Shutdown works complete: The EM-MEF must be in the 'ready to start' position. The safety and control functions are operational. Any bypass or strap of EIS must be properly reported. Please note any exceptions or additional remarks:</p>	<p>Superintendent's signature</p>	<p>Name: Superintendent EN/MEF responsible of the zone or GLIMOS responsible of the experience Signature: Date:</p>
<p>2 - Access system Functionality: The access system for the machine/zone is put in operation. The safety and control functions are operational. Any bypass or strap of EIS must be properly reported. Please note any exceptions or additional remarks:</p>		<p>Name: GS-ASE-AC Signature: Date:</p>
<p>3 - Patrol The area is Please note</p>	<p>SPS Ring Patrol EPC start up checks Cold check out tests DSO Tests</p>	<p>Name: Patrol leader or Shift Leader on duty in CCC Signature:</p>
<p>4 - BE-DS The purpose procedures. Please note</p>	<p>Minimum 2 weeks</p>	<p>Name: Patrol leader or Shift Leader on duty in CCC Signature:</p>
<p>5 - Radiation protection The DGS-RP technician checks the absence of unnecessary material in the zone and the radiation shielding are in place. Radiation sign posting is in place. Limitations on beam operation can be expressed in accordance with reduced shielding. Radiation monitoring system (measurement, alarm functions and alarm transmission) is operational. Please note any exceptions or additional remarks :</p>		<p>Name: DGS-RP-AS or designee Signature: Date:</p>
<p>6 - Final Authorisation At this point the machine is Please note any exceptions or additional remarks :</p>	<p>Operations Group leader signature</p>	<p>Name: Group Leader BE-OP or deputy Signature: Date:</p>
<p>7 - Beam Permit suspension Date of suspension: Date of re-activation:</p>	<p>7 - Beam Permit cancellation <input type="checkbox"/> Cancellation during the run Date of cancellation: <input type="checkbox"/> Cancellation at the end of the run (The beam is stopped and all safety equipment are consigned)</p>	<p>Name: Suspension by any qualified person / Annulation by Group Leader BE-OP or Deputy Group :</p>
<p>Explanation or related documents :</p>		<p>Signature: Date:</p>

Final remarks

- ▣ Safety is not there to make it harder or more difficult for you to do your work.
It is there to ensure that your work is done without danger to yourself, others or to the equipment or the accelerator itself
- ▣ We want you to go home at the end of the day in the same condition you arrived, free from harm, injuries or work-related illness.
- ▣ **EVERYONE** is responsible for safety!