Safety Consolidation in and around the Injector chain*

S Baird

On behalf of

R Brown, V Chohan, J-L Duran-Lopez, B Linseisen, R Steerenberg, F Szonsco (for PS Safety review) T Otto & the PS Radiation Working Group (PSRWG) P Bonnal (Risk analysis procedures)

* Safety Consolidation at the PS

Safety Consolidation at the PS



Safety Consolidation at the PS

- In view of the decision to keep the PS as LHC Injector for 25 years*
- PS Safety review (F Szoncso)
 - Snapshot of the situation today
 - Aiming to identify Hazards
- Risk analysis (P Bonnal)
 - Establish a prioritized action list for risks identified by the PS Safety Review
- Input from the PS Radiation Working Group (T Otto)
 - Evaluation of beam intensities and loss rates
 - Identification of main radiation hazards
 - Impact on operations & tunnel interventions
 - Recommendations

* Decided after Chamonix 2010

PS Safety review

• Mandated by S Myers & R Trant to:

- 'establish the facts related to the safety of the CERN PS and assess the safety compliance of the PS in view of it's long-term operation as LHC injector'
- Members: EN/MEF, HSE, BE/OP, TSO
- Aim to identify hazards whilst avoiding any prejudgment
 - Groups involved in the operation, maintenance, modification and emergency handling at the PS were contacted individually
 - Standard questionnaire plus specialized questions
 - Report the situation as it is today (as seen by those intervening in the tunnel)
- The results can be found in the CERN Proton Synchrotron Safety Review
 - https://edms.cern.ch/document/1119511/1

PS Safety Review: Teams contacted

- Civil Engineering, buildings, tunnel structures
- Services: Tunnel cooling and ventilation, Electricity, Cabling, Transport
- Beam related equipment: Vacuum, RF, Beam instrumentation, Kickers & Septa, Magnets
- Safety systems: Interlocks, Access and Safety systems, Fire Brigade, Environment
- Shutdown Coordination

PS Safety Review: Hazards indentified 1/2

- 41 potential hazards identified including...
 - Asbestos pipe insulation
 - Safety communication for personnel intervening in the tunnel (CERN and external contractors)
 - Leakage of air from the tunnel, smoke extraction system has no filter, problems to maintain constant pressure differentials in the tunnels
 - Possibility of corrosive smoke in case of fire (cables, batteries...)
 - No flooding warning interlock in presence of pressurized water systems
 - HV is present on ion pumps permanently (during access)
 - Many of the procedures for testing magnets and other elements rely on expert knowledge and not written instructions

PS Safety Review: Hazards indentified 2/2

- Cable deterioration due to radiation, overfilled cable trays & unidentified cables
- Lack of building/tunnel maintenance (leaks, water infiltrations)
- Some walkways and stairs are unsuitable and difficult to use
- Tunnel concrete floor slabs damaged
- The AUG layouts and the action of individual buttons are not clear
- Few systems have individual emergency stop buttons (not coherent approach)
- Lack of safety exercises and evacuation drills
- Radiation issues are covered by the PSRWG

Prioritizing risk mitigation measures



Possible measures that will most improve outstanding safety issues → Top of the list Actions that are to be taken within budgetary limits

Evaluation and analysis phase

- Identify all safety risks from the hazards listed in the PS Safety Review Report
- **Evaluate** those risks from to 2 perspectives:
 - Probability of occurrence
 - Impact on health, safety and environment
- $Risk = P \times I$

- Analyze those risks:
 - List the existing mitigation measures (already in place):
 - Preventive measures (probability)
 - Protective measures (impact)
 - List possible additional mitigation measures
 - Estimate their feasibility (cost, manpower, schedule...).

Evaluation and analysis phase

Review existing mitigation measures, i.e. those already in place

(risks are weighed taking these measures into account) 1st ranking (before new measures are implemented) sorting = from highest risk to lowest risk

Identify additional mitigation measures

 (incl. their cost estimate, the manpower required, their feasibility from a schedule point of view...)
 Risks are then re-weighed considering the implementation of these additional mitigation measures
 2nd ranking (after new measures are implemented) sorting = from highest risk improvement to lowest.

PSRWG: PS Beam Intensities and Loss

The PSRWG evaluated beam intensities and loss rates for 2010 operation of the PS. This allowed a correlation between beam loss and the observed radiation hazards

Calculated from intensity & loss

Average/supercycle

	Intensity	Relative Loss	Loss rate	
Injection	8.2 10 ¹² s ⁻¹	6 %	5 10 ¹¹ s ⁻¹	
Extraction (high.int. beams)	6.4 10 ¹² s ⁻¹			
СТ		10 %	6.4 10 ¹¹ s ⁻¹	
MTE		1 – 2 %	Up to 1.3 10 ¹¹ s ⁻¹	

Not including nTOF, LHC, EAST HALL

Main Radiation Hazards in PS

Not measured today

Hazard	Main Locations	Concern	Mitigation*
Air activation	Whole PS, numerous pathways	Release to environment, radiation dose to workers and public	Assessment to demonstrate negligibility
Stray radiation	Route Goward Downstream of South-hall	External irradiation of personnel on- site and of public	Shielding
Activation of material in the tunnel	SMH16 (MTE) Downstream SEH31 (CT)	External irradiation of workers during access	Allow decay time

* other than reduction of beam loss

Activation: Ambient dose rates **limit** the possibility for urgent interventions

E.g. Replacement of SMH16



14 days after accelerator stop: $H^*(10) \approx 20 \text{ mSv h}^{-1}$ \downarrow Septum exchange possible without breaking internal RP rules

Solutions:

- Hardware upgrade to allow remote handling
- Wait longer (unrealistic due to logarithmic decay characteristics)
- Reduce and/or constrain beam loss

PSRWG Recommendations (1)

Air activation

- Cost an upgrade of ventilation allowing proper assessment of releases, in terms of CHF and of person-mSv
- Take an informed decision

Stray Radiation

- Homogenise radiation shielding on top of PS, allowing for probable intensity upgrades: Linac 4 and 2 GeV PS Booster at full capacity
- + 180 cm earth downstream of South-Hall
- +180 cm concrete on Route Goward

PSWRG Recommendations (2)

- Accelerator Activation
 - Reduce loss focalized on SMH16 by various means (dummy septum, barrier buckets, ...)

Introduce a beam loss constraint for routine operation:

- < 10¹⁰ s⁻¹ at any location (without septa)
- < 10¹¹ s⁻¹ at septa
- $< 10^{12} \text{ s}^{-1} \text{ overall}$
- These constraints allow major interventions after a breakdown (magnet or septum exchange) with 14 days decay time

Actions for the future

- Hazards identified in the PS Safety review
 - Risk analysis to assess the hazards identified and produce a set of prioritized actions
 - Implement inside an Injector Consolidation program?
- PSRWG
 - Modify ventilation system to allow measurement of air activation
 - Additional shielding requirements identified
 - Remote handling for certain elements?
 - Reduce localized losses with "technical or beam" solutions
 - Use a beam loss constraint rather than an extracted intensity limit



Questions asked 1/3

- Do you believe that your equipment is operationally safe today?
- What risk does your equipment pose for the safe operation of the PS?
- Does your equipment pose any safety issue to other personnel?
- Do you believe your equipment will degrade in terms of safety and will require replacing or even redesigning?
- How could your equipment be improved to make it safer than it is today?
- When making interventions on your equipment, do you consider the procedures you follow today are safe?
- To make your interventions safer, what procedures should be improved?

Questions asked 2/3

- Do you consider the PS tunnel to be a safe working environment?
- What elements of the tunnel do you consider to be either unsafe or a potential risk to your health and safety?
- Do you consider any other PS hardware to be unsafe?
- Are you aware of any environmental issue in the PS that should be addressed?
- Are you and your team fully aware of the emergency equipment and procedures while working in the tunnel?
 - Emergency exits?
 - Emergency lighting?
 - Emergency phones and numbers?
 - Emergency stop buttons (AUG)?
 - Fire fighting equipment? Extinguishers, what type and how to use them?

Questions asked 3/3

• Specific questions....

- Can beam losses affect your equipment?
- Does induced radio-activity affect interventions on your equipment?
- Is your equipment protected by specific interlocks?
- Do you use/store dangerous chemicals/materials
- Do you have dangerous systems which must remain on during a shutdown period?
- Is the tunnel equipped with smoke extractions systems?
- Do your equipment present a particular fire risk?
- How is the AUG system laid out?

•••••