



ALBA Synchrotron Light Source

Since Sept-2021: Pulsed elements at Linac Group

- *Operation and Maintenance of ALBA pulsed magnets*
- *ALBA II injector elements definition*

Jaume Casanova

Linac Group



Pablo Lengua

Operations Group



Raquel Muñoz

Linac Group Head



ALBA is the Spanish Synchrotron Radiation Facility



Public institution with funding 50/50 from the **Spanish Ministerio de Ciencia e Innovacion** and the **Catalan Department de Recerca i Universitats**



National and international (28%) staff



National and international (35%) users

National and international collaborations




ALBA key parameters

e- Energy = 3 GeV

C = 270 m

Emittance = 4.5 nmrad



12 operating BLs
 2 in construction
 1 for acc. diagnostics

Current
251.63 mA

Size (1 σ)
FE34
H = 53.1 μ m
V = 23.7 μ m

Orbit (RMS)
H = 0.059 μ m
V = 0.031 μ m

Beam for BL

Time to inject: 00:12:33
 Annual BA: 96.68 %
 Annual MTBF: 86.8 h


Operation mode: Lifetime 19h 00m, Avg. pressure 5.0e-10 mbar, Current x lifetime 4834 mAh

Top-up operation

Beamline Status		ID Gap
BL01	MIRAS	24.07 mm
BL04	MSPD	B = 2.10 T
BL09	MISTRAL	
BL11	NCD-SWEET	6.26 mm
BL13	XALOC	7.34 mm
BL16	NOTOS	
BL20	LOREA	60.75 mm
BL22	CLAESS	13.00 mm
BL24	CIRCE	28.27 mm
BL29	BOREAS	41.43 mm

Message from CR: Wednesday 16-Jun-2021 13:07:40

100 MeV LINAC



LINAC @ 100 MeV

Charge: 1 nC

Rep rate 3.125 Hz

Flexible e-gun: flexible filling patterns


BOOSTER

Parameter	Value
Nominal inj E	100 MeV
Minimum inj E	60 MeV
Nominal ext E	3 GeV
Circumference	249.6 m
Emittance	10 nm·rad
Nominal Current	1 mA
Rf frequency	500 MHz
# cavities	1
In the same tunnel as the SR	

Extraction

STORAGE RING

Parameter	Value
Energy	3 GeV
Circumference	269.9 m
Emittance	4.5 nm·rad
Nominal Current	250 mA
Rf frequency	500 MHz
# cavities	6
Long straights	4 (8 m)
Medium straights	12 (4 m)
Short straights	8 (2 m)



Poster: *Operation and Reliability of the ALBA Kicker Magnets*

ALBA History and Future




12h30 Talk
A Double Dipole Kicker for ALBA II

First proposal for building a synchrotron in Spain: in the '90s
10 Years for the approval - 10 Years up to the operation

2021
10 Operating BLs
3 BLs in construction

Next decade fully exploiting the initial infrastructure by increasing number of BLs and add additional platforms (as Advanced Microscope Center)

2030
ALBA II





*Thanks,
and
enjoy the
Workshop!!*