


TE-VSC general meeting 2023



1. VSC's **structure**: changes and new posts.
2. **Operation** in 2023 and **schedule** for 2024.
3. **Three additional projects** in 2024.

This presentation encompasses merely a **small fraction of the topics** I aim to address.

A comprehensive overview can be downloaded from January 2024 onwards.

For **technical reports and advancement**, please refer to our series of **seminars**

<https://indico.cern.ch/category/16375/>

HL-LHC will be comprehensively treated in the next seminar (V. Baglin)

Group structure



Bruegel the elder, source Wikipedia

November 2023

SECRETARIAT



Camilla Hervet



Paolo Chiggiano
-Group Leader-

TE – VSC

Vacuum, Surfaces & Coatings group



M. Taborelli
-Deputy Group Leader-

GL OFFICE



P. Gomes
Collab. & Contr. Soft. strategy



P. Cruikshank



V. Baglin
-VSM Section Leader-



G. Bregiozzi
-BVO Section Leader-



C. Garion
-DLM Section Leader-



G. Pigny
-ICM Section Leader-



J. A. Ferreira S.
-IVO Section Leader-



M. Taborelli
-SCC Section Leader-

Vacuum Studies and Measurements (VSM)



Beam Vacuum Operation (BVO)



Design, Logistics & Methods (DLM)



Interlocks, Controls & Monitoring (ICM)



Injectors & Insulation Vacuum Operation (IVO)



Surface, Chemistry Coatings (SCC)



Staff Members

Left TE-VSC in 2023:

- Chiara Pasquino
- Dariia Ternova
- Paul Cruikshank

New staff members in TE-VSC:

- Graeme Barlow (DLM)
- Laura Bruno (SCC)
- Maria Carmen Giordano (IVO) from 2024


No planned change in structure in 2024-2025

Student, fellows and collaborators in Dec 2023

Students & collaborators



Number of non-staff members in TE-VSC



12-2023: **48** (exc. COAS)

12-2022: **49** (exc. COAS)

12-2021: **46** (exc. COAS)

11-2020: **51** (exc. COAS)

11-2019: **53** (exc. COAS)

11-2018: **53** (exc. COAS)

12-2017: **58** (exc. COAS)

12-2016: **55** (exc. COAS)

12-2015: **37** (exc. COAS)

12-2014: **38** (7 COAS)

New posts in 2024



Abel Grimmer, *Spring*, source Wikipedia



Last day of work at CERN for **Berthold**: June 30, 2024.

Posts	Planned contract start	
Vacuum Technician (IVO)	Q2-Q3	Approved
Material Science Technician (surface treatments, SCC)	Q1	
Vacuum Technical Engineer (VSM or DLM)	Q4	
<i>Vacuum Operation Engineer (BVO)</i>	Q1-2025	<i>Requested</i>
<i>Control Software Engineer (ICM)</i>	2025	
<i>Vacuum Technician (4 years, IVO)</i>	2025	



Giorgione, Tre età dell'uomo
Galleria Palatina, Firenze



Age of staff members in Dec 2023

Total staff: 72

Average age: 46.6




LHC operation in 2023



Banksy, Beyond the curtain

LHC operation in 2023



[Generated at: 2023-07-23 12:16:15]


BE-OP-LHC team



January 2023: LHCb VeLo RF BOX



Credit: M Kraan (Nikhef)



Credit: Freek Sanders (Nikhef)

Context

‘An **incident in January 2023** led to an over pressurization of the VELO Detector Volume and subsequent **deformation of the RF Foils**.

The cause of the over pressurization was an unlikely **conjugation of unusual situations**, planning shortcomings and miscommunication between different teams.

Ultimately, though, the **deformation was not prevented because the existing safety system failed to act due to a hardware failure**. This failure, in turn, affected the control system, which further compounded the issue.


A **temporary replacement for the safety system electronics** was quickly implemented and installed, but the decision was taken to **entirely redesign the VELO Safety System during 2023** and replace it prior to the installation of the new RF foils.

Additional steps were taken during 2023 regarding **mechanical redesign** of the vacuum system and redefinition of certain procedures.’


Rodrigo Ferreira & Josef Sestak: LMC November 22nd, 2023

Simulation of elastic-plastic behaviour of the RF box


Mechanical analysis of the VeLo RF box with non-linear elastic-plastic model



Local buckling occurring at 100 mbar



Instability for an external overpressure of ~56 mbar. **Back-buckling** phenomena studied in detail.





Residual deformation after an internal overpressure of 200 mbar.

Report: Mechanical deformations of the velo RF box due to 200 mbar EDMS: 2820818



VeLo – New vacuum safety system

New measurement assembly


Enable to plan and enforce a procedure to **perform regular proof-tests of the Safety System**, as mandated by the IEC 61511 standard, without posing significant risks to the vacuum system and the RF foils.




New VeLo RF box: NEG coating



VeLo RF foils exchange intervention







18.03.2023

Crystal collimator
Non-Conformity

appeared during testing

21.04.2023
1st stable beam (3bx3b)




24.05.2023

RF finger module Vacuum
spikes caused by beam
induced arcing/heating




02.04.2023
RF Rupture discs
following IP4 SVC trip



12.05.2023
1st collisions with 2374 b
(mixed scheme to
minimize HL)



12 fb-1 in ~1month





Matteo Solfaroli (BE-OP-LHC); presented at the JAP 2023

RF-finger fault

May 25-26, 2023: **Pressure spikes** within the vacuum sector **A4L1** during the fill ID 8828 (**$1.63 \cdot 10^{11}$ p/b – 2358 bunches**) lead to a **beam dump due to losses**.



RF-finger faults: analysis of the problem




RF finger faults: analysis of the problem

Taskforce ABP & VSC


Anomalous heating of a stainless-steel spring



Heated spring



EM field leakage outside the RF fingers




Impedance measurement test bench

- Important progress in simulation and measurement.
- Development and testing of consolidation strategies


RF-finger fault: Mitigation strategy

Replace the current 71 modules in the ID212.7 RF contact with newly designed modules wherever it is possible to implement such a substitution.


Deformable RF Finger




Retrofitted ID 212.7





Unshielded Bellows






21.04.2023
1st stable beam (3bx3b)



24.05.2023
RF finger module Vacuum spikes caused by beam induced arcing/heating


20 fb-1 in ~1.5month



18.03.2023
Crystal collimator Non-Conformity appeared during testing




02.04.2023
RF Rupture discs following IP4 SVC trip



12.05.2023
1st collisions with 2374 b (mixed scheme to minimize HL)

12 fb-1 in ~1month



17.07.2023
Power glitch, magnet quench, and leaking bellow in IT.L8

Matteo Solfaroli (BE-OP-LHC); presented at the JAP 2023

LHC Inner Triplet in L8



Edward Henry Potthast, A Holiday, Art Institute Chicago





Paul Cruikshank, A charismatic leader at CERN



18.03.2023

Crystal collimator
Non-Conformity
appeared during testing


21.04.2023
1st stable beam (3bx3b)



24.05.2023


RF finger module Vacuum
spikes caused by beam
induced arcing/heating

20 fb-1 in ~1.5month



31.08.2023 (B)
08.09.2023 (A)


2 vacuum leaks on IP8-TDIS
Preventing p+ operation, but Pb ion possible



26.09.2023: 1st
stable Pb ion beam of
2023




02.04.2023
RF Rupture discs
following IP4 SVC trip




12.05.2023
1st collisions with 2374 b
(mixed scheme to
minimize HL)

12 fb-1 in ~1month



17.07.2023
Power glitch, magnet quench,
and leaking bellow in IT.L8

2.16 nb⁻¹ to ALICE



Matteo Solfaroli (BE-OP-LHC); presented at the JAP 2023

Injector chain and experimental areas: operation in 2023



Source Wikipedia, C. Monet: Impression, soleil levant; Musée Marmottan Monet









LHC injectors vacuum performance in 2023

Excellent availability, as usual:

- ❑ LINAC4: Less than 30 min VSC downtime.
- ❑ PSB: No downtime
- ❑ PS: Downtime dominated by RF bypass failure that opened a leak (no VSC responsibility)
- ❑ SPS: Better year. Failures dominated by vacuum interlocks. Pressure rise dominated by beam related phenomena.

No systematic failure. Most of the failures linked to non VSC origin

LINAC4	
LINAC4 availability	98.2%
Vacuum fault duration	0.4h
PSB	
PSB availability	96.8%
Vacuum fault duration	0.0h
PS	
PS availability	90.8%
Vacuum fault duration	17.6h
SPS	
SPS availability	82.0%
Vacuum fault duration	1.3h



Operation schedule in 2024



F. Hodler, Landscape of Swiss Alps, Israel Museum

LHC in 2024




Moved to 2025
Research Board
decision

- **Physics in LHC** restarts in week 17.
- **PbPb run**: 2.5-3 weeks in 2024 and 2025 run
- **Oxygen run** after TS#1 in 2025

Rende Steerenberg: LMC, 22 Nov 2023

Long-term schedule update

- **LS3 readiness review in Q3 2024**
- 30 months for SPS i.e. NA CONS
- Progressive commissioning of LHC:
 - First sectors recommissioning, i.e. leak tests after pressure test, in January 2028 (2-3 & 3-4)
 - First sectors cooldown in March 2028 (2-3 & 3-4)



Under approval: <https://edms.cern.ch/document/2311633/2.1>

Rende Steerenberg: LMC, 22 Nov 2023

Three projects:

- In-house assembly of beryllium beampipes
 - Beam-screen treatment in LHC
 - SA18



Caravaggio, The cheater of cards, Princeton

In-house assembly of beryllium beampipes


CERN has always relied on an **external supplier to produce beryllium** experimental vacuum **chambers**.

However, in 2023, our supplier declared its intention to **discontinue the assembly** of these pivotal vacuum chambers.

Subsequently, during the past summer, a proposal was made to **establish a new assembly facility at CERN**, thereby bringing the fabrication process in-house. This program has now been **approved by the Director-General**.

In-house assembly of beryllium beampipes

A new workshop



Preliminary, Courtesy of Isabel Bejar Alonso

Beam-screen treatment in LHC

The objective of the Beam Screen Treatment (**BST**) project is to **reduce the cryogenic heat load of the LHC** by implementing an in-situ chemical modification of the beam screen surfaces.

The project will unfold in three distinct phases:


- Selecting the most **suitable method**.
- Applying this method within a **mock-up** of half-cell.
- **Integrating** the chosen method into the LHC during the **LS3 period**.

Over the course of the long shutdown period spanning 400 weekdays, there is a potential to treat up to **100 half-cells** for a cost of **4 MCHF**, which includes material, IS and M-to-P for graduate programmes.


The project necessitates the contribution of approximately **100 person-months** of both cat-2 and cat-3 staff members.

Beam-screen treatment in LHC


Development of coatings to reduce LHC beam-screen heat loads after a restricted period of beam conditioning in the LHC arcs.



SEY ≤ 1 after 15K conditioning validated for PE-CVD coating in C₃H₈ and thin aC coating by PVD




SEY = 1 still reached after several cycles of 15K conditioning ↔ air exposure




New building for superconducting RF cavities: SA18

SA18 – Project Team Structure




In approval phase, D. Smekens

One last sentence



J. Mirò, Bleu (II/III), Centre Pompidou

SCADA Applications




Critical equipment with gas injection in the beam vacuum and permanent TM pumping.

SCADA integrated into the general LHC frame.

Three new types of pumping groups.


Now operational.

New Coldex



Refurbished applications after changes in the hardware. Motorized system.

IT String



Inner Triplet magnet string for HL-LHC in SM18



Vacmon

New vacmon is fully operational:

- Templating mechanism
- Vistars
- Sector valves
- Integration with elogbook
- TPG300 daily snapshot w/ change notifications

Vacmon

Status of sector valves



TPG300 Daily Snapshots

Select Machine: Day: Compare to: Only Diff

TPG300 Configurations



Name	Gauge	Filter	Valid	Status	UpThr	LowThr	MainPart	Sector
VRGPT.UA23.R19.40.01	VGRB.265.4L2.X	--	Valid	Deact	1.00E-03	8.00E-04	LSSV2	D4L2.X
VRGPT.UA23.R19.40.01		Medium	Valid	Deact	2.00E-06	1.00E-06	LSSV2	D4L2.X
VRGPT.UA23.R19.40.01	VGPB.265.4L2.X	Medium	Valid	Deact	2.00E-06	was 0.00E+00	LSSV2	D4L2.X
VRGPT.UA23.R19.40.01		--	Valid	Deact	2.00E-05	1.00E-05	LSSV2	D4L2.X
VRGPT.UA23.R19.40.01	VGPB.265.4L2.X	Medium	Valid	Deact	2.00E-06	1.00E-06	LSSV2	D4L2.X
VRGPT.UA23.R19.40.01		Medium	Valid	Deact	2.00E-06	1.00E-06	LSSV2	D4L2.X

Total 6 items < 1 > 50 / page

SCADA Performance Improvements

- **Several algorithms improved** to increase the performance of the vacuum SCADA
- **Deployment of the Unified Mobiles System** resulted in a **52% improvement** in LHC SCADA


application performance.



Last LHC upgrade
21st of November

VacCC Exporter Validator

- Tool used **to run multiple parallel tests** to validate files produced during an export, ensuring their accuracy and integrity.
- Current tests include:
 - Legacy or Unified Mobiles System validation
 - PLC and SCADA memory validation
 - PLC function calls validation
- Integrated with vaccumProductionExports Gitlab CI/CD pipelines to automatically validate export files pushed to the repository
- **Adaptable to accommodate additional tests in the future** as the need for further testing arises



VacCC : Vacuum Controls Configurator

Some pictures



P2 Agilent consolidation



Agilent's test procedure




ITL VPG troubleshooting



Sector valves consolidation



Test for SVCU crate consumption



VELO TPG300 troubleshooting




SPS valve troubleshooting



Profibus Support BVO




De-cabing lockout



VPG for Beam screen TB

Einstein Telescope's Beampipe



BEAMPIPES FOR GRAVITATIONAL WAVE TELESCOPES 2023

Beampipe know-how for GW observatories

The direct detection of gravitational waves (GWs) in 2015 opened a new window to the universe, allowing researchers to study the cosmos by merging data from multiple sources. There are currently four gravitational wave telescopes (GWTs) in operation: LIGO at two sites in the US, Virgo in Italy, KAGRA in Japan and GEO600 in Germany. Discussions are ongoing to establish an additional site in India. The detection of GWs is based on Michelson laser interferometry with Fabry-Perot cavities, which reveals the expansion and contraction of space at the level of ten-thousandths of the size of an atomic nucleus, i.e. 10^{-10} m. Despite the extremely low strain that needs to be detected, an average of one GW is measured per week of measurement by studying and minimising all possible noise sources, including seismic vibration and residual gas scattering. The latter is reduced




Beam me up

The participants of the March workshop that was dedicated to vacuum technologies for beampipes of next-generation gravitational-wave telescopes.

solutions were adopted, then the vacuum pipe system would amount to half the estimated cost of the CE and almost one-third of the ET, with underground civil engineering the dominant amount. Reducing the cost of vacuum systems requires the development of different technical approaches with respect to previous-generation facilities. Developing cheaper technologies is also a key subject

vacuum systems provided a starting point for the presentations of ongoing developments. To conduct an effective cost analysis and reduction, the entire process must be taken into account – including raw-material production and treatment, manufacturing, surface treatment, logistics, installation and commissioning in the tunnel. Additionally, the interfaces with the experimental areas and other services

- Available space : 43.4 m x 3.5 m
- Pipe length : around 36 m.







Merci à vous tous!