


AWAKE Electron Sources for Run 2

- Run2 prototype in CTF2 (ARTI)
- First results with beam
- Conclusion and outlook



AWAKE collaboration meeting 25-26 April, Uppsala
Steffen Doebert, J. Arnesano

Injector prototype in CTF2 for CLEAR and AWAKE ARTI (AWAKE Run2 Test Injector)




Reduced scale prototype, 60 MeV, T24 as buncher and PSI-linearizing structure for acceleration.
Goal: demonstrate the velocity bunching and emittance preservation with x-band
Prototyping of key hardware

F-Cup

Screen BTV1

ARTI in CTF2

RF-GUN




Spectrometer

Status:


- Phase 1 installed and operational
 - All safety documentation finished
 - DSO tests successfully performed
 - Beam permit obtained
 - Diagnostics installed and being commissioned
 - Laser table installed and equipped
 - Laser aligned and synchronised
- First beam tests were successful and promising

RF-gun build by INFN Frascati.

RF Conditioning data from the INFN RF-GUN in CTF2



RF-gun conditioned to 120 MV/m on the cathode



Counting: 1-5k breakdowns depending on threshold
→ Very good result, promising for future reliable operation

ARTI photoinjector laser


Eduardo Granados (SY-STI)

Miguel Martinez Calderon (SY-STI)


Baptiste Groussin (SY-STI)





Setup at CLEAR laser lab



Optical setup of CTF2 Photoinjector laser and energy stability



Dedicated laminar flow tent





Conversion efficiency:


- IR to green ~60%
- Green to UV ~30%
- Overall ~ 18%

IR to UV conversion stages

Output at 1030 nm



Output at 257.5 nm




Peak (X,Y)R [μm]	(2351.7, 1554.4) 2819.0
Centroid (X,Y)R [μm]	(4131.2, 3306.5) 5291.5
Peak % Resp. [%]	65.1
Eff. Area [mm²]	16.856
Fluence [J/cm²]	0.803
Eff. Diameter 86.5% [mm]	Invalid
Aper. Diameter 86.5% [mm]	0.066
Knife Edge 84.0% [mm]	7.839, 7.350
Ellipticity	
Major, Minor 86.5% [mm]	7.852, 7.061
Circularity	0.899
Gaussian Fit 86.5%	
Coefficient	0.862, 0.857
Aperture Uniformity	
Min, Mean, Max [digital]	24277.0, 27091.0, 30476.0
Sigma, RMS [digital]	1849.5, 27152.9
Image Uniformity	
Min, Mean, Max [digital]	6.0, 12219.9, 42656.0
Flat Top 14.0%	
Beam Uniformity	0.390
Plateau Uniformity	0.003
Flatness Factor	0.381
Edge Steepness	1.000

SHG BBO CRYSTALS. Type 1, Thickness = 2.0 mm

Aperture, mm	θ, deg	φ, deg	Coating	Catalogue number	Price, EUR
6×6	23.4	90	AR/AR @ 515+1030 nm	BBO-654H	480
8×8	23.4	90	AR/AR @ 515+1030 nm	BBO-854H	630
10×10	23.4	90	AR/AR @ 515+1030 nm	BBO-1054H	835

BBO FOR 4HG @ 1030 nm


Aperture, mm	Thickness, mm	θ, deg	φ, deg	Coating	Catalogue number	Price, EUR
6×6	0.1	50	90	P/P @ 515/257 nm	BBO-641H	600
6×6	0.15	50	90	P/P @ 515/257 nm	BBO-642H	570
6×6	0.2	50	90	P/P @ 515/257 nm	BBO-643H	550
6×6	0.3	50	90	P/P @ 515/257 nm	BBO-644H	535






Output at 515 nm

Spot on cathode control and performance


UV pulse energy control




UV spot size control



UV position on cathode



UV pulse duration



CLR:CTF2LA

Controls integrated in WorkingSet

Hardware References LSA DB


JAPC view for the SCT.USER.SETUP user mapped on the CLEAR-2020 LSA cycle.

LTIM	Event	Load	Start	Delay	Clock Str.	AqnUTC	AqnC	AqnNano
CX.LAS-USTART	true	CFX.SCY-CT.CX.GENERA...		2865	19.2 MHz	24/04/2023 11:48:28	1113	1113011800
CX.LAS-SYNC-S	true	CFX.SCY-CT.CX.GENERA...		2880	19.2 MHz			
CX.LAS-SYNC	true		CX.LAS-SY...	19200	19.2 MHz			
CX.LAS-SYNC-N	true	CFX.SCY-CT.CX.GENERA...		300	19.2 MHz	24/04/2023 11:48:28	1202	1202904750

NewFocusPiconotor	Motion Status	Position	Position	Current Velocity
CO.TOMB.201.UVCATHOR	STOPPED	1056	1056	0
CO.TOMB.201.UVCATVER	STOPPED	343	343	0
CO.TOTL.201.UVCATMAG	STOPPED	27000	27000	0
CO.TOMB.103.UVATTS	STOPPED	5200	5200	0


RF synchronization performance

From TEM Messtechnik




Thanks to Ben Wooley!


RF locking remote control panel



Timing jitter so far




Phase noise spectrum



Integrated 1 Hz – 1 MHz ~ 1.5 ps RMS

Lots of room for improvement...


First results with beam



RF set-up:
Input Power: 13 MW
Gradient: 114 MV/m

Warning: calibrations still floating

First results with beam




**Beam on Screen:
Beam size: ~ 0.5 mm sigma**

Yes it is really so beautiful !

Warning: calibrations still floating

First results with beam




**Beam in spectrometer.
Energy: ~ 5.7 MeV**

Energy spread: ~ 185 keV

We still have some issues with the magnet setting which was limited by software

Warning: calibrations still floating

First results with beam



Beam charge:
 Faraday Cup: up to 440 pC
 This example ~ 300 pC



Warning: calibrations still floating

Copper Qe: 9×10^{-4}

Very promising for Copper cathodes



No dark current basically not measurable for time being:
 $< 5 \text{ pC}$ (preliminary)

Simulations



We measured for time being 5.7 MeV and 185 keV for the non optimised beam ?!?

Simulations




Measured beam size around 0.5 mm, no emittance estimation yet


PIC Dark Current Simulations



No Solenoid




Solenoid: Antisymmetric mode






Pablo Martinez-Reviriego, IFIC

Dark Current Simulations




Pablo Martinez-Reviriego, IFIC



X-band structure developments

Travelling wave Constant Impedance



Shunt Impedance [$M\Omega/m$]	100
Group Velocity v_g/c [%]	2.4
Q-Factor	7061
Attenuation [1/m]	0.7
Length [m]	0.9



Mechanical design
made at CERN



CLIC style tolerances
Vacuum brazing design

Structure to be
inserted in a solenoid
of 150 mm diameter
bore radius



Designed by INFN Frascati, D. Alesini, M. Diomede,
for CompactLight and EuPraxia

First short prototype under construction



C. Capelli, N. Chritin

Verify mechanical design, brazing assembly and tolerances needed
Maybe low power RF measurements but no high power test planned

Conclusion and outlook



- Very good start of the beam commissioning. No major problems spotted so far**
Of course fine tuning is needed and systematic measurements.
Clearly much more work to do !
Apologises for the poor-man data acquisition

- Will alternate commissioning periods with installations periods to complete the injector**

- Interesting times ahead, a first visible piece of the injector for Run 2c**


- Thanks to Jordan Arnesano for his contributions to AWAKE**
Welcome to Tobias Kulenkampff to take over in June

Additional material






BILL OF MATERIALS				
ITEM	DESCRIPTION	QUANTITY	REVISION	REV. DATE
01	PHYS PHOTO-SELECTOR	SPFPM-002		
02	PHYS PHOTO-SELECTOR	SPFPM-003		
03	TO-400 PHOTO-SELECTOR	SPFPM-004		
04	ISOBLE INSULATOR	SPFPM-005		
05	GATE VALVE	SPFPM-006		
06	SUPPORT CATHODE ASSEMBLY	SPFPM-007		
07	ISOBLE INSULATOR	SPFPM-008		
08	ISOBLE INSULATOR	SPFPM-009		

X-band accelerating structure Mechanical design



Structure to be inserted in a solenoid of 150 mm diameter bore radius





CLIC style tolerances
Vacuum brazing design