



苏州八匹马超导科技有限公司





HL-LHC MCBRD CCT Magnets: Review and Latest Progress in China

Qingjin XU, Yingzhe Wang
IHEP-CAS
For the CCT Magnet Team

2023.05.10






MCBRD: the HL-LHC D2 orbit correctors, 12+1 units, providing a **5 Tm** integrated field in two apertures, **vertical in one and horizontal in the other**.




Main design parameters of the CCT magnet




Items	Values
CCT skew angle	30°
No. of turns per layer	365
Slot size in former (mm)	2×5
Spacing per turn	5.222
Inside/Outside diameter of the former (mm)	Inner former:105.35/119.35
	Inner former:120.80/134.85
Inside diameter of the groove/slot(mm)	1 st layer: 109.15/119.15
	2 nd layer: 124.65/134.65
Reference radius (mm)	35
Diameter of aperture (mm)	105
Current (A)	395



Items	Values
Diameter of yoke (mm)	614
Thickness of yoke lamination (mm)	5.8
Diameter of aperture (mm)	167
Position of aperture (mm)	94.19
Yoke key slot(mm)	8(3.01) × 6
Diameter of cooling hole (mm)	110
Position of cooling hole (mm)	205



Opera



Opera

Progress of series production




苏州八匹马超导科技有限公司

	Coil name	Winding method	Location	Coil stand-alone performance (4.2 K)	Magnet performance at 4.2 K
Magnet1	MCBRD_CB01	Wet wind	CERN	530 A	Both apertures reached ultimate current 422 A, and passed 4-hour stability test
	MCBRD_CB03	Direct wind		410 A (training stopped due to the availability of the test station)	
	MCBRD_CB02	Direct wind	CERN	Failed to reach the design current	
Magnet2	MCBRD_CB04	Wet wind	CERN	422 A (training stopped due to the availability of the test station)	Both apertures reached ultimate current 422 A, and passed 4*1 hour stability test
	MCBRD_CB06	Wet wind		530 A	
Magnet3	MCBRD_CB09	Direct wind with new channel size	<i>Shipping to CERN</i>	530 A	Both apertures reached ultimate current 422 A, and passed stability test
	MCBRD_CB12	Direct wind with new channel size		526 A (25 quenches)	
	MCBRD_CB13	Direct wind with new channel size	BAMA	530 A (20+33 quenches)	-
	MCBRD_CB14	Direct wind with new channel size	BAMA	530 A (30+34 quenches), detraining problem, put in quarantine	-
	MCBRD_CB17	Direct wind with new channel size	BAMA	<i>Waiting for VPI</i>	-
MCBRD_CB10, 11, 15, 16		Shipped to CERN for fabrication			

Training-history of Bama coils CB09-14





苏州八匹马超导科技有限公司





Manufacture of CB14



苏州八匹马超导科技有限公司




Manufacture of CB14



Stand-alone test of CB14 at IHEP



苏州八匹马超导科技有限公司




Stand-alone test of CB14



苏州八匹马超导科技有限公司

Traning history of CB14





Changes:

- Changes of the operators.
- **The inlet pipeline between mix tank and impregnation furnace (exposed in the air ~10°C) didn't use any thermal insulation.**
- It takes a longer time (6~7h) of injection compared with CB09 ~ CB13 (3~4h).




Corrective action of the VPI station



Qualification of the VPI system



苏州八匹马超导科技有限公司



Set the curing procedure.
设定固化程序。

60°C → 30min → 80°C → 1440min → 80°C → 60min → 135°C → 180min → 135°C → 20°C

- We use a 0.5m quadrupole CCT magnet as a qualification of the VPI system after applying the corrective actions.
- This magnet will be tested this week.


Training history of MCBRD03 (1st test)




苏州八匹马超导科技有限公司

- AP1(CB12, 25 quenches 526A) reached $\pm 422A$ after **11 quenches**.
- AP2(CB09, 33 quenches 530A; after thermal cycle > 500A) reached $\pm 422A$ **without any quenches**.


The training history of MCBRD03



The 3.5 h holding test @combined powering



Quench locations of Aperture 1 (take the absolute value)





Training history of MCBRD03 (2nd test)



苏州八匹马超导科技有限公司

- Both Apertures reached the nominal current **without any quenches** after thermal cycle.



Training history and quench location of the 2nd test


Field Quality of MCBRD03




苏州八匹马超导科技有限公司

Stair steps & magnet filed measurement of Aperture 2 (MCBRD_CB09)

Magnetic filed measurement of Aperture2: stair step





Integral Field and Transfer Function



Field Quality of MCBRD03

Multipoles (individual powering)



Multipoles –AP1 (individual powering)

Aperture 1 (MCBRD_CB12) @ ramping up								
	-100A		-200A		-300A		-394A	
n	an	bn	an	bn	an	bn	an	bn
2	-4.50040	2.13859	-5.19001	3.45314	-5.69287	4.14465	-7.03831	4.70526
3	0.42357	3.05241	0.18448	0.57213	-0.03520	1.13365	-0.37439	1.63961
4	0.69611	-0.30172	0.65365	-0.19803	0.53357	-0.14939	0.44021	0.08241
5	0.19717	2.55257	0.11417	1.83818	0.14957	1.74971	0.16902	2.15402
6	-0.19741	-0.10484	-0.20612	-0.14335	-0.18974	-0.15380	-0.25060	-0.20054
7	-0.03104	-0.05045	-0.05929	-0.26855	-0.07823	-0.32614	-0.07640	-0.47337
8	0.11026	-0.02358	0.08175	-0.02506	0.09058	0.00234	0.08240	-0.01950
9	0.00820	0.06000	-0.00708	0.02217	-0.02059	0.02763	0.00184	0.06223
1	0.00357	-0.03813	0.00631	-0.03708	0.01437	-0.03765	0.00618	-0.04837
0								
Aperture 1 (MCBRD_CB12) @ ramping up								
	100A		200A		300A		394A	
n	an	bn	an	bn	an	bn	an	bn
2	-4.27368	4.38865	-4.76084	4.00735	-5.17860	4.17969	-6.07863	4.65889
3	0.36779	2.18547	0.15767	0.15551	-0.02551	0.83986	-0.30444	1.34324
4	0.74333	0.18810	0.59700	-0.02378	0.54989	-0.04978	0.62414	-0.00873
5	0.20771	2.49497	0.10856	1.78722	0.12524	1.70399	0.18207	2.09014
6	-0.15192	-0.06673	-0.17020	-0.10741	-0.19285	-0.15217	-0.21987	-0.20909
7	-0.03102	-0.06196	-0.03172	-0.24929	-0.04694	-0.33945	-0.05676	-0.43269
8	0.10576	-0.03406	0.09840	-0.02648	0.11139	-0.02338	0.09832	-0.03368
9	-0.00692	0.00781	-0.02450	-0.00030	-0.03826	0.01176	-0.02535	0.04364
1	-0.00104	-0.06223	0.01566	-0.03488	0.01173	-0.03651	0.01373	-0.07574
0								







Multipoles –AP2 (individual powering)

Aperture 2 (MCBRD CB09) @ ramping up									
n	+100A		+200A		+300A		+394A		
	an	bn	an	bn	an	bn	an	bn	
2	0.51334	6.79305	0.61303	6.74085	-0.23368	6.94466	-3.68201	7.08871	
3	0.45030	2.16348	0.22338	0.15573	0.05082	1.11222	-0.15213	0.71026	
4	-0.43018	0.07183	-0.24788	-0.01038	-0.16346	-0.03915	-0.07066	-0.07836	
5	0.21841	2.63806	0.13708	1.99150	0.14264	1.97349	0.11056	2.43106	
6	0.06052	-0.13307	0.09526	-0.18572	0.12340	-0.20998	0.21066	-0.22405	
7	0.00995	-0.02104	-0.00808	-0.20955	-0.04935	-0.28444	-0.05895	-0.36796	
8	-0.06597	-0.04159	-0.04817	-0.02937	-0.04165	-0.03832	-0.07723	-0.04529	
9	-0.03095	0.08791	-0.03611	0.04426	-0.04073	0.05505	-0.04554	0.10164	
1	-0.04532	0.01203	-0.00950	0.00659	0.00633	0.00578	0.02094	-0.02666	
0									
Aperture 2 (MCBRD CB09) @ ramping up									
n	-100A		-200A		-300A		-394A		
	an	bn	an	bn	an	bn	an	bn	
2	0.50806	6.94348	0.53457	6.81459	-0.22350	6.84083	-3.79837	7.06555	
3	0.40866	2.33744	0.21651	0.12295	0.05553	0.99451	-0.12747	0.69508	
4	-0.42887	0.13706	-0.22545	0.09656	-0.27681	-0.00620	-0.16837	-0.01531	
5	0.21136	2.60452	0.16334	2.04470	0.14316	2.02251	0.13484	2.45293	
6	0.07233	-0.14474	0.11447	-0.19324	0.15643	-0.20411	0.19943	-0.18717	
7	-0.00372	-0.09899	-0.00102	-0.23372	-0.02910	-0.29176	-0.05522	-0.38597	
8	-0.07444	-0.01502	-0.02921	-0.01717	-0.05957	-0.01806	-0.10929	0.01936	
9	-0.02501	0.02681	-0.02942	0.05095	-0.04431	0.04024	-0.03427	0.08583	
1	0.05695	0.03257	0.00114	0.02397	0.00025	0.03355	-0.02465	0.04118	
0									

Field Quality of MCBRD03

Crosstalk-transfer function (combined powering)

Crosstalk- Multipoles (combined powering)



Crosstalk-transfer function (combined powering)

Aperture1[A]	Aperture2[A]			Aperture2[A]	Aperture1[A]		
	0	+394	-394		0	+394	-394
100	-12.74612	-12.73445	-12.74309	100	-12.75385	-12.75027	-12.75106
200	-12.76495	-12.75368	-12.75757	200	-12.77169	-12.76685	-12.77325
300	-12.77356	-12.75995	-12.75994	300	-12.77974	-12.76914	-12.76993
394	-12.77209	-12.74035	-12.74116	394	-12.77406	-12.75245	-12.74987
300	-12.78550	-12.77455	-12.77610	300	-12.79290	-12.78426	-12.78461
200	-12.78216	-12.77885	-12.77919	200	-12.79216	-12.78834	-12.78916
100	-12.79174	-12.79051	-12.79057	100	-12.81219	-12.80341	-12.80296
-100	-12.75393	-12.75110	-12.74580	-100	-12.76019	-12.75610	-12.75203
-200	-12.76771	-12.76220	-12.76016	-200	-12.77425	-12.77341	-12.76705
-300	-12.77440	-12.76306	-12.76396	-300	-12.78133	-12.76898	-12.76940
-394	-12.77367	-12.74435	-12.74318	-394	-12.77462	-12.75280	-12.75145
-300	-12.78892	-12.78000	-12.77920	-300	-12.80112	-12.78394	-12.78416
-200	-12.77904	-12.78471	-12.78618	-200	-12.80038	-12.78889	-12.78942
-100	-12.80929	-12.80321	-12.80262	-100	-12.81261	-12.80343	-12.80335

Crosstalk-Multipoles (combined powering)

		Aperture 1 (MCBRD CB12) at 394A					
Aperture2[A]	0A		394		-394		
n	an	bn	an	bn	an	bn	
2	-6.07863	4.65889	8.13214	-6.81124	-12.50908	2.22331	
3	-0.30444	1.34324	-1.21701	8.59996	1.84462	5.39625	
4	0.62414	-0.00873	0.50878	0.27393	-0.40927	0.04036	
5	0.18207	2.09014	-0.18451	2.47873	0.56530	2.53141	
6	-0.21987	-0.20909	0.15336	0.15714	-0.35529	-0.16529	
7	-0.05676	-0.43269	-0.24873	0.01071	-0.08740	-0.41142	
8	0.09832	-0.03368	-0.12367	-0.20674	0.09972	0.01695	
9	-0.02535	0.04364	0.24268	-0.02647	-0.03161	0.10476	
10	0.01373	-0.07574	0.28325	0.20327	0.03408	-0.04311	

		Aperture 2 (MCBRD CB09) at 394A					
Aperture1[A]	0A		394		-394		
n	an	bn	an	bn	an	bn	
2	-3.68201	7.08871	-10.34655	-2.62457	-9.80432	16.34188	
3	-0.15213	0.71026	2.87709	-0.34995	-2.86050	0.00720	
4	-0.07066	-0.07836	0.17573	-0.02580	0.11868	-0.14828	
5	0.11056	2.43106	0.29614	2.59239	-0.07203	2.61698	
6	0.21066	-0.22405	0.16676	-0.19371	0.12004	-0.32182	
7	-0.05895	-0.36796	-0.10420	-0.39263	-0.05007	-0.37748	
8	-0.07723	-0.04529	-0.03795	-0.07794	-0.08337	-0.02172	
9	-0.04554	0.10164	-0.04821	0.08660	-0.03792	0.10154	
10	0.02094	-0.02666	0.01740	-0.04619	0.02038	-0.00807	

Summary



- 3 series CCT magnets have been fabricated. All of them reached the ultimate current and passed the field quality test. The 4th magnet is under fabrication.
- Reasons for the detrainning problem of CB14 have been found and about to be solved.
- Components for 2 CCT magnets have been shipped to CERN from IHEP, to verify the performance with components from China and CERN fabrication process.
- Shipment of MCBRD03 and yoke laminations for 1 CCT magnet will reach CERN in the middle of June.



Thanks for your attention

