



The CMS BRM System

Richard Hall-Wilton (TS/LEA)

On behalf of the

CMS Beam Conditions and Radiation Monitoring Group

Institutes Involved:

Auckland, Canterbury, CERN, DESY, Karlsruhe, Princeton, Rutgers, Tennessee, UCLA



BRM Group Remit

Provide monitoring of the beam-induced radiation field within the UXC55 cavern and the adjacent straight sections.

Provide real-time fast diagnosis of beam conditions and initiate protection procedures in the advent of dangerous conditions for the CMS detector

- System features must include:
 - Active whenever there is beam in LHC
 - Ability to initiate beam aborts
 - Provision of warning & abort signals to CMS subdetectors
 - Postmortem reporting
 - Provision of online and offline beam diagnostic information to CMS and LHC
 - Bench-marking of integrated dose and activation level calculations
 - Integration of all online beam diagnostic information (including subdetectors).
 - Updating at ≥ 1 Hz

BRM Subsystems: The Prioritized List

PHASE 1: Installed for Startup

- RADMON
 - Extension of LHC wide radiation monitoring system
- BCM2: Diamond leakage current monitor at rear of HF
 - Readout as extension of the LHC Beam Loss Monitor (BLM) system
 - Commissioned against BLM ionization chambers in Long Straight Section
 - Output to CCC and CMSCR
 - Input into beam abort (after commissioning against LHC BLM)
- BCM1L: Diamond leakage current monitor in tracker vol. (close to beampipe)
 - No FE electronics
 - Commissioned in conjunction with BCM2
 - Output to CCC and CMSCR
 - Input into beam abort after commissioning (against BCM2)
- BSC: Beam Scintillator Counters
 - Large area scintillator tiles on the front of HF
 - Output to CMSCR
 - Initially only a monitoring system

PHASE 2

- BCM1F: Diamond + fast amplifier for bunch by bunch monitoring
 - Installed prior to First physics run (or earlier)
 - Output to CMSCR
 - Initially only a monitoring system

CCC=CERN Central Control RM
CMSCR=CMS Control Rm


PHASE 3

- Upgrade systems under consideration for 2008/9
- Upgraded BSC (position, robustness, technical trigger)
 - PLT: Pixel Luminosity Telescope (not yet endorsed).
 - Would also be a beam diagnostic device

Increased complexity/deviation from standard LHC interfaces



CMS Beam Monitoring

Symmetric +ve, -ve Z



C.M.S. PARAMETERS
Longitudinal View - Field Off

RADMON: 18 monitors around UXC





14.4m

10.9m




BPTX: 175m



BRM Subsystem Summary

Subsystem	Location	Sampling time	Function	Readout + Interface
Passives	In CMS and UXC	Long term	Monitoring	---
RADMON	Around CMS	1s	Monitoring	CMS + Standard LHC
BCM2	At rear of HF	40 us	Protection	CMS + Standard LHC
BCM1L	Pixel Volume	Sub orbit ~ 5us	Protection	CMS + almost std LHC
BSC	Front of HF	Bunch by bunch	Monitoring	CMS Standalone
BCM1F	Pixel volume	Bunch by bunch	Monitoring + protection	CMS Standalone



All online systems read on when machine operational and possibility of beam in LHC
Systems are independent of CMS DAQ



BCM Functionality




- Use synthetic diamond sensors as simple Flux/rate monitors
 - 2003-2006: Prototypes tested in CDF, CERN East Hall, KAZ (Karlsruhe), PSI

- Generate warnings/alarms/beam aborts based on sustained above-threshold readings or very rapid rate of increase towards threshold
 - Deadtime free monitoring
 - CMS configurable thresholds
 - Rolling history of conditions available online,
 - **Initiate CMS beam abort if conditions above abort threshold**

- CMS:
 - Direct warning/alarm, monitoring, diagnostic and postmortem information
 - User selectable time scales over which above-threshold conditions assessed

- LHC:
 - Provide full monitoring + beam dump post-mortem reporting to CCC
 - Close interaction with LHC operations and LHC machine protection group

Example: CMS BCM Sensors in CDF- Online Monitoring Plots



CMS BCM Sensors in CDF:


- Sensors + electronics in realistic hadron collider environ
- Cross calibrate with existing CDF beam monitoring (BLM and diamond based)
- **Uses 20us Sampling**




Beam Conditions Monitor in detail:

- Three locations
 - **BCM1:** Inside the CMS detector, $z=1.8\text{m}$ from the IP, $r=4.8\text{cm}$
 - 8 Diamonds per end (4 poly- and 4 single- crystal diamonds)
 - **BCM2:** Outside the central detector ($z= 14.365\text{ m}$)
 - Two locations (12 diamonds per end)
 - Shielded from IP ($r= 29\text{cm}$)
 - As close as possible to Beampipe ($r=5\text{cm}$)
- All locations:
 - monitor diamond leakage current synthetic polycrystalline diamond sensor
 - Warning/alarm abort thresholds to be CMS configurable
- Readout:
 - BCM2:
 - Standard LHC BLM readout (Tunnel card to DAB board to database)
 - Exactly the same readout and reporting structure
 - BCM1_L:
 - LHC BLM readout from DAB card onwards.
 - Sub orbit monitoring ($\sim 10\mu\text{s}$) synchronized to orbit Clock
 - No tunnel card
 - Custom mezzanine card on DAB board. Uses BLM interface and reporting structure
- BCM1_L, BCM2 have marginal sensitivity for pilot run
- Post-mortem and monitoring data
 - Reporting mechanism unchanged from BLM system ie CMW/FESA

BCM1 Unit



Carbon fibre frame
Modular design
Compact



BCM1_L

- Leakage current measurement
- Sensor: polycrystalline diamond
 - 10x10x0.4mm
 - 7000e-/MIP
- No front end electronics
- Bias voltage: 500V (nominal)
- Sensor orientation set by need for ExB to avoid anomalous leakage currents
- No direct cooling

BCM1_F

- Bunch by bunch measurement
- Sensor: Single crystal diamond
 - 5x5x0.5mm
 - 18000e-/MIP
- Dedicated front end electronics
 - JK16 amplifier -> optohybrid
- Bias voltage: ~100V (nominal)
- Limited space for front end electronics
- No direct cooling

BCM: Monitoring Timescales


BCM2: monitors leakage current on half-orbit scale

- LHC-standard readout hardware from LHC Beam Loss Monitor (BLM) group
 - Replaced ionization chamber with polycrystalline diamond (10x10x0.4mm)
 - Sampling time: 40 us
 - Monitoring time scales: 12 staggered buffers to cover 40us to 100s history

BCM1L: monitors leakage current on sub-orbit scale

- Synchronizes with orbit marker
- User configurable sub-orbit sampling scheme: (2us minimum)
 - Statistical measurement of conditions at user specified positions in orbit
 - Sub-orbit monitoring averaged and passed to std BCM2 staggered buffer readout
 - Dedicated sampling of beam abort gap

BCM1L
Sampling
Scheme






Beam Conditions Monitor - Status

- Diamonds ordered - majority already received
 - BCM2 diamonds metallised. Ready for packages
 - Rest of diamonds ready soon
- Packaging prototype design done -
 - Final packaging soon.
- Support structures design done - manufacture will start soon
- BCM1_F prototype FE electronics complete
- Cables for BCM2 already laid
- Cabling for BCM1 being prepared
- On track for being installed on time

Full BCM Readout Chains

- Baseline systems on track
 - BCM2 readout chain
 - Full chain validated [sensor to backend readout]: Karlsruhe Aug 06
 - BCM1L readout chain
 - Custom Mezzanine card tested: Based on Tevatron design
 - Prototype of chain from sensor to VME backplane expected April 07
- Procurement of final hardware ongoing - no showstoppers expected
- Will complete full slice test by end next Month
 - => BCM1, BCM2 readout chain + interface to CMS and CCC



CMS Beam Scintillator Counters

- ✓ Simple standalone system: No front end electronics
- ✓ Simple to commission
- ✓ Monitoring Independent of CMS DAQ status

Readout:


- PMTs mounted on side of HF, readout over long cables (80m) to USC.
- ADC & discriminator + TDC readout
 - Same back end as BCM1F

BSC1 --- 11 000 cm²

Inner radius - 15 cm

BSC2 --- 1 000 cm²

Inner radius - 5 cm





CMS: display similar to ZEUS example

CMS Beam Scintillator Counters





- ✓ Output to CMS (+CCC?): statistical measurements
 - Rate monitoring on sub orbit scales + bunch by bunch, inc. Abort gap monitoring
 - Relative time measurements: incoming vs outgoing particles
 - **Should be sensitive during 450 GeV run**

□ Status:




- Recovered scintillator / PMTs tested
- PMTs Tested for fringe magnetic field expected
- Final design of mounting underway
- Will be mounted in the summer
- Cables installed
- Readout design ongoing

Cross-sectional Areas
 HF = 5.6m² TK = 3.8m²
 BSC paddles = 0.6m² BSC = 1.1m²

Ratios
BSC_Paddles/TK = 17%; BSC/HF = 20%



BCM2 + BSC2



RADMON and Passive Monitors

■ RADMON Units (In conjunction with TS-LEA)

□ Measures

- Dose, dose rate using RadFETs
- Hadron ($E > 20$ MeV) flux and fluence, SEU rate via SRAM
- 1 MeV equiv neutron fluence via pin diodes ($\alpha > 100$ keV fluence)

□ 18 Monitors deployed around CMS (UXC + USC)

- Data reported back to the RADMON database
- Installation of RADMON infrastructure started



□ Used for Online benchmark points for verification of simulations


■ Passive Dosimeters (In conjunction with TS-LEA, DESY)

□ CERN standard dosimeters

- Pin diodes, TLDs, RPLs, Alannine

□ Provide detailed radiation mapping after Pilot run







Summary

- Priorities for startup BRM subsystems defined.
- Mechanical Infrastructure well advanced
- Readout chains progressing/well advanced
 - Exception: BSC/BCM1F back end only starting (off-the-shelf solution is foreseen)
- Services and Installation schedule
 - Mapped to CMS master schedule.
 - Fine detail of installation sequence still needs to be choreographed
- Interface work commencing
 - Done in close contact with the accelerator groups
 - Mechanism is defined through the LEADE protocols.
- Full BCM slice test expected March 07
 - RADMON system test already done by TS-LEA