

# Pad MicroMegas & $\mu$ RWELL characterization for MPGD based HCAL

Piet Verwilligen, Luigi Longo on behalf of RD51 Common Project on  
Resistive MPGD Calorimetry team


INFN Bari - Napoli - Frascati - Roma & Weizmann Institute

# Why MPGD based HCAL?

Proposal of a sampling calorimeter with **Micro-Pattern Gas Detector** as active layer

## Advantages

- ▶ Radiation hardness
- ▶ High rate capability ( $MHz/cm^2$ )
- ▶ Suitable for fine granularity
- ▶ Good space ( $> 50\mu m$ ) and time resolution (5 – 10 ns)
- ▶ Good response uniformity ( $\sim 10\%$ )
- ▶ Relatively cheap for large area instrumentation





**$\mu RWell$**  and resistive **Micromegas** best MPGD options for reducing discharge effects

# Why MPGD based HCAL?

**Proof of concept:** HCal prototype made of 8 MPGD based active layers and 8 absorbers ( $2\lambda_N$ )

## MPGD detectors:

- build 7  $\mu$ RWELL & 4 MicroMegas thanks to CERN MPT workshop and INFN:
  - 20x20 cm<sup>2</sup> of active area
  - 1 cm<sup>2</sup> pixel  $\rightarrow$  384 pixels
  - common readout board for both technologies
- preliminary tests (HV stability, gain measurements, measurements under X-ray or with Fe55 ) performed at the various institutes (Bari, Frascati, Naples, Rome3, Weizmann)



# Test beam

- **Goals of the test beam:**

- measure efficiency, cluster size, spatial resolution, time resolution, gain uniformity.
- best 8 detectors will be used for the HCal prototype

- **Test beam setup:**

- 2 supporting structures (48x52x100cm3):
  - one for the tracker system made of 2 scintillators plus 2 Tmm
  - one for the 11  $\mu$ RWELL+MicroMegas chambers (plus one RPWELL)
- DAQ based on SRS+APVs:
  - not yet able to work with different FECs at least using CTF (under debugging; next week we will be at 154 and any help will be appreciated)
- Gas needed: Ar:CO<sub>2</sub> (93:5:2) or (93:7), Ar:CO<sub>2</sub>:CF<sub>4</sub> (45:15:40) order already in place (thanks Eraldo for taking care)
- Desy table for the calo structure for performing a full scan of the detectors (not yet requested)
- HV, logic unit already ordered and taken from the pool but we would need a rack

