



Test result of MBXF1

Michinaka SUGANO (KEK)

KEK



**On behalf of CERN-KEK Collaboration for D1
Development for HL-LHC**

Outline

- Test result of the 1st cycle for MBXF1
 - 1.9 K Hi-pot test
 - Validation of newly implemented varistor
 - Training performance
 - Energy extraction with varistor
 - He gas recovery with an additional storage bag
 - Other test items (Joint resistance, RRR measurement)

The results of MFM will be presented in another talk by Kento SUZUKI.

D1 magnet (MBXF)



- Beam separation dipole (D1) by KEK
 - Design study of D1 for HL-LHC within the framework of the CERN-KEK collaboration since 2011.
 - 150 mm single aperture, 35 Tm (5.6 T x 6.3 m), Nb-Ti technology.
 - Development 2-m long model magnets (3 units) at KEK
- Deliverables for HL-LHC
 - *1 full-scale prototype cold mass (LMBXFP)*
 - *6 series cold masses (LMBXF1-6)*
- Current status of D1 prototype and series production magnet
 - MBXFP1 : In preparation for the horizontal test at CERN
 - **MBXF1: The 1st test cycle was completed. The 2nd test cycle is being conducted.** ← This slide
 - MBXF5: Magnet assembly has been almost completed in Hitachi.
 - MBXF2: Coil winding and curing was completed.

Remaining issues in the KEK test facility

- Sufficient energy extraction with the allowable maximum voltage and complete He gas recovery is needed.
- Dump resistors of 25 m Ω or 50 m Ω were used for the cold test of MBXFP1.
 - 25 m Ω : Insufficient energy extraction resulted in incomplete He gas recovery.
 - 50 m Ω : The maximum voltage exceeded the allowable limit of 600 V for the DCCB of the power converter. Training above 106% of the nominal current could not be performed.
- Target: Maximum voltage < 600 V at the ultimate current
Magnet dissipation energy < Safety limit = 1.6 MJ
(Max. experienced energy in the cold test of MBXFP1)
- To satisfy these targets, varistor and additional He gas bag were implemented before the cold test of MBXF1.

Installation of the new EE system: Varistor




- Non-linear resistor: varistor (Metrosil[®])

- Composed of SiC disks
- C=32.01
- $\beta = 0.3$

- Technical meetings with CERN experts had been held twice so far, and some concerns attributed to “parallel connection scheme” were raised

- Imbalance of the circuit current
- Imbalance of the turn-on time

- KEK had proposed a “gradual powering plan” to check the EE system and setup for monitoring current imbalance using Rogowski coils (PEM Ltd.)




Recall

Additional Helium Gas Storage Bag

- Limitation of helium gas recovery at quenches of MBXFP1.
- Present capacity: 280 m^3 (#2: 80 m^3 , #4: 200 m^3)
- Helium gas at 13.23 kA w/ Varistors: 294 m^3 (prediction)
- Plan: new Helium gasbag (#4b, 40 m^3)
 - Total capacity: $320 \text{ m}^3 > 294 \text{ m}^3$
 - #4b Gasbag to be installed next to #4 Gasbag in the same tent warehouse
 - The gasbag is already available. The drawings are being prepared in a rush.




In the event of MBXFP1 quench



Additional Helium Gas Storage Bag

- New Helium gasbag (#40-sub, 40 m³):
 - construction and system commissioning completed in March 2023.
- In operation for MBXF1 powering test.



Test schedule

- Insertion of MBXF1 into the vertical cryostat: April 7
- 1st test cycle
 - Cool-down: April 12 – 17
 - 1.9 K Hi-pot test: April 17
 - System check: April 18 – 26
 - MFM at 3 kA: April 19
 - Training: April 27 – May 2
 - MFM: May 10 – 17
 - Current holding at the ultimate current: May 18
 - Warm-up: May 18 – 26
- 2nd test cycle
 - Cool-down: May 28 – 31
 - 1.9 K Hi-pot test: June 1
 - System check: June 2
 - MFM at 3 kA: June 2
 - Training: June 5
 - MFM: June 6 –

Test items


- 1.9 K Hi-pot test
 - Coils to ground: max 1.3 kV
 - Heater to coils: max 2.3 kV
- R14: The magnet shall fulfil the electrical test requirements during assembly and at 1.9 K.
- System check with Metrosil varistors
- MFM at 3 kA
- Training up to the ultimate current
 - R1: Ramp to the ultimate current with ramp of 12 A/s and flattop for 4 hours.
 - R21: Ramp to and from the ultimate current at ± 30 A/s
- MFM up to the nominal current
 - Perform Z-scan field measurement at [687, 1k, 3k, 5k, 7k, 9k, 10k, 11k, 12k, 11k, 10k, 9k, 7k, 5k, 3k, 1k, 687] A.
 - Perform DC-loop at the magnetic center.
 - Splice joint resistance and inductance measurements along with the field measurement.
 - R8: The integral multipoles of the magnet at 1.9 K and at nominal current shall target the range “upper limit, lower limit” as defined in Table 1.
 - R19: Each internal splice shall have an electrical resistance lower than 1 n Ω at 1.9 K.
- 1.9 K Hi-pot test (only at the end of the 2nd cycle)
- Warm-up
 - RRR measurement

1.9 K Hi-pot test

- Hi-pot test was performed after cool-down in the 1st and 2nd cycles.
- MBXF1 passed all the following tests.**

Criteria: Leak current $< 10 \mu\text{A}$ for 30sec





- Coil-GND: 1.3 kV
- Heater-GND: 2.3 kV
- Between adjacent heater strips: 2.3 kV




- Another 1.9 K Hi-pot test will be conducted before the 2nd warm-up.

Validation of varistor


3kA shutdown



- Signals from Rogowski coils and temperature of SiC disks has been monitored every shutoff/quench event to ensure no sign of imbalance promotion
 - At every higher current we perform 3kA shutdown to check reproducibility
- In the 1st cycle:
 - Current imbalance < 7%
 - Turn-on time imbalance < 300 μ s
- Detailed report can be found :
 - <https://indico.cern.ch/event/1282199/>



Training performance



Quench current of MBXF1

| | Quench # | Run ID | I_q (A) |
|--------------------|----------|--------|-----------|
| 1 st TC | 1 | 69 | 10639 |
| | 2 | 71 | 11353 |
| | – | 73 | 12099 |
| | 3 | 75 | 12260 |
| | 4 | 77 | 12331 |
| | 5 | 79 | 12326 |
| | 6 | 80 | 12559 |
| | 7 | 82 | 12778 |
| | – | 86 | 13214 |
| 2 nd TC | – | 508 | 13213 |

← $I_{nominal}$

← $I_{ultimate}$

← $I_{ultimate}$



Temperature: 1.9 K
 Ramp rate: 12 A/s or 30 A/s
 Quench detection: 0.1 V, 10 msec
 Quench protection: QPH and varistor
 Quench start location: quench antenna

- The training quenches started at a lower current with respect to the prototype.
- After 2 quenches, the magnet current reached the nominal current.
- The ultimate current was attained after 7 quenches.
- After thermal cycle, the magnet reached the ultimate current without quench, showing perfect training memory.


Quench start location

| | Quench # | Run ID | I _q (A) | Quench origin | Longitudinal position by QA | Position |
|--------------------|----------|--------|--------------------|---------------|-----------------------------|----------|
| 1 st TC | 1 | 69 | 10639 | Top coil | 1, 2, 3 | LE |
| | 2 | 71 | 11353 | Bottom coil | 2, 3 | LE |
| | 3 | 75 | 12260 | Top coil | 9, 10, 11 | RE |
| | 4 | 77 | 12331 | Top coil | 4, 5, 6 | SS |
| | 5 | 79 | 12326 | Bottom coil | 2 | LE |
| | 6 | 80 | 12559 | Bottom coil | 10 | RE |
| | 7 | 82 | 12778 | Top coil | 1, 2, 3 | LE |

Run 69: I_q=11353 A




ID and long. position of quench antennas (QAs)




- The quench position was identified by using quench antennas.
- The first quench occurred at LE same as MBXFP1. Then the quench origin changed with progressing training. No specific weak point was found.
- Normal training behavior was confirmed.

Current holding



- The current holding for 4 hours was successfully done at the nominal, nominal +200 A, and the ultimate current. This is the first time of current holding at the ultimate current for more than a half hour including the 2 m-long model magnets.
- The ramping-up/down up to the ultimate current with a ramp rate of 30 A/s was also successful.



Measured maximum coil voltage



- The maximum coil voltage was evaluated by the current shutdown and quench.
- Dump resistors of 25 m Ω or 50 m Ω were utilized for MBXFP1.
 - $R_{dump}=25$ m Ω \rightarrow Insufficient energy extraction
 - $R_{dump}=50$ m Ω \rightarrow Maximum coil voltage exceeding 600 V below the ultimate current
- In MBXF1, the varistors are confirmed to be effective to suppress the maximum coil voltage thanks to their non-linear $V-I$ characteristics.


MITTs, magnet dissipation energy

MITTs (MAAs)





- Through the commissioning of the Varistor system, it was found that parameter β has a current dependence and is smaller at lower current.
 - It turns out to be the higher MITTs and lower energy extraction at the current below 10 kA wrt the design.
- Nevertheless, profit of using the Varistor is obvious: the dissipation energy during the training quenches are significantly reduced wrt $R_{\text{dump}}=25 \text{ m}\Omega$ while the maximum voltage is below 600 V.

He gas recovery




- Measured evaporated He gas volume at the shutdown at the ultimate current = 290 m³ (as prediction) < Capacity of the He gas bag = 320 m³
- **Evaporated He gas could be completely recovered up to the ultimate current.** An increase in the capacity of He gas bag was successful.

Joint resistance



- Joint resistance was evaluated to be $0.645 \text{ n}\Omega < 1 \text{ n}\Omega$.

RRR measurement



- RRR was evaluated during the warm-up after the 1st test cycle. RRR is defined as the following equation.


$$RRR = \frac{R(293K)}{R_{low}}, R_{low}: \text{Normal resistance just before superconducting transition}$$

- RRR= 197 for MBXF1 (ex. RRR=217 for MBXFP1)

Summary

- Cold test of the first series production magnet (MBXF1) is being performed at KEK. The results are summarized as follows.
 - 1.9 K Hi-pot test → Passed
 - Successful validation of newly implemented varistor
 - Good training performance: 2 quenches to the nominal, 7 quenches to the ultimate
 - Reaching the ultimate without quench after thermal cycle, perfect training memory
 - Current holding at the ultimate for 4 hours → OK
 - Ramp to the ultimate with 30 A/s → OK
 - Complete recovery of evaporated He gas in the shutdown at the ultimate
 - Joint resistance < 1nΩ → OK
- MFM in the 2nd test cycle is ongoing. The 2nd test cycle will be completed in the week of June 12.

Current history



- Many shutdowns were repeated mainly for the validation test of the varistor.