



Status of D1

Tatsushi NAKAMOTO, KEK

**On behalf of CERN-KEK Collaboration for
D1 Construction for HL-LHC**

Acknowledgement

- KEK (in particular)

M. Sugano, K. Suzuki, Y. Arimoto, R. Ueki, Y. Ikemoto, H. Kawamata, N. Okada, R. Okada, H. Ohhata, A. Terashima, K. Tanaka, N. Ohuchi, T. Ogitsu.

- Univ. of Tokyo

N. Kimura.

- CERN (in particular)

E. Todesco, [J. C. Perez \(WPE\)](#), H. Prin, D. Duarte Ramos, C. Scheuerlein, H. G. Gavela, A. Devred.



- Hitachi

M. Yanagisawa, A. Yokogi, H. Togashi, T. Tahara, T. Chiba

- Fusac Technologies

T. Ichihara.

Japanese Contribution to HL-LHC: D1 magnets




- Beam separation dipole (D1) by KEK
 - Design study of D1 for HL-LHC within the framework of the CERN-KEK collaboration since 2011.
 - 150 mm single aperture, 35 Tm (5.6 T x 6.3 m), Nb-Ti technology.
 - Development 2-m long model magnets (3 units) at KEK
- Deliverables for HL-LHC
 - *1 full-scale prototype cold mass (LMBXFP)*
 - *6 series cold masses (LMBXF1-6)*

7 units x 7-m long cold masses

Status of D1, T. Nakamoto, KEK

Design parameters

	prototype, series production (7m)
Coil aperture	150 mm
Field integral	35 T m
Field (3D)	Nominal: 5.60 T, Ultimate: 6.04 T
Peak field (3D)	Nominal: 6.58 T, Ultimate: 7.14 T
Current	Nominal : 12.11 kA, Ultimate 13.23 kA
Operating temperature	1.9 K
Field quality	$<10^{-4}$ w.r.t B_1 ($R_{ref}=50$ mm)
Load line ratio (3D)	Nominal: 76.5%, Ultimate: 83.1% at 1.9 K
Differential inductance	Nominal: 4.0 mH/m
Conductor	Nb-Ti: LHC-MB outer cable
Stored energy	Nominal: 340 kJ/m
Magnetic length	6.26 m
Coil mech. length	6.58 m
Magnet mech. length	6.73 m 12 ton
Heat load	135 W (Magnet total) 2 mW/cm³ (Coil peak)
Radiation dose	> 25 MGy



Large-aperture single layer coil →

Mechanical support of a coil is challenging

Three 2 m model magnets were developed at KEK.



D1 Prototype Cold Mass: MBXFP1

Delivery of MBXFP1 to CERN



- The first D1 prototype cold mass was shipped from KEK on Jan. 25.
- The containership departed at Yokohama (Feb. 12) and arrived at Rotterdam (March 27). Delivery to CERN on April 4.
- The wooden box was totally covered by “mold”. Very kind support of TE-MSC-LMF and EN-HE-HH teams to pull out the cold mass under unpleasant condition. Material of shipping structure shall be modified at the next shipping for series cold masses.
- Data loggers were set on the cold mass. Thanks to barrier films with desiccant agents, the cold mass was kept in dry condition during the whole transportation. Measured acceleration was within $\pm 2G$ all the time except the loading onto the ship (-2.4 G and -2.8G).

Cryostatting of MBXFP1 at CERN




Courtesy of Delio Duarte Ramos,
Franco Julio Mangiarotti

- Many thanks to Herve and Delio for completing the cold mass and for cryostatting.
- Cryostatting report at WP3 meeting by Delio can be found at <https://indico.cern.ch/event/1296834/>
- Dimensions are mostly good and accepted. One deviation is detected between end cover and cold mass shell. Root cause will be investigated by CERN and KEK.
- Cold test at SM18 will be performed soon.


First series magnet: MBXF5 (in order of coil winding)

Recall Major NC in Manufacturing of MBXF5

- LT-1 and LB-1 coils for MBXF5 were completed.
 - Estimated coil pre-stress: Good.
 - LB-1: L120.7 (L) & 122.9 (R), LT-1: 121.7 (L) & 122.2 (R) (unit: MPa).
 - EDMS 2724784
- All components for the magnet were already fabricated.
- Collaring and yoking processes were successfully done in June 2022.
- NC: potential coil insulation damage was found after removal of the collaring-mandrel. EDMS 2753776.
 - Investigation is underway.



Spacers more than plan were removed from the RE side and the coil were exposed to the flat-rollers...



カラーマンドレル引き抜き後のコイル内径面外観検査で傷が確認された。
 ① LE側ボトムコイルポール端部：絶縁2層目・3層目の折り込み部に損傷
 ② LE側から700mm位置：ウエッジ、トップコイルケーブル表面に傷
 ③ RE側から2000mm位置：トップコイル・ボトムコイルケーブル表面に傷、MP部絶縁損傷
 ④ RE側から2100mm位置：トップコイルケーブル表面に傷

Actions for NC

- Investigation of insulation damage on the MBXF5 coil inner surface.
- Root cause analysis and redesign of the collaring mandrel for MBXF1 assembly.



- ✓ Technical meeting on Aug. 25, 2022 (EDMS 2773481)
- ✓ LHC-MBXFC-QN-0004 v.0.1 (EDMS 2753776 v.0.1)

- Assembly of MBXF1 magnet with modified collaring mandrel.
- Disassembly of MBXF5 magnet.
 - Detailed investigation of the insulation damage.
 - Proposal of coil repair.



- ✓ Technical meeting on Nov. 15, 2022 (EDMS 2799279)




- MBXF5 coil repair and validation



- ✓ LHC-MBXFC-QN-0004 v.1.0 (EDMS 2753776 v.1.0)



- Resume of MBXF5 magnet assembly

Microscopic Investigation after MBXF5 Disassembly








- September 2022.
- 9 damaged locations identified.
- No damage on the SC strand

Repair of MBXF5 Coils



After repair of the damaged insulation



Electrical soundness of the repaired coils was validated by electrical test (coil resistance, inductance, impulse test at 1.3 kV).

Present status MBXF5



- NC was closed in Feb. 2023 and the magnet assembly was resumed.
- Visual inspection of coil surface after yoking: OK.
- Manufacturing of MBXF5 was completed in June 2023.
- MBXF5 is currently situated in the vertical cryostat at KEK for powering test. But cooling has been suspended due to malfunction of a revolution indicator of the cold turbine.


Second series magnet: MBXF1 (in order of coil winding)

Status of MBXF1


- Coil winding of MBXF1 started in June 2022 following MBXF5 manufacturing.
- Due to a major NC of MBXF5, MBXF1 magnet was completed in February 2023 while MBXF5 was repaired.
- Powering test started in April 2023 at KEK's test facility where some upgrades were implemented for enabling the training quench up to the ultimate current (13.2 kA).
- Test results were satisfactory as shown in the next slides.
- MBXF1 will be the first series cold mass to be completed around early

Test facility upgrades



New extraction system



Varistor (Metrosil®)



Energy extraction section



- Non-linear resistance, varistors (Metrosil®) was installed
- Can suppress the maximum voltage below 600 V
- Expect an excellent energy-extracting performance


Additional gas storage bag



- Helium gas at 13.23 kA w/ Varistors: **294 m³** (prediction)
- New Helium gasbag was installed (#4b, **40 m³**)
 - Total capacity: **320 m³** > 294 m³
 - #4b Gasbag to be installed next to #4 Gasbag in the same tent warehouse

Training performance

Full scale magnets




Quench current of MBXF1

	Quench #	Run ID	I _q (A)
1 st TC	1	69	10639
	2	71	11353
	–	73	12099 ← I _{nominal}
	3	75	12260
	4	77	12331
	5	79	12326
	6	80	12559
	7	82	12778
2 nd TC	–	86	13214 ← I _{ultimate}
	–	508	13213 ← I _{ultimate}

Temperature: 1.9 K
 Ramp rate: 12 A/s or 30 A/s
 Quench detection: 0.1 V, 10 msec
 Quench protection: QPH and varistor
 Quench start location: quench antenna

- The training quenches started at a lower current with respect to the prototype.
- After 2 quenches, the magnet current reached the nominal current.
- The ultimate current was attained after 7 quenches.
- **After thermal cycle, the magnet reached the ultimate current without quench, showing perfect training memory.**

Field Quality: DC loop at the Z center - MBXF1 -





- Measured b_3 differs from the calculation by < 4 unit at $I_{nominal}$ (12.11 kA).
- For other allowed multipoles, measurement agrees with the calculation within 0.5 unit.

Predicted FQ (Integral) in the LHC cryostat

- MBXF1 -

Note: difference of ferromagnetic environment between KEK test stand and LHC cryostat.



- From the obtained field quality in the KEK cryostat, we estimated the actual field quality predicted in the LHC cryostat.
 - Requirements will be fulfilled in most of the harmonics.
- MFM of the D1 prototype cold mass at SM18 will be crucial to confirm the effect of the LHC cryostat on FQ.

Summary

- MBXFP1: Delivered to CERN in April 2023. Horizontal cold test in October is planned.
- MBXF5: After a major NC with coil insulation damages, the magnet was successfully recovered and completed in June 2023. The cold powering test has been suspended due to the trouble of the test facility.
- MBXF1: The test result of the cold powering test looks good. The final cold mass assembly at Hitachi is underway. Delivery to CERN as the first series cold mass is anticipated in May 2024.
- MBXF2: Coil winding was already started in February 2023 and magnet assembly (yoking) is underway.
- MBXF3: Coil winding will be started in October 2023.
- MBXF4: Coil winding is planned in 2024.
- MBXF6: The deliverables in JFY2023 will be the whole parts needed for the coil winding and the magnet assembly, but NOT including the actual manufacturing work at Hitachi. The coil winding is foreseen in April/May 2024.