



Status of CC cryomodules

Niklas Templeton – STFC Daresbury Laboratory
On behalf of the UK Crab Cavity collaboration









13th HL-LHC Collaboration Meeting – Vancouver (CA) – 26 Sep '23

Status of CC cryomodules

- UK involvement in HL-LHC Crab Cavities
- RFD SPS Cryomodule Build
 - Last 12 months
 - Challenges & Lessons Learnt
- DQW LHC Cryomodules
 - Challenges & Continuous Improvement




UK involvement in WP4 collaboration



omodules, N. Templeton, HL-LHC-CM-13, Vancouver

RFD As-Built Timeline (simplified)



Highlights (last 12 mo.)

- Top Plate Equipped - Warm Mag Shield, Thermal Screen, MLI
- New MLI skills!



Highlights (last 12 mo.)





- Bi Phase Cryoline delivered Feb '23
- 18 months late
- Several NCs found after delivery – some with major impact
- Pressure test failure
 - Rig design not fit for purpose



Highlights (last 12 mo.)


Bi Phase line NC resolution

- New Pressure Test Rig
 - Developed & delivered in-house min timescales
 - 54 components
 - 24 unique parts
 - FEA verification
- He Level Ports replaced in-house
- Re-qualification tests passed ✓




Highlights (last 12 mo.)

- Bi Phase, Tuner & Top Plate integration (steps 3-5)




Highlights (last 12 mo.)

- Cavitystring to Top Plate load transfer (step 6)



Highlights (last 12 mo.)

- Thermal Screen & 50K MLI (step 9)



Highlights (last 12 mo.)


- Lower OVC integration



Highlights (last 12 mo.)

Many CERN visitors for knowledge transfer & build support:

- RF
- Fibre optic strain gauge
- Survey & alignment
- Cryo instrumentation
- TIG & orbital welds
- Tuner assembly
- Management & load transfer oversight
- Transport tooling & logistics



Highlights (last 12 mo.)

- Elegant solutions to incidental challenges
- Faster in-house manufacturing
- Vacuum & pressure test rigs & procedures
- 3D printed leak test tools (clamshells)
- Qualification of assembly tooling & infrastructure
- *Organisational evolution*



Assembly Procedures

- Based on poster logic + tooling & infrastructure
- To troubleshoot & de-risk technical tasks
- 'BOM kits' can be prepped by sub-step
- Extremely valuable for LHC CC Cryomodules
- Includes requirements, torques & sign-off checklists for travellers

Step 11

- 1 Installation of insulation vacuum instrumentation
- 2 Installation of secondary beam line vacuum assemblies
- 3 Installation of blow-off valve for insulation vacuum
- 4 Inspection and leak check of UHV secondary line

11-3 Install Blow-Off Valve


32	VALVE FLANGE (INNER)	UNIONFITTELLA	Ø 70x10 (Ø10)
33	VALVE FLANGE (OUTER)	ADAPTORFLANG Ø 80x10	Ø 80x10 (Ø10)
34	SPRING WIRE	SPRING	Ø 1.5x100
35	WIRE CABLE - MOUNTING	WIRE CABLE	Ø 1.5x100
36	WIRE CABLE - MOUNTING	WIRE CABLE	Ø 1.5x100
37	WIRE CABLE - MOUNTING	WIRE CABLE	Ø 1.5x100
38	WIRE CABLE - MOUNTING	WIRE CABLE	Ø 1.5x100

- Install Valve Flange with O-ring, relief spring and ancillaries as shown
- Wire rope to be double looped through crimped collars (see image) but should be as taught as possible without excessive bending



Some RFD Metrics


- Total Assembly Procedures = **840 pages!**
- Cryomodule Components: **10K (>5k unique)**
- Tooling drawings: **524**
- **28 NCRs Resolved**
- Total build team effort **<9 FTE per year!**
 - FT engineers & technicians + shared specialist & support staff
 - *not including apprentice effort



Challenges & Lessons Learnt

- Integration complexity, sensitivity & design 'teething'
- Recruitment & retention
- Supplier QA Management
- Internal QA & EDMS/MTF management effort
- Material specifications, traceability, coating & cleaning
- Co-ordinating specialist support & visits

UK DQW Schedule



- RFD build delays impacted DQW progress
- RI Cavity Delivery delays






DQW Tooling & Infrastructure

(Re)design work:

- Top Plate Lifting Gantry Mods ✓
- Transfer Table ✓
- Cavitystring tooling – nearly done



Next:

- Anti-shock transport frame
- Bi Phase Qualification Rig



DQW Cryomodule Procurement

- Beamline vac equipment - received or on-order
- Cavitystring Trolley II - received
- 2x common string trolley tooling - on-site
- OVC tender - live
- Warm Mag Shield tender - live
- Cryolines materials & fabrication - on-going (critical)



DQW Improvements

More info in WP4
break-out talks

- More staffing & more experience

Infrastructure upgrades


- Parts management workstation ✓
- Build area flooring
- Improved storage, workbenches & layout


Parts management

- 5S consultancy discussions ✓
- ID > QC > Processing > Label + Storage

Technical sub-team

- Dimensional control
- Mock assembly
- Managing cleaning etc.
- BOM kit prep.






Status of UK CC Cryomodules, N. Templeton, HL-LHC-CM-13, Vancouver

Shipping

- Agreed with CERN to use CERN transport team and truck



Formulaire_demarrage x Liste_Poids_lourd x Formulaire_Poids_Lourds x

EN ENGINEERING DEPARTMENT

CERN

Poids Lourds

N° CERN **384**

Marque : MERCEDES-BENZ	Type : ANTOS 1832
Plaques : GE 565100	Mise en service : 29.10.2015
N° chassis : WDB 963 003 1L9 878 82	Prix : CHF 114 500,00
Détenteur : MAZZARINO THIERRY 160364	Hayon : LV-00283
Contrôle technique : <input type="text"/>	N° commande : CA 6041122
Permis : Permis 384	Plan : <input type="text"/>

Longueur : 9500
Largeur : 2550
Hauteur plateau : 3655
Poids à vide : 9000
PTRA : 18000
PTAC : 18000
Charge Utile : 9000

Recherche par n° CERN Recherche par plaque Effacer la recherche

Shipping

- Documentation is progressing well with tight coordination between AJBM + Ben Lewis (STFC Logistics) + Simon Barriere (CERN)

RFD Crab Cryomodule Shipping Items

Category	Grouped sub-system	Total ex. VAT(€)	Country of origin	Commodity code	Notes	Notes (to be deleted when complete)	Sub-System (to be deleted when complete)	Unit cost ex. VAT (€) (to be deleted when complete)	Quantity Required to be deleted when complete	Total ex. VAT(€)	Notes (Ofelia - cost from DQM manufacturing (€GIP from KDFP))	KCHF part TTC	Notes	
Cryomodule	2x Jacketed RFD cavities	2079	CH		Shipped from CERN		RFD Cavity	849.4	2	1699			GIP to CHF exchange rate: 1 GIP*	
							RFD Helium Vessel	178.0	2	356			1145	
							Cold Magnetic shield	11	2	24			240	
	RF couplers	582	CH		Shipped from CERN	FPC wire from UR1_SHIPMENT_TRANSPORT_LIST_rev05_17-09-21	RFD Full set of HOMs	146.1	2	292			146.1	197
							RFD Probe	14.8	2	30			14.8	20
							RFD Fundamental Power Coupler	74.2	2	148			74.2	100
							RF Internal lines (FCM, pick-up, FPC double tube)	111.3	1	111			111.3	150
	2x Mechanical tuners	163	CH		Shipped from CERN		RFD Tuner	81.6	2	163			81.6	110
	Outer vacuum chamber	126	Italy				Outer Vacuum Chamber	126.1	1	126			126.1	170
	Outer magnetic shield	43	UK			Andy confirmed price from RFS	Outer Magnetic shield	37	1	37			37.1	50
	Thermal shield	63	CH		Shipped from CERN		Thermal shield	63	1	63			63.1	85
	Multi-layer insulation blankets	18	France		Shipped from France to UK by UPS, numéro de suivi 122470A38600100637, add 2 other refs		Multi-Layer Insulation	19	1	19			18.5	25
	Cavity support system	27	UK			15140+Vat for blade support assemblies from ASSP; Cavity support system 59992 from TSW	Cavity Support System	19	2	37			18.5	25
	Alignment measurement system	37	CH		Shipped from CERN		Cryomodule Support System	11	1	11			11.1	15
	Cryogenic and vacuum instrumentation	119	CH		Shipped from CERN		Cavity PSI Alignment System	37	1	37			37.1	50
	8x Vacuum bellows (various)	89	CH		Shipped from CERN		Vacuum Instrumentation	89	1	89			89.0	120
	4x Vacuum valves	356	CH		Shipped from CERN		Cold to Warm Transition and Shielded Inter-cavity Bellows	30	1	30			29.7	40
	Cryogenic pipework	152	UK			Andy confirmed cost from OradeaRFS; inc upper line support	Vacuum Instrumentation	22	4	89			22.3	30
	Fasteners and ancillaries	74	UK				Vacuum Valves	89	4	356			89.0	120
	Cryogenic ancillaries	20	UK				Cryogenic internal lines	100.0	1	100			115.0	155
Shipping and transportation hardware	35	UK		Temporary import required for transport		Welding internal lines during assembly	25.0	1	25			51.9	70	
TOTAL ex. VAT (€)		3983				Fasteners and ancillaries	74	1	74			74.2	100	
TOTAL inc. VAT (€)		4779				Helium level, gauge bells total 2100-VAT from RFS; What else should be included here?	22	1	22			22.3	30	
						8845+VAT for frame from GIM; 11250+VAT for arms from GIM	Cryogenic Safety Systems	30	1	30			30	
							Anti-shock Transportation Frame	1	1	1			1	
							Transport cradling	0.2	1	0.2			0.2	
							Fasteners and ancillaries							
										3974.2593				
										4769.1112				

DQW Series Build Timeline (Sep '22)

