

# Status of Canadian Contribution to WP4

Bob Laxdal

TRIUMF Hi-Lumi Technical Coordinator

Sept. 25, 2023



**TRIUMF is  
Canada's  
particle  
accelerator  
centre**





 **TRIUMF**




**June 25, 2018**  
**“Great science knows no borders.”** Minister Kirsty Duncan

Canadian Minister of Science and Sport Kirsty Duncan announces 10M\$ support for TRIUMF to build 5 Hi Lumi LHC RFD Crab Cavity Cryomodules  
Working with the Canadian research community and industry, TRIUMF will lead the production of the cryomodules with a \$2 million in-kind contribution for a total project value of \$12 million.



# Scope and constraints


# High Luminosity Canada – part of global collaboration (CERN, USA, UK) that will deliver Crab Cavity modules – essential for the luminosity increase at ATLAS and CMS



# Scope of Canadian Contribution


## Scope:

- TRIUMF to work with CERN and UK colleagues to develop RFD cryomodule design, assembly tooling and fixtures, assembly procedures
- TRIUMF to receive 10 dressed RFD resonators from US-AUP, to re-qualify the cavities, to install the fundamental power coupler and to assemble each pair of RFDs into five hermetic strings
- TRIUMF to assemble hermetic strings into five cryomodules
- TRIUMF to qualify the cryomodules through testing at TRIUMF before packaging and shipping to CERN



# Cavity Re-qualification at TRIUMF


- CERN acceptance of AUP cavities will happen at TRIUMF
- Acceptance criteria are established in a document from AUP in consultation with TRIUMF
- We will receive qualified cavities under vacuum and with test coupler and vacuum diagnostic on board
- The acceptance document itemizes a series of warm and cold measurements to confirm that the cavity has not been degraded during transport and is acceptable to be installed in the CM.
- A cavity test is expected to take 10 days





# Cryomodule Qualification/Commissioning at TRIUMF

- Hardware checks
  - Check the operation of diagnostics at room temperature
  - Leak check and pressure test – all volumes
  - Measure warm rf frequency, alignment
- Qualify at 77K
  - Cooldown to 77K
  - leak check, alignment check
  - Check rf frequency
- Qualify at 4K
  - Cooldown cold mass to 4K
  - Check alignment
  - Check rf frequency
  - Check operation of tuner
  - Power each cavity independently to check gradient and Q
  - Check static load to 4K based on falling level



The testing will be done in the SRF test area. A CM test is expected to take 4 weeks with 1 week of preparation, 2 weeks of testing and 1 week of warm-up and removal.

The amplifier will be supplied by CERN

# Project Strategy


- The project strategy calls for procurement of parts for a single cryomodule, TCM0, followed by procurement of parts for the production series TCM1-4
- Gate 3A enabled us to launch procurements to support cavity testing, infrastructure upgrades and for parts to prepare prototype cryomodule (CM) as drawing readiness allows
- Project slippages due to Covid and other forces vs. boundary conditions on project funds are having an impact on this strategy
  - Shifting timelines for
    - TCM0 cavities from AUP
    - Released drawings and parts from CERN
  - Fixed timeline for spending the funds

Project Milestone	Date	Inputs
Gate 1 ✓	Dec 2019	Conceptual design review, preliminary scope def'n
Gate 2 ✓	Aug. 2020	Final scope def'n, detailed budget
Gate 3A TCM0 ✓	May 2021	TCM0 design

# Funding and priorities

- Due to the nature of the funding agreement ALL funds for the project must be spent before April 2025
- Project slippage means that now spending is a major risk to the Canadian contribution and strategies are being modified
- TRIUMF has presently spent or committed 42% of the funds - TRIUMF will have to spend the remaining 58% in the next 18 months
- Risk mitigation requires
  - Ordering production quantities as soon as possible (In addition to TCM0 procurements)
  - Timely release of drawing packages for long lead items of series
  - Prioritization for higher cost items
  - Timely arrival of items where CERN is doing a group purchase for UK and Canada so cheques can be written

Year	Spent	Encumbrance	Total	Available
<b>21-22</b>	\$338,027	\$0	\$338,027	\$9,661,973
<b>22-23</b>	\$202,100	\$0	\$202,100	\$9,459,873
<b>23-24</b>	\$356,297	\$3,304,595	\$3,660,892	\$5,798,981
<b>Total</b>	<b>\$896,424</b>	<b>\$3,304,595</b>	<b>\$4,201,019</b>	<b>\$5,798,981</b>



■ Spent ■ Encumbered ■ Remaining

# Progress Milestones

<b>Milestone</b>	<b>Application</b>	<b>Achieved</b>
4k-2k Cryo insert qualified	Infrastructure	Nov 2022
OVC Drawings released	TCM0	Apr 2023
OVC tender released	TCM0	May 2023
OVC material order issued	TCM1-5	Jun 2023
Clean room tender released	Infrastructure	Jun 2023
Sector Valves received	TCM0	Jul 2023
OVC order issued (Axton)	TCM0	Jul 2023
Mu-metal tender released	TCM1-5	Jul 2023
Clean room contract issued	Infrastructure	Sep 2023
Mu-metal contract issued	TCM1-5	Sep 2023
MLI tender issued	TCM1-5	-


# Infrastructure preparations

## Progress Milestones - Infrastructure

<b>Milestone</b>	<b>Application</b>	<b>Achieved</b>
4k-2k Cryo insert qualified	Infrastructure	Nov 2022
OVC Drawings released	TCM0	Apr 2023
OVC tender released	TCM0	May 2023
OVC material order issued	TCM1-5	Jun 2023
Clean room tender released	Infrastructure	Jun 2023
Sector Valves received	TCM0	Jul 2023
OVC order issued (Axton)	TCM0	Jul 2023
Mu-metal tender released	TCM1-5	Jul 2023
Clean room contract issued	Infrastructure	Sep 2023
Mu-metal contract issued	TCM1-5	Sep 2023
MLI tender issued	TCM1-5	-


# TRIUMF SRF Facilities

- The legacy from the development of the TRIUMF superconducting linacs is an SRF facility and know-how, unique in Canada,
- The lab supports the in-house accelerator program, external collaborations as well as SRF research and, through NSERC funds, a varied student program in close partnership with U.Victoria



# TRIUMF SRF Facilities – Hi-Lumi Upgrade


- To improve the throughput of Hi-lumi CMs we are installing a second clean-room in the ISAC-II experimental hall
- The clean room will allow dedicated string assembly over the life of the project – ready March 2024







# TRIUMF SRF Facilities

# New Hi-Lumi Area






# Preparation for cavity testing

- TRIUMF will requalify the AUP cavities upon delivery from JLab
- TRIUMF has upgraded the cavity test facility in preparation for cavity delivery
  - Prepared and qualified cryo-insert for multi-purpose cryostat to test dressed cavities at 2K in jacketed mode
  - Upgraded cavity test diagnostics
  - Upgraded 2K pumping capacity
- **Ready for jacketed 2K testing of AUP cavities**







# Dummy cavity for TCM0

- AUP anticipates only one TCM0 cavity in Spring 2024
- TRIUMF is fabricating a Dummy cavity
  - Identical LHe volume and mass as the actual cavity
  - Identical beam and helium interfaces as the RFD cavity
  - Identical support interfaces
- Will be used for testing prior to cavity delivery and during assembly of TCM0 cavity string



# Infrastructure in the queue

- String assembly frame
  - Based on UK design
  - Ready to send for manufacture
  - Rails and castors received
- Cavity manipulation/rinsing tooling
  - In design
- Top assembly frame
  - Detailed design
- Cryomodule trolley
  - Detailed design



# Infrastructure upgrade status

		specified	designed	ordered	received
Clean room upgrade	Garments	✓		✓	✓
	Particulate monitoring	✓		✓	✓
	Vacuum equipment	✓		✓	✓
	New clean room	✓		✓	
Cavity testing	4k/2k insert	✓	✓	✓	✓
	Test diagnostics	✓	✓	✓	✓
	2k pumping capacity	✓	✓	✓	✓
Assembly fixtures	Hermetic string cart	✓	✓	parts ✓	parts ✓
	Dummy cavity	✓	✓		
	Cavity handling tooling	✓	50%		
	Top down assembly stand	✓	90%		
	Cryomodule trolley	✓	50%		



# Cryomodule Fabrication

## Progress Milestones - Cryomodules

<b>Milestone</b>	<b>Application</b>	<b>Achieved</b>
4k-2k Cryo insert qualified	Infrastructure	Nov 2022
OVC Drawings released	TCM0	Apr 2023
OVC tender released	TCM0	May 2023
OVC material order issued	TCM1-5	Jun 2023
Clean room tender released	Infrastructure	Jun 2023
Sector Valves received	TCM0	Jul 2023
OVC order issued (Axton)	TCM0	Jul 2023
Mu-metal tender released	TCM1-5	Jul 2023
Clean room contract issued	Infrastructure	Sep 2023
Mu-metal contract issued	TCM1-5	Sep 2023
MLI tender issued	TCM1-5	-

# Cryomodule fabrication milestones

- Drawings for OVC completed and RFQ issued
  - Considerable effort to translate EU/CERN specifications for NA vendors
  - Good learning exercise
- Contract for one outer vacuum chamber (OVC) issued to Axton (Vancouver)
- Material for five OVCs ordered from Outokumpu – delivery in Oct. 2023
  
- Tender complete for 5 mu-metal shields
- Successful bidder selected
- First article by Feb. 2024 – final article by Dec. 2024






# First articles received

First articles shipped from CERN to TRIUMF

- 5 Sector valves were received by TRIUMF SRF Group on July 21, 2023



# Cryomodule fabrication strategy

CM string assembly requires cavities from AUP, FPCs and beamline assemblies from CERN – first articles are required to assemble TCM0.

Next items for series production where TRIUMF requires released drawings

- MLI blankets
- Thermal shield
- Cold tuner frame and warm tuner actuator assembly
- Cryogenic internal lines and supports


TRIUMF also requires delivery of CM parts in CERN scope and group purchased parts (at least for first articles):

- Cavity testing - rf components – Jan 2024
- String assembly – Mar 2024
- Cryomodule assembly – Apr 2024
- Cryomodule testing – May 2024



<b>AUP Delivery Projection</b>			
<b>Cavity Pair</b>	<b>Module</b>	<b>Early dates</b>	<b>Late dates</b>
Pre-series Cavity	TCM0	Mar 2024	-
Series 1 and 2	TCM1	May 2024	Apr 2025
Series 3 and 4	TCM2	Sep 2024	Jun 2025
Series 5 and 6	TCM3	Nov 2024	Jul 2025
Series 7 and 8	TCM4	Jan 2025	Sep 2025
Series 9 and 10	TCM5	Mar 2025	Oct 2025

# Timeline



# Summary

- Revamping strategy to address finite time window for available funds
  - Prioritizing with CERN the release of drawings for CM series to launch other long lead items
  - Milestone dates for CERN deliverables communicated to CERN
- Preparing TCM0 and series production CMs
  - OVC production launched – TCM0
  - OVC material ordered - series
  - Mu-metal vendor selected – series
  - Sector valves received from CERN
- Cavity testing infrastructure
  - 4k/2k assembly tested and meets all specs
  - Pumping station installed
  - Ready for 2k testing
- New clean room ordered for March 2024 – tooling in preparation

