





WP4-Series cryomodules design

13th HL-LHC Collaboration Meeting, CERN – 25-28 September 2023


Teddy Capelli on behalf of the WP4 collaboration

LHC Cryomodules overview



■ RFD Cryomodule

- Overall dimensions (L/l/h): 3350/950/1900mm
- Mass : ~4400kg
- Cavities : RadioFrequency Dipole
- HOM filters : 4 pces (2 per cavity)
- Pick Up Antenna : 2 pces (1 per cavity)
- Position of installation : Point 1 (Before and after ATLAS)



■ DQW Cryomodule


- Overall dimensions (L/l/h): 3120/1000/1800mm
- Mass : ~4300kg
- Cavities : Double Quarter Wave
- HOM filters : 8 pces (4 per cavity)
- Pick Up Antenna : 2 pces (1 per cavity)
- Position of installation : Point 5 (Before and after CMS)



Overview of cryomodule design updates



- Detailed design and simulation for DQW/LHC cryomodule
- New input imposing a modification of the design of both DQW and RFD cryomodules
- Optimisation of the design integrating the feedback from RFD cryomodule
 - Feedback provided by STFC on RFD assembly :
 - Clean room
 - String assembly
 - MLI design and installation

see presentations of N.Templeton & E.Jordan



OVC updates and simulations

- Design optimization for mechanical performances and new interfaces needed for LHC
- Simulations :
 - Operation and transport load cases check
 - Overall buckling check
 - Bolted and welded joints checks




DQW OVC simulations

Total deformation

B: Full model
Total Deformation
Type: Total Deformation
Unit: mm
Time: 1 s

1.1655 Max
1.036
0.90651
0.77701
0.64751
0.518
0.3885
0.259
0.1295
0 Min




- Load case : Normal operation
- Vacuum inside / Atmospheric pressure outside
- The overall deformation impact cavity alignment

Sub modelling for stress analysis


G: Submodel bottom
Stress Intensity
Type: Stress Intensity
Unit: MPa
Time: 1 s

3733.6 Max
200
133
114.02
95.006
76.013
57.013
38.016
19.019
0.12346 Min



I: Top_submodel Max Assembly
Stress Intensity
Type: Stress Intensity
Unit: MPa
Time: 2 s


386.4 Max
200
133
114
95.006
76.01
57.013
38.016
19.019
0.022656 Min



Stress intensity

B: Full model
Stress Intensity
Type: Stress Intensity
Unit: MPa
Time: 1 s

646.69 Max
133
116.38
99.75
83.125
66.5
49.875
33.25
16.625
0.0001524 Min



OVC strength assessment :

See EDMS 2920955 - DQW vacuum vessel strength assessment
Courtesy T. Hernandez – E.Cano Pleite

RFD OVC simulations



C: Static Structural FULL MODEL

Total Deformation

Type: Total Deformation

Unit: mm

Time: 1 s





Total deformation

- Load case : Normal operation
- Vacuum inside / Atmospheric pressure outside
- The overall deformation impact cavity alignment

Static Structural


Stress Intensity

Unit: MPa



Stress intensity

Sub modelling for bolted joint analysis



Worst bolt (combination of maximum axial, bending, shear, torsional)



Conditions	Preload [N]	Axial Force [N]	Bending moment [N·mm]	Torsional moment [N·mm]	Shear force [N]	Safety factor
Frictional	22600	22719	9250.7	512.3	2016.8	1.3

OVC strength assessment :


See EDMS 2272855 - RFD vacuum vessel strength assessment
 Courtesy T. Hernandez – E.Cano Pleite

Cryogenic for series cryomodules

- Design and drawing for manufacturing for DQW cryogenic lines
- Detailed study of the cryogenic extension for LHC
- Definition and integration of cryogenic instrumentation for DQW cryomodule
- Update RFD drawing with feedback from RFD/SPS
 - Minor geometry changes
 - Material specification update





Cryogenic Safety extension



DQW Cryogenic biphas support

- Adapted from RFD design
- Design optimization for minimal deformation and assembly sequence improvement
- Operation and transport mechanical check
- Overall buckling check
- Welded joint stress assessment



Type: Stress Intensity
Unit: MPa
Time: 1
04/08/2023 17:35

Stress intensity (testing load case)


170.41 Max
151.48
132.54
113.61
94.673
75.738
56.804
37.869
18.935
0.00014114 Min



Load Multiplier (Nonlinear): 36.151
Unit: mm
04/08/2023 17:58

Buckling

1.0056 Max
0.89385
0.78212
0.67039
0.55865
0.44692
0.33519
0.22346
0.11173
0 Min




RFD Cryogenic support strength assessment

See EDMS 2901074

Courtesy L.Giordanino

Cryogenic biphas support alternative solution for both DQW and RFD




- Alternative solution:
 - Bolted design (no welds required)
 - Reduction of cost of manufacturing
 - Easier installation on cavities
 - Modular design (easy to change)
- Preliminary analysis feedback:
 - Larger deformation : optimisation needed
 - Safety factor of screw to be checked

G: Model with fully bolted configuration

Total Deformation
Type: Total Deformation
Unit: mm
Time: 2 s
9/22/2023 4:59 PM

3.27777 Max
2.9135
2.5493
2.1851
1.8209
1.4567
1.0926
0.72837
0.36419
0 Min



Stress intensity


G: Model with fully bolted configuration

Equivalent Stress
Type: Equivalent (von-Mises) Stress
Unit: MPa
Time: 2 s
9/22/2023 5:01 PM

430
175
150
125
100
75.005
50.007
25.000
0.008718 Min


Cavity support DQW & RFD for LHC

- Material update for the 3 adjustment sets
- Blade connexion head change – **on-going**
(suppression of the angular problem + possibility to assemble from top)
- DQW detailed design based on RFD + simulation – **on-going**




Thermal screen updates RFD & DQW



Difficulties to access the fasteners connecting the pipe to the top plate





RFD/SPS design



Welding test with optical mechanical measurement




LHC series design




Thermal screen DQW & RFD

- Strength check
- Fasteners preload
- Thermal analysis
- Thermo-mechanical sim. of cooldown




Stress intensity



D: only mechanical loads
Stress Intensity 5
Type: Stress Intensity
Unit: MPa
Time: 1
25/08/2023 10:56


27.426 Max
24.378
21.331
18.284
15.237
12.189
9.142
6.0947
3.0474
9.3999e-5 Min



Total deformation

D: only mechanical loads
Total Deformation 2
Type: Total Deformation
Unit: mm
Time: 5
25/08/2023 10:53

0.6915 Max
0.61467
0.53784
0.461
0.38417
0.30733
0.2305
0.15367
0.076834
0 Min





Thermal shield analysis :

- See EDMS 2869783 - Bolted clamp evaluation
 - See EDMS 2936498 - Thermo-mechanical simulations for RFD
 - See EDMS 2894500 - Thermo-mechanical simulations for DQW
- Courtesy J.Swieszek

LHC integration

- Integration and position of motorized jack (collaboration with BE/GM and ATS/DO)
- Vacuum interconnexion (collaboration with TE/VSC and ATS/DO)
- Position and routing of RF lines (collaboration with S.Calvo SY/RF)
- Integration and position of the connexion boxes for cryogenic instrumentation
- Request from survey team to change the WPS reserved space position
- Accessibility of the tuner actuation in the Tunnel
- Design of the safety extension to improve accessibility to cryogenic equipment
- Detailed integration in collaboration with G.Cipolla (SY/RF) and the team of P.Fessia (ATS/DO)



LHC integration– courtesy G. Aparicio – P. Fessia - ATS/DO

DQW assembly sequence updates

Technologies and contact

Radiofrequency	Survey/Alignment	Cryogenic lines	Vacuum	Design	Tools
Coordinator: Rina DELEGA EN: ROBERTOVAL Subcontractor: CALVO	Coordinator: Massimo SISON Worker: ROSSI	Coordinator: KENNETH BRUGGEMAN Engineer: GUYMONT	Coordinator: Chiara PIZZOLINO Engineer: FIORE Designer: GABRIELE Worker: BRILLI	Coordinator: GIULIA CAPRIOLA Engineer: ANTONIO Designer: TIZIO Worker: BIANCHI	Coordinator: PAUL APFELDER Worker: MICHIELSEN

Manufacturing and contact

CDM Manufacturing	STC
Coordinator: Maria CARLA LACI Worker: BARRIQUET	Coordinator: Mike TEMPLETON (STFC) Worker: PETER LAMBERT (STFC) Designer: BERTY LAMBERT (STFC) Designer: ANDREW BERRY (STFC) Designer: DANIEL BERRY (STFC) Designer: ANDREW BERRY (STFC)



Overview of assembly sequence – DQW CRYOMODULE for LHC

- Iterative work (updating individual component -> Cryomodule -> Assembly seq.-> Compatibility with spec)
- >12'000 parts in the cryomodule (Wo tooling)
- Different team involved with specific requirements (Cryo, RF, Vacuum, Survey, ext. collab, Manufacturing)
- 7 top configurations (transport, test x2, storage, LHC x4)




Thermal budget

Evaluation and optimisation of the DQW cold warm transitions

- Similar design between RFD and DQW (longer CWT on jumper side)



Calculation of thermal loads for every thermal intercept layout possible




Results

Intercept	Heat loss [W]	Heat gain [W]	Heat loss [W]	Heat gain [W]	Heat loss [W]	Heat gain [W]
Q 2 K	2.00	0.00	0.00	0.00	0.00	0.00
Q 80 K	15.00	0.00	0.00	0.00	0.00	0.00
Q 1 300 K	-10.40	0.00	0.00	0.00	0.00	0.00
Q 2 300 K	-6.60	0.00	0.00	0.00	0.00	0.00



!! No 4-20K circuit in SPS today !!!

Thermal analysis cold-warm transition
See EDMS 2433067 - J.Swieszek EN-MME

C: CWT, cavity side, short
Temperature
Type: Temperature
Unit: K
Time: 1
27/03/2023 12:33



C: CWT, cavity side, short
Total Heat Flux
Type: Total Heat Flux - Top/Bottom
Unit: W/mm²
Time: 1
27/03/2023 12:34



	Static heat loss
Q 2 K	2 W
Q 80 K	15 W
Q1 300 K	-10.4 W
Q2 300 K	-6.6 W

Thermal budget

Thermal simulation/calculations of the cryogenic instrumentation and safety extension








Table 3 : Heat-loads

Temperature range	Symbol	Heat-load [W]
300K - 80K	q_{80K_out}	8,5
80K - 2K	q_{2K_in}	2,2
300K - 2K	q_{in}_out	4,1

Thermal evaluation of Cryo. Instrum.
 See EDMS 1760706
 Courtesy J.Swieszek

A: Gas conductivity insulated
 Temperature
 Type: Temperature
 Unit: K
 Time: 1
 1/10/2020 11:02 AM





	Heat loss, 2 K [W]	Heat loss, 80 K [W]
Solids conduction + surface-to-surface radiation	0.3	4.3
He gas conduction	0.3	-
Multi layer insulation	0.004	0.43
TOTAL	0.7	4.8

Thermal evaluation of Cryo. Safety extension
 See EDMS 2323043
 Courtesy E.Cano Pleite

Thermal budget

Evaluation of the new RF coaxial lines designed by the team of E.Montesinos – SY/RF

- Similar modular design between RFD and DQW
- Coated stainless steel straight section
 - Coating 5 μm copper:
 - inner face of external tubes
 - outer face of internal tubes
- Copper elbows and connexions
- 2D axis-symmetric modelling used for simulation



Thermal analysis :



See EDMS 2367094 - Simulation of RF coaxial line (V-HOM, H-HOM for RFD)

Courtesy J.Swieszek – L.Giordanino

Thermal budget

Evaluation of the new RF coaxial lines

- Parametric study : influence of the current wave position



move	Q 2K (W)	Q therm1 (W)	Q therm2 (W)	Q 300K (W)
0	0.565	7.064	1.192	-5.494
0.02	0.517	7.009	1.163	-5.494
0.04	0.481	6.974	1.152	-5.735
0.06	0.482	6.982	1.171	-6.057
0.08	0.518	7.028	1.204	-6.248
0.1	0.566	7.080	1.229	-6.181
0.12	0.594	7.105	1.230	-5.899
0.14	0.583	7.087	1.208	-5.590

worst scenario
(biggest heat loss
in the 2K bath)

- Thermal contact resistance included in the study :
 - Copper / St. Steel
 - St. Steel / St. Steel

h_cu_ss	Q 2K (W)	Q therm1 (W)	Q therm2 (W)	Q 300K (W)
h_cu_ss_2MPa	0.542	6.779	1.231	-5.386
perfect contacts	0.594	7.105	1.230	-5.899

Thermal analysis :

See EDMS 2367094 - Simulation of RF coaxial line (V-HOM, H-HOM for RFD)

Courtesy J.Swieszek – L.Giordanino

Thermal budget RFD

	Static loads		
	2 K bath	10 K intercept	80 K intercept
Radiation [2] [5]	3.4	-	30
CWT [6]	6	1	50.6
Supports [7] [8]	0.4	2.1	8
	0.5	0.9	5
FPC [9] [10] [11]	2.6	2.4	44.4
VHOM lines [12]	0.3	1	10.8
VHOM antennas [13]	-	-	-
HHOM lines [12]	0.3	1	10.8
HHOM antennas [13]	-	-	-
Pickup lines [14]	2	-	10.6
Pickup antennas [13]	-	-	-
Tuner [15]	0.8	-	10.2
Instrumentation [2] [16]	2.3	-	10
He level sensor [17]	0.4	-	0.8
Cryo safety device [18]	0.7	-	4.8
Beam screen [19]	-	-	-
Beam impedance in cavity [20]	4	-	-
Cavity [21]	-	-	-
Static			
TOTAL	23.7	8.4	196

Thermal budget report for RFD:

See EDMS 2310389 - Thermal budget RFD cryomodule
 Courtesy J.Swieszek – L.Giordanino

Thermal budget DQW

	Static loads (estimates)		
	2 K bath	10 K intercept	80 K intercept
Radiation	3.4	-	30
CWT	5.5	1	50.6
Supports	0.4	2.1	8
	0.6	1.1	6
FPC	3	2.8	50
HOM lines	0.9	7.2	42
HOM antennas	-	-	-
Antennas coax lines	4	-	21.2
HF and Field antennas	-	-	-
Tuner	0.8	-	10.2
Instrumentation	2.3	-	10
He level sensor	0.4	-	0.8
Cryo safety device	0.7	-	4.8
Beam screen	-	-	-
Beam impedance in	4	-	-
Cavity	-	-	-
Static			
TOTAL	26	14.2	233.6

Thermal budget report for DQW to be updated

Thermal budget estimate DQW/SPS - 2016

EDMS 1729079	
	2 K bath
<i>Static</i>	
Radiation [1]	3.4
CWT [2]	0.2
Supports [3],[4]	2
FPC [5]	4
Instrumentation [6]	2.3
HOM/Pickup [7],[8]	3.9
Tuner [9]	1
Total Static	16.8

Revised estimation using measurements taken during cold tests DQW/SPS – 2017/2018

	2 K bath
Radiation	3.1 W
CWT	0.1 W
Supports	2.1 W
FPC	5.3 W
Instrumentation	2.4 W
HOM	3.2 W
Pickup	0.6 W
Tuner	1.4 W
Total Static	18.1 W

Thermal budget RFD

Thermal budget DQW

Static + dynamic

	NOMINAL			DESIGN CASE			ADDITIONAL (EXCEPTIONAL)		
	Static + Dynamic 3.4 MV (40 kW FPC)			Static + Dynamic 4.1 MV (40 kW FPC)			Static + Dynamic 5 MV (40 kW FPC)		
	2 K bath	10 K intercept	80 K intercept	2 K bath	10 K intercept	80 K intercept	2 K bath	10 K intercept	80 K intercept
Radiation [2] [5]	3.4	-	30	3.4	-	30	3.4	-	30
CWT [6]	6	1	50.6	6	1	50.6	6	1	50.6
Supports [7] [8]	0.4	2.1	8	0.4	2.1	8	0.4	2.1	8
	0.5	0.9	5	0.5	0.9	5	0.5	0.9	5
FPC [9] [10] [11]	4.8	4.6	46.4	4.8	4.6	46.4	4.8	4.6	46.4
VHOM lines [12]	1.4	2.6	13	1.4	2.6	13	1.4	2.6	13
VHOM antennas [13]	0.2	-	-	0.2	-	-	0.3	-	-
HHOM lines [12]	1.4	2.6	13	1.4	2.6	13	1.4	2.6	13
HHOM antennas [13]	0.3	-	-	0.5	-	-	0.7	-	-
Pickup lines [14]	2	-	10.6	2	-	10.6	2	-	10.6
Pickup antennas [13]	0	-	-	0	-	-	0	-	-
Tuner [15]	0.8	-	10.2	0.8	-	10.2	0.8	-	10.2
Instrumentation [2] [16]	2.3	-	10	2.3	-	10	2.3	-	10
He level sensor [17]	0.4	-	0.8	0.4	-	0.8	0.4	-	0.8
Cryo safety device [18]	0.7	-	4.8	0.7	-	4.8	0.7	-	4.8
Beam screen [19]	1.4	-	-	1.4	-	-	1.4	-	-
Beam impedance in cavity [20]	-	-	-	-	-	-	-	-	-
Cavity [21]	14	-	-	20	-	-	50	-	-
	Static + Dynamic			Static + Dynamic			Static + Dynamic		
TOTAL	40	13.8	202.4	46.2	13.8	202.4	76.5	13.8	202.4

Thermal budget report for RFD:

See EDMS 2310389 - Thermal budget RFD cryomodule
Courtesy J.Swieszek – L.Giordanino

Static + dynamic (estimates)

	NOMINAL			DESIGN CASE			ADDITIONAL (EXCEPTIONAL)		
	Static + Dynamic 3.4 MV (40 kW FPC)			Static + Dynamic 4.1 MV (40 kW FPC)			Static + Dynamic 5 MV (40 kW FPC)		
	2 K bath	10 K intercept	80 K intercept	2 K bath	10 K intercept	80 K intercept	2 K bath	10 K intercept	80 K intercept
Radiation	3.4	-	30	3.4	-	30	3.4	-	30
CWT	5.5	1	50.6	5.5	1	50.6	5.5	1	50.6
Supports	0.4	2.1	8	0.4	2.1	8	0.4	2.1	8
	0.6	1.1	6	0.6	1.1	6	0.6	1.1	6
FPC	5.5	5.3	54	5.5	5.3	54	5.5	5.3	54
HOM antennas	-	-	-	-	-	-	-	-	-
HOM lines	4.2	7.8	39	4.2	7.8	39	4.2	7.8	39
HF and Field antennas	-	-	-	-	-	-	-	-	-
Antennas coax lines	4	-	21.2	4	-	21.2	4	-	21.2
Tuner	1	-	12	1	-	12	1	-	12
Instrumentation	2.3	-	10	2.3	-	10	2.3	-	10
He level sensor	0.4	-	0.8	0.4	-	0.8	0.4	-	0.8
Cryo safety device	0.7	-	4.8	0.7	-	4.8	0.7	-	4.8
Beam screen	1.4	-	-	1.4	-	-	1.4	-	-
Beam impedance in cavity	-	-	-	-	-	-	-	-	-
Cavity	14	-	-	20	-	-	50	-	-
	Static + Dynamic			Static + Dynamic			Static + Dynamic		
TOTAL	43.4	17.3	236.4	49.4	17.3	236.4	79.4	17.3	236.4


Thermal budget report for DQW to be updated

Preliminary estimate with margin


Status of drawing packages RFD and DQW



- Cryogenic lines :
 - Drawings fully updated
 - **Control #2 on-going**




- Beam vacuum equipment:
 - All drawing are **released**
 - Ac coating to be decided for extremity chamber



- Outer Vacuum Chamber:
 - All drawing are **released**
 - Correction of fastener reference to be updated on top drawing




- Thermal screen + MLI :
 - **Control 2 on-going**
 - **MLI 3D spec done, to be reviewed**



- Magnetic shield :
 - Modification proposal for the extremity asked by STFC
 - **New version of drawing created – to be discussed**
 - **Minor modification (1 part changed)**






- Cavity support system:
 - Material update for the adjustment sets
 - New design of the blade head to simplify assembly
 - Drawing ready : **end of October 23**



- Internal cryogenic support :
 - All drawing **released** or under control #2
 - **Alternate solution** for the biphas support under evaluation



- Tuner:
 - Improvement for LHC already implemented in CM design for internal parts,
 - Drawing for manufacturing approved **oct 23** for internal part,
 - External actuator further changer needed, target for the design : **end of 23**




- Cryomodule assembly:
 - Regular updates
 - Design freeze step by step





Thank you for your attention

AI use for the design



Remaining open points

- Magnetic shield geometry simplification for assembly improvement (DQW + RFD)



- UHV shielded bellows sequence of assembly (pre-assembled outside of clean room)
(See preliminary report on the tests carried out at CERN)



- Extremity vacuum chamber internal Ac coating
- Correct the OVC fasteners listed in the BOM of the OVCs
- DN100 RF joint to improve the string assembly

Comparison with RFD experience

RFD 2021 (only a summary is shown here, see presentation of 17.11.2021 for detailed explanations) :

*Parts degreased and manually cleaned outside cleanroom ; rinsed and assembled inside cleanroom

Status after rinsing, before assembly :

RF fingers and inside bellow convolutions : ISO 2-3

Bellow outside surface and flanges : ISO 6 with yellow oxide traces

Status after assembly :

Inside RF fingers and bellow convolutions : ISO 6 (really close to ISO 5)

Fixing area with Ag coated screws on both sides (& springs on one side) : ISO 5, it was ISO 8 before a huge effort of cleaning inside cleanroom without rinsing

⇒ **Maintaining sub ISO 4 is not possible due to complex assembly sequence and need of tightening coated fasteners inside the assembly** (between the bellow and the RF finger)

Should not have been accepted for string assembly, but we could not do better with this procedure

DQW 2023 :

*Parts degreased, manually cleaned and assembled outside cleanroom ; whole subassembly rinsed inside cleanroom

After rinsing of the whole subassembly :

Outside surface : ISO 4 (reaches ISO 5 if we carefully check the yellow oxide traces)

Inside surface : ISO 4

Fixing area with springs : ISO 5, without extra blowing or cleaning effort done

Accepted for string assembly !

It requested a strong care in order to dry the subassembly correctly

Around a factor 3 in time saving !

Almost a factor 100 in cleanliness level improvement !



Versus




Dressed cavities comparison



DQW


RFD




Tuner actuation



Tuner double tube



Tuner frame



Beam screen



RF coaxial lines

H-HOM filter
LHCACFHC0322

V-HOM filter
LHCACFHC0322

